

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY URBAN	90% FED/ 10% STATE	90% FED/ 10% STATE	90% FED/ 10% STATE								
				MAINLINE ROADWAY 0004	STRUCTURE SN057-0249 0011	STRUCTURE SN057-0250 0011								
52100520	ANCHOR BOLTS, 1"	EACH	72		48	24								
52100540	ANCHOR BOLTS, 1 1/2"	EACH	24			24								
54213447	END SECTIONS 12"	EACH	2	2										
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1										
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24" *	FOOT	10	10										
58700300	CONCRETE SEALER	SO FT	7,204		629	6,575								
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	248		103	145								
60100060	CONCRETE HEADWALL FOR PIPE DRAINS *	EACH	14	14										
60100945	PIPE DRAINS 12"	FOOT	136	136										
60107600	PIPE UNDERDRAINS 4"	FOOT	3,670	3,670										
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	182	182										
20046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	383		168	215								
60500060	REMOVING INLETS	EACH	2	2										
60600305	CONCRETE CURB (DOWELLED)	FOOT	42	42										
60900515	CONCRETE THRUST BLOCKS	EACH	2	2										
61000120	TYPE E INLET BOX, STANDARD 610001 (SPECIAL)	EACH	2	2										
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	6,387.5	6,387.5										
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	6	6										
* 63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2										
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	6	6										
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6	6										
* 63100217	TRAFFIC BARRIER TERMINAL, TYPE 6B (SPECIAL)	EACH	2	2										
63200310	GUARDRAIL REMOVAL	FOOT	7,072	7,072										
63500105	DELINEATORS	EACH	28	28										
63500120	DELINEATOR REMOVAL	EACH	28	28										
64200105	SHOULDER RUMBLE STRIPS	FOOT	11,520	11,520										
66201120	CONCRETE SHOULDER CURB	FOOT	20	20										
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	600	600										
66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1										
66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1										
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	12	12										

LEGEND:

* SPECIALTY ITEMS

FILE NAME =	USER NAME = keysrb	DESIGNED -	REVISED -
ct:\pwwork\pwwork\keysrb\d0101450\0570530-sh1-500.DGN		DRAWN -	REVISED -
Johnson, Depp & Oulsenberry CONSULTING ENGINEERS Springfield, Illinois	PLOT SCALE = 20,0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 8/19/2010	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	157-THB-2 & 57-7HB-1/BR	MCLEAN	153	5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 70520	

SHEET NO. 3 OF 5