

**PAVED DITCH REMOVAL**

LOCATION	STATION TO	STATION	OFFSET	FOOT
IL CENTRAL RR	9+87.00	10+00.00	RT	13

**AGGREGATE SHOULDERS, TYPE B**

LOCATION	STATION TO	STATION	OFFSET	TON
FR I-55	359+75.00	371+13.00	LT	230
FR I-55	359+75.00	371+13.00	RT	230
FR I-55	374+87.00	384+00.00	LT	185
FR I-55	374+87.00	384+00.00	RT	185
TOTAL				830

**HOT-MIX ASPHALT SHOULDERS, 8"**

LOCATION	STATION TO	STATION	OFFSET	SQ YD
FR I-55	359+75.00	371+13.00	LT	506
FR I-55	359+75.00	371+13.00	RT	506
FR I-55	374+87.00	384+00.00	LT	406
FR I-55	374+87.00	384+00.00	RT	406
TOTAL				1824

**CONCRETE REMOVAL**

LOCATION	STATION TO	STATION	OFFSET	CU YD
FR I-55	370+83.81	370+86.81	LT&RT	6
FR I-55	375+10.20	375+13.20	LT&RT	5
TOTAL				11

**END SECTIONS, 12"**

LOCATION	STATION	OFFSET	EACH
FR I-55	370+98.76	LT	1
FR I-55	371+17.24	RT	1
FR I-55	374+86.44	LT	1
FR I-55	375+02.14	RT	1
TOTAL			4

**PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 12"**

LOCATION	STATION	OFFSET	EACH
FR I-55	373+30.59	24.4' LT	1
FR I-55	375+48.99	90.5' RT	1
TOTAL			2

**PRECAST REINFORCED CONCRETE FLARED END SECTIONS, 36"**

LOCATION	STATION	OFFSET	EACH
FR I-55	373+18.98	74.9' RT	1

**STORM SEWERS, CLASS A, TYPE 1, 12"**

LOCATION	STATION TO	STATION	OFFSET	FOOT
FR I-55	372+05.93	372+95.41	LT&RT	109
FR I-55	373+30.59	373+38.55	LT	8
FR I-55	373+45.59	373+95.37	LT	50
FR I-55	373+95.37	375+48.99	LT&RT	193
TOTAL				360

**STORM SEWERS, CLASS A, TYPE 1, 36"**

LOCATION	STATION TO	STATION	OFFSET	FOOT
FR I-55	372+95.41	373+18.98	RT	29

**STORM SEWER REMOVAL 12"**

LOCATION	STATION TO	STATION	OFFSET	FOOT
FR I-55	372+05.93	373+08.84	LT&RT	117
FR I-55	373+41.74	373+56.79	LT	16
TOTAL				133

**STORM SEWER REMOVAL 15"**

LOCATION	STATION TO	STATION	OFFSET	FOOT
FR I-55	373+38.55	373+56.79	LT	24

**STORM SEWER REMOVAL 24"**

LOCATION	STATION TO	STATION	OFFSET	FOOT
FR I-55	373+45.59	373+56.79	LT	17

**STORM SEWERS JACKED IN PLACE, CLASS B 36"**

LOCATION	STATION TO	STATION	OFFSET	FOOT
FR I-55	372+95.41	373+38.55	LT&RT	93

**CONCRETE HEADWALL FOR PIPE DRAINS**

LOCATION	STATION	OFFSET	EACH
FR I-55	371+26.64	LT	1
FR I-55	371+59.36	RT	1
FR I-55	374+40.72	LT	1
FR I-55	374+73.28	RT	1
TOTAL			4

**PIPE DRAINS 12"**

LOCATION	STATION	OFFSET	FOOT
FR I-55	370+98.76	LT	6
FR I-55	371+17.24	RT	6
FR I-55	374+82.76	LT	12
FR I-55	375+01.24	RT	6
TOTAL			30

**MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID**

LOCATION	STATION	OFFSET	EACH
FR I-55	372+05.93	4.6' LT	1
FR I-55	373+95.37	26.1' LT	1
TOTAL			2

**MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, OPEN LID**

LOCATION	STATION	OFFSET	EACH
FR I-55	373+38.55	23.7' LT	1

**MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID**

LOCATION	STATION	OFFSET	EACH
FR I-55	373+45.59	26.1' LT	1

**MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID**

LOCATION	STATION	OFFSET	EACH
FR I-55	372+95.41	58.1' RT	1

**REMOVING MANHOLES**

LOCATION	STATION	OFFSET	EACH
FR I-55	373+56.79	13.9' LT	1

**TYPE B INLET BOX, STANDARD 609001**

LOCATION	STATION	OFFSET	EACH
FR I-55	370+98.76	LT	1
FR I-55	371+17.24	RT	1
FR I-55	374+82.76	LT	1
FR I-55	375+01.24	RT	1
TOTAL			4

**STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS**

LOCATION	STATION TO	STATION	OFFSET	FOOT
FR I-55	362+56.59	370+94.09	RT	837.5
FR I-55	370+00.61	370+75.61	LT	75.0
FR I-55	375+05.91	376+93.41	LT	187.5
FR I-55	375+24.39	381+61.89	RT	637.5
TOTAL				1737.5

**TRAFFIC BARRIER TERMINAL, TYPE 6**

LOCATION	STATION TO	STATION	OFFSET	EACH
FR I-55	370+75.61	371+18.76	LT	1
FR I-55	370+94.09	371+37.24	RT	1
FR I-55	374+62.76	375+05.91	LT	1
FR I-55	374+81.24	375+24.39	RT	1
TOTAL				4

**TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)**

LOCATION	STATION TO	STATION	OFFSET	EACH
FR I-55	362+06.59	362+56.59	RT	1
FR I-55	369+50.61	370+00.61	LT	1
FR I-55	376+93.41	377+43.41	LT	1
FR I-55	381+61.89	382+11.89	RT	1
TOTAL				4

**GUARDRAIL REMOVAL**

LOCATION	STATION TO	STATION	OFFSET	FOOT
FR I-55	366+98.29	370+76.16	RT	378
FR I-55	369+23.25	370+75.99	LT	153
FR I-55	375+16.12	376+74.01	LT	158
FR I-55	375+21.19	378+98.89	RT	378
TOTAL				1067

**WOVEN WIRE FENCE, 4'**

LOCATION	STATION TO	STATION	OFFSET	FOOT
FR I-55	367+00.00	371+29.00	LT	429
FR I-55	374+43.00	379+00.00	LT	457
TOTAL				886

**WOVEN WIRE FENCE REMOVAL**

LOCATION	STATION TO	STATION	OFFSET	FOOT
FR I-55	367+00.00	370+79.00	LT	379
FR I-55	375+18.00	379+00.00	LT	382
TOTAL				761

**PAINT PAVEMENT MARKING - LINE 5"**

LOCATION	STATION TO	STATION	OFFSET	FOOT
FR I-55	359+75.00	384+00.00	LT&RT	8169

**RAISED REFLECTIVE PAVEMENT MARKER**

LOCATION	STATION TO	STATION	OFFSET	TWO WAY AMBER
FR I-55	359+75.00	383+75.00	-	31

**GUARDRAIL MARKERS & BARRIER WALL MARKERS**

LOCATION	STATION TO	STATION	OFFSET	GUARDRAIL MARKERS	BARRIER WALL MARKERS
FR I-55	BEGIN STA.	362+06.59	RT		
	END STA.	382+11.89	RT	21	4
FR I-55	BEGIN STA.	369+50.61	LT		
	END STA.	377+43.41	LT	5	4
TOTAL				26	8

**TERMINAL MARKER - DIRECT APPLIED**

LOCATION	STATION	OFFSET	EACH
FR I-55	362+06.59	RT	1
FR I-55	369+50.61	LT	1
FR I-55	377+43.41	LT	1
FR I-55	382+11.89	RT	1
TOTAL			4

**PIPE DRAIN REMOVAL**

LOCATION	STATION TO	STATION	OFFSET	FOOT
FR I-55	370+85.00	370+85.00	RT	50
FR I-55	375+12.00	375+64.00	RT	77
TOTAL				127

**STORM SEWER TO BE FILLED**

LOCATION	STATION TO	STATION	CU YD
FR I-55	373+28.96	373+56.79	8
FR I-55	373+56.79	375+48.99	6
TOTAL			14

FILE NAME =	USER NAME = laughl1n1	DESIGNED - CWG	REVISED -
ei:\pw_work\p1dot\laughl1n1\02232385\0672692-sh1-schedule.dgn		DRAWN - BWC	REVISED -
	PLOT SCALE = 40.0000' / in.	CHECKED - RMD	REVISED -
	PLOT DATE = Aug-23-2010 11:26:44AM	DATE - 02/09/09	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 2 OF 2 SHEETS STA. TO STA.

F.A.U. RE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8159	110X-3VB-4	SANGAMON	78	10
CONTRACT NO. 72692				
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		