

AGGREGATE SHOULDERS, TYPE B

48101200

STATION TO STATION	SIDE	WIDTH	TON
FAP 713 (IL 101)			
554+11.6	555+65.1	LT	4
554+11.6	554+74.3	RT	4
555+08.3	555+18.2	RT	4
563+10.9	564+55.0	RT	4
563+95.3	564+55.0	LT	4
TOTAL			16.3
USE			17

AGGREGATE SHOULDERS, TYPE B (SPECIAL)

X4811300

STATION TO STATION	SIDE	WIDTH	TON
FAP 713 (IL 101)			
555+18.2	556+58.3	RT	4
555+65.1	556+58.3	LT	4
562+17.8	563+95.3	LT	4
562+17.8	563+10.9	RT	4
TOTAL			19.1
USE			20

HOT-MIX ASPHALT SHOULDERS

48203100

STATION TO STATION	SIDE	SURFACE WIDTH	SQ YD	TON
FAP 713 (IL 101)				
554+00.9	556+37.3	LT	4	105.0
554+00.9	556+37.3	RT	4	105.0
562+38.8	564+55.0	LT	4	96.1
562+38.8	564+55.0	RT	4	96.1
TOTAL				33.8
USE				34

PIPE CULVERT REMOVAL

50105220

STATION	SIDE	DESCRIPTION	FOOT
FAP 713 (IL 101)			
556+49.5	RT	15" CMP	17
TOTAL			17

PIPE CULVERTS, CLASS D TYPE 1  
EQUIVALENT ROUND-SIZE 24"

54205479

STATION	SIDE	OFFSET	FOOT
FAP 713 (IL 101)			
554+91.3	RT	29.9	40
TOTAL			40

METAL END SECTIONS  
EQUIVALENT ROUND-SIZE 24"

54215769

STATION	SIDE	OFFSET	EACH
FAP 713 (IL 101)			
554+91.3	RT	29.9	2
TOTAL			2

CLASS SI CONCRETE (OUTLET)

60600095

STATION TO STATION	SIDE	CU YD
FAP 713 (IL 101)		
553+75.0	553+99.0	LT
553+75.0	553+99.0	RT
TOTAL		6.02
USE		6.1

GUARDRAIL SCHEDULE

63200310 63000001 63100167 63100085 78200410 78201000

STATION TO STATION	SIDE	GUARDRAIL REMOVAL	SPBGR TYPE A 6' POSTS	TRAFFIC BARRIER TERMINALS		GUARDRAIL MARKERS TYPE A	TERMINAL MARKERS DIRECT APPLIED
				TYPE 1 SPECIAL (TANGENT)	TYPE 6		
				FOOT		EACH	
FAP 713 (IL 101)							
555+18.23	556+60.75	RT	90	46.87	1	1	4
555+65.10	556+60.75	LT	90		1	1	4
562+15.25	563+10.90	RT	90		1	1	4
562+15.25	563+95.28	LT	90	84.38	1	1	4
TOTALS			360	131.25	4	4	16

TEMPORARY CONCRETE BARRIER

70400100

STATION TO STATION	SIDE	FOOT
FAP 713 (IL 101)		
555+26.6	563+49.4	LT & RT
TOTAL		823.3

RELOCATE TEMPORARY CONCRETE BARRIER

70400200

STATION TO STATION	SIDE	FOOT
FAP 713 (IL 101)		
555+26.6	563+49.4	LT & RT
TOTAL		823.3

PAINT PAVEMENT MARKING - LINE 5"

78001120

STATION TO STATION	SIDE	DESCRIPTION	WHITE	YELLOW
			FOOT	
FAP 713 (IL 101)				
553+75.0	564+55.0	CL	NO-PASSING	1080.0
553+75.0	564+55.0	CL	SKIP-DASH	270.0
553+75.0	564+55.0	LT	EDGE LINE	1080.0
553+75.0	564+55.0	RT	EDGE LINE	1080.0
TOTALS			2160.0	1350.0
USE			3510	

PAVEMENT MARKING REMOVAL

78300100

STATION TO STATION	SIDE	DESCRIPTION	SQ FT
FAP 713 (IL 101)			
553+24.0	555+10.6	CL	SKIP-DASH
553+24.0	555+10.6	CL	NO-PASSING
563+55.4	565+20.0	CL	SKIP-DASH
563+55.4	565+20.0	CL	NO-PASSING
555+10.6	563+55.4	RT	EDGE LINE
555+04.5	563+59.5	LT	EDGE LINE
TOTAL			1075.5
USE			1076

BRIDGE APPROACH DRAINS

54215547 60100935 60900115

LOCATION	SIDE	EACH	FT	EACH
FAP 713 (IL 101)				
562+27.75	LT	1	19.2	1
	RT	1	19.2	1
TOTAL		2	38.4	2
USE		2	40	2

IMPACT ATTENUATORS, TEMPORARY  
(FULLY REDIRECTIVE, NARROW)  
TEST LEVEL 3

Z0030260

STATION	SIDE	EACH
FAP 713 (IL 101)		
555+26.6	LT	1
563+49.4	LT	1
TOTAL		2

IMPACT ATTENUATORS, RELOCATE  
(FULLY REDIRECTIVE)  
TEST LEVEL 3

Z0030330

STATION	SIDE	EACH
FAP 713 (IL 101)		
555+26.6	RT	1
563+49.4	RT	1
TOTAL		2