

SUMMARY OF QUANTITIES			80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION AND SAFETY TYPE CODE			
CODE NO.	ITEM	SP. PROV.	UNIT	0005 ROADWAY	0011 STRUCTURE		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)		UNIT	96	96		
20200100	EARTH EXCAVATION		CU YD	200	200		
20200500	EARTH EXCAVATION (WIDENING)	*	CU YD	65	65		
20400800	FURNISHED EXCAVATION		CU YD	5	5		
25000210	SEEDING, CLASS 2A		ACRE	0.25	0.25		
25000400	NITROGEN FERTILIZER NUTRIENT		POUND	23	23		
25000500	PHOSPHORUS FERTILIZER NUTRIENT		POUND	23	23		
25000600	POTASSIUM FERTILIZER NUTRIENT		POUND	23	23		
25000700	AGRICULTURAL GROUND LIMESTONE		TON	1	1		
25100115	MULCH, METHOD 2		ACRE	0.25	0.25		
25100630	EROSION CONTROL BLANKET		SQ YD	948	948		
28000250	TEMPORARY EROSION CONTROL SEEDING		POUND	50	50		
28000400	PERIMETER EROSION BARRIER		FOOT	1421	1421		
28000500	INLET AND PIPE PROTECTION		EACH	1	1		
28100109	STONE RIPRAP, CLASS A5	*	SO YD	520	69	451	
28100707	STONE DUMPED RIPRAP, CLASS A4	*	SO YD	355	355		
28100709	STONE DUMPED RIPRAP, CLASS A5	*	SO YD	1293		1293	
28200200	FILTER FABRIC		SQ YD	2168	424	1744	
35101400	AGGREGATE BASE COURSE, TYPE B		TON	16	16		
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	*	SO YD	507	507		
40600200	BITUMINOUS MATERIALS (PRIME COAT)		TON	0.5	0.5		
40600300	AGGREGATE (PRIME COAT)		TON	3	3		
40600990	TEMPORARY RAMP	*	SO YD	135	135		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50		TON	107	107		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING		TON	10	10		
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)		SO YD	46	46		
44000100	PAVEMENT REMOVAL	*	SO YD	372	372		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"		SO YD	1673	1673		
44000400	GUTTER REMOVAL		FOOT	648	648		
48101200	AGGREGATE SHOULDERS, TYPE B		TON	17	17		

FILE NAME :	USER NAME :	DESIGNED :	REVISED :
ea\pwork\p\idot\laughlin\1\0233251\06	2403-ahc-500.dgn		
PLOT SCALE :	CHECKED :	REVISED :	REVISED :
100.0000 / in.			
PLOT DATE :	DATE :	REVISED :	REVISED :
Aug-17-2010 01:18:07PM			

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 1 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
713	1208-3	SCHUYLER	75	3
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 72A03	