

SUMMARY OF QUANTITIES

CODE NO.	ITEM	SP. PROV.	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION AND SAFETY TYPE CODE			
					0005 ROADWAY	0011 STRUCTURE		
48203100	HOT-MIX ASPHALT SHOULDERS		TON	34	34			
50100100	REMOVAL OF EXISTING STRUCTURES		EACH	1		1		
50105220	PIPE CULVERT REMOVAL	*	FOOT	17	17			
50200100	STRUCTURE EXCAVATION		CU YD	341		341		
50300100	FLOOR DRAINS		EACH	26		26		
50300225	CONCRETE STRUCTURES		CU YD	290.6		290.6		
50300255	CONCRETE SUPERSTRUCTURE		CU YD	719.2		719.2		
50300260	BRIDGE DECK GROOVING		SQ YD	1965		1965		
50300280	CONCRETE ENCASEMENT		CU YD	11.2		11.2		
50300300	PROTECTIVE COAT		SQ YD	2569		2569		
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL		L SUM	1		1		
50500505	STUD SHEAR CONNECTORS		EACH	6588		6588		
50800105	REINFORCEMENT BARS		POUND	4940		4940		
50800205	REINFORCEMENT BARS, EPOXY COATED		POUND	251,440		251,440		
50800515	BAR SPLICERS		EACH	2356		2356		
51201600	FURNISHING STEEL PILES HP12X53		FOOT	900		900		
51202305	DRIVING PILES		FOOT	900		900		
51203600	TEST PILE STEEL HP12X53		EACH	2		2		
51204650	PILE SHOES		EACH	32		32		
51500100	NAME PLATES		EACH	1		1		
* 51603000	DRILLED SHAFT IN SOIL		CU YD	135.1		135.1		
* 51604000	DRILLED SHAFT IN ROCK		CU YD	28.8		28.8		
52000220	FINGER PLATE EXPANSION JOINT, 6"		FOOT	64		64		
52000600	FABRIC REINFORCED ELASTOMERIC TROUGH		FOOT	76		76		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I		EACH	18		18		
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II		EACH	18		18		
52100530	ANCHOR BOLTS, 1 1/4"		EACH	48		48		
52100510	ANCHOR BOLTS 3/4"		EACH	24		24		
52100520	ANCHOR BOLTS, 1"		EACH	12		12		
54205479	PIPE CULVERTS, CLASS D, TYPE 1 EQUIVALENT ROUND-SIZE 24"		FOOT	40	40			
54215547	METAL END SECTIONS 12"	*	EACH	2	2			
54215769	METAL END SECTIONS, EQUIVALENT ROUND-SIZE 24"	*	EACH	2	2			

* Specialty Items Rev.

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED - 8/18/10	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pwwork\p\ridot\laughlinr1\0233251\06	2\03-shr-500.dgn	DRAWN -	REVISED -					713	120B-3	SCHUYLER	75	4
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -		SCALE: NONE	SHEET NO. 20F	4SHEETS	STA. TO STA.	CONTRACT NO. 72A03			
	PLOT DATE = Aug-19-2010 08:51:39AM	DATE -	REVISED -		FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT					