

SUMMARY OF QUANTITIES				80% FED. 20% STATE TOTAL QUANTITIES		CONSTRUCTION AND SAFETY TYPE CODE						
CODE NO.	ITEM	SP. PROV.	UNIT			0005 ROADWAY	0011 STRUCTURE					
58700300	CONCRETE SEALER		SO FT		780		780					
59100100	GEOCOMPOSITE WALL DRAIN		SO YD		48		48					
60100060	CONCRETE HEADWALL FOR PIPE DRAINS		EACH		4	4						
60100935	PIPE DRAINS 10"		FOOT		40	40						
20046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	•	FOOT		151		151					
60500060	REMOVING INLETS		EACH		1	1						
60600095	CLASS SI CONCRETE (OUTLET)		CU YD		6.1	6.1						
60900115	TYPE B INLET BOX, STANDARD 609001		EACH		2	2						
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS		FOOT		131.25	131.25						
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6		EACH		4	4						
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	•	EACH		4	4						
63200310	GUARDRAIL REMOVAL		FOOT		360	360						
67000400	ENGINEER'S FIELD OFFICE, TYPE A		CAL MO		17	17						
67100100	MOBILIZATION		L SUM		1	1						
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	•	L SUM		1	1						
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	•	L SUM		1	1						
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	•	L SUM		1	1						
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	•	EACH		1	1						
70103815	TRAFFIC CONTROL SURVEILLANCE		CAL DA		10	10						
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	•	EACH		1	1						
70300100	SHORT-TERM PAVEMENT MARKING		FOOT		200	200						
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"		FOOT		7020	7020						
70301000	WORK ZONE PAVEMENT MARKING REMOVAL		SO FT		2444	2444						
70400100	TEMPORARY CONCRETE BARRIER		FOOT		823.3	823.3						
70400200	RELOCATE TEMPORARY CONCRETE BARRIER		FOOT		823.3	823.3						
* 78001120	PAINT PAVEMENT MARKING - LINE 5"		FOOT		3510	3510						
* 78200420	GUARDRAIL MARKERS, TYPE B	•	EACH		16	16						
* 78201000	TERMINAL MARKER - DIRECT APPLIED	•	EACH		4	4						
78300100	PAVEMENT MARKING REMOVAL		SO FT		1076	1076						
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	•	CU YD		94		94					

*Specialty Items

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED - 8/18/10	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ci:\pwr\work\pwr\dot\laughlinr1\d0233251\06	2A03-shr-500.dgn	DRAWN -	REVISED -					713	120B-3	SCHUYLER	75	5	
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -					CONTRACT NO. 72A03					
	PLOT DATE = Aug-19-2010 08:51:48AM	DATE -	REVISED -					FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

SCALE: NONE SHEET NO. 30F 4SHEETS STA. TO STA.