

PAVEMENT MARKING SCHEDULE																
LOCATION			TEMPORARY PAVEMENT MARKING				THERMOPLASTIC PAVEMENT MARKING				PAVEMENT MARKING REMOVAL	SHORT-TERM PAVEMENT MARKING (2 LIFTS)	SHORT-TERM PAVEMENT MARKING (2 LIFTS)	WORKZONE PAVEMENT MARKING REMOVAL		
			LINE 4" SOLID (WHITE)	LINE 4" SOLID (YELLOW)	LINE 4" SKIP DASH (WHITE)	LINE 8" SOLID (WHITE)	LINE 4" SOLID (WHITE)	LINE 4" SOLID (YELLOW)	LINE 4" SKIP DASH (WHITE)	LINE 8" SOLID (WHITE)						
STA	TO	STA	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	SQ FT			
IL 255 - NORTHBOUND																
1598+00	TO	1615+52	1752	1752	878	1752	1752	878		1445	478	135	102			
1619+35	TO	1627+03	768	768	384	768	768	384		834	208	58	45			
1629+17	TO	1673+81	3801	4484	2232	507	3801	4484	2232	3738	1153	343	249			
1673+81	TO	1690+36	1288	1855	414	367	1288	1855	414	367	1384	378	127			
1692+17	TO	1746+21	4952	5404	1351	452	4952	5404	1351	452	4168	1228	418			
IL 255 - SOUTHBOUND																
1622+41	TO	1627+24	483	483	242	483	483	242		398	132	37	28			
1629+37	TO	1675+81	3821	4644	2322	360	3821	4644	2322	3834	1201	357	260			
1675+81	TO	1690+81	960	1500	375	540	960	1500	375	540	1297	243	60			
1692+64	TO	1745+60	4885	5298	1324	411	4885	5298	1324	411	4072	1204	407			
SOUTHBOUND COLLECTOR																
1594+00	TO	1615+66	1803	2188		350	1803	2188		1478	355	167	87			
1619+32	TO	1627+36	717	804	201	87	717	804	201	87	827	183	82			
1629+55	TO	1658+27	2166	2148		733	2166	2148		733	1915	527	165			
RAMP 3																
338+00	TO	354+05	1805	1245		360	1805	1245		1182	292	123	69			
RAMP A																
107+60	TO	122+63	1138	1503		387	1138	1503		1117	273	118	65			
RAMP B																
201+60	TO	227+73	2813	2180		453	2813	2180		1870	475	201	113			
RAMP C																
374+30	TO	397+61	2381	1820		411	2381	1820		1579	424	156	97			
RAMP D																
401+73	TO	420+79	1808	1384		542	1808	1384		1442	347	147	82			
SUB TOTAL			38887	38978	9720	5940	38887	38978	9720	5940	32158	9088	3134	2039		
TOTAL			85383		5940		85383		5940		32158		12232		2039	

MICRO-SURFACING TAPER SCHEDULE			
STATION	WIDTH	LENGTH	MICRO SURFACING SINGLE PASS TYPE II
IL 255 - NB	FOOT	FOOT	SQ YD
1598+00	38	1	2
1615+52	38	1	2
1619+35	51	1	3
1627+03	38	1	2
1629+17	38	1	2
1690+36	26	1	1
1692+17	26	1	1
1746+21	26	1	1
IL 255 - SB			
1622+41	38	1	2
1627+24	38	1	2
1629+37	38	1	2
1690+81	26	1	1
1692+64	26	1	1
1795+60	26	1	1
SB COLLECTOR			
1594+00	18	1	1
1615+66	30	1	2
1619+32	30	1	2
1627+36	18	1	1
1629+55	18	1	1
RAMP 3			
354+05	18	1	1
RAMP A			
122+63	18	1	1
RAMP B			
201+60	20	1	1
RAMP C			
397+61	18	1	1
RAMP D			
401+73	18	1	1
TOTALS			38

PARTIAL DEPTH PATCHING						
LOCATION	LANE	LENGTH	WIDTH	BITUMINOUS MATERIALS (PRIME COAT)	PARTIAL DEPTH REM 3 INCH	PARTIAL DEPTH PATCHING
IL 255 NB						
1598 + 00	INSIDE	20.0	12.0	0.008	28.7	4.5
1598 + 00	MIDDLE	20.0	12.0	0.008	28.7	4.5
1598 + 00	OUTSIDE	20.0	12.0	0.008	28.7	4.5
1603 + 00	OUTSIDE	80.0	12.0	0.025	80.0	13.4
1627 + 00	OUTSIDE	4.0	12.0	0.002	5.3	0.9
1629 + 10	MIDDLE	4.0	12.0	0.002	5.3	0.9
1629 + 10	OUTSIDE	4.0	12.0	0.002	5.3	0.9
1635 + 28	MIDDLE	10.0	2.0	0.001	2.2	0.4
1658 + 00	MIDDLE	20.0	4.0	0.003	8.9	1.5
1712 + 00	EP/RAMP	800.0	2.0	0.056	177.8	29.9
1736 + 50	OUTSIDE	20.0	4.0	0.003	8.9	1.5
IL 255 SB						
1622 + 40	INSIDE	4.0	12.0	0.002	5.3	0.9
1622 + 40	MIDDLE	4.0	12.0	0.002	5.3	0.9
1622 + 40	OUTSIDE	4.0	12.0	0.002	5.3	0.9
1628 + 20	INSIDE	4.0	12.0	0.002	5.3	0.9
1628 + 20	MIDDLE	4.0	12.0	0.002	5.3	0.9
1628 + 20	OUTSIDE	4.0	12.0	0.002	5.3	0.9
1658 + 00	EP/RAMP	300.0	2.0	0.021	86.7	11.2
1678 + 00	EP/GORE	360.0	2.0	0.025	80.0	13.4
1693 + 70	OUTSIDE	4.0	12.0	0.002	5.3	0.9
1710 + 30	OUTSIDE	80.0	12.0	0.033	108.7	17.9
1718 + 00	EP/RAMP	300.0	2.0	0.021	86.7	11.2
1745 + 30	INSIDE	4.0	12.0	0.002	5.3	0.9
1745 + 30	OUTSIDE	4.0	12.0	0.002	5.3	0.9
IL 255 SB - CD						
1615 + 80	OUTSIDE	4.0	12.0	0.002	5.3	0.9
SUBTOTAL:				0.234	747.1	125.5
ANTICIPATED FAILURES (15%):				0.035	112.1	18.8
TOTAL:				0.3	859	144

MICRO-SURFACING SCHEDULE			
STATION	MICRO-SURFACING SINGLE PASS TYPE II		
	SQ YD		
IL 255 - NORTHBOUND			
1598+00	TO	1615+52	7397
1615+52	TO	1619+35	BRIDGE OMISSION
1619+35	TO	1625+52	2722
1625+52	TO	1627+03	638
1627+03	TO	1629+17	BRIDGE OMISSION
1629+17	TO	1672+60	18337
1672+60	TO	1675+44	1073
1675+44	TO	1680+84	1680
1680+84	TO	1690+36	2750
1690+36	TO	1692+17	BRIDGE OMISSION
1692+17	TO	1746+21	15612
IL 255 - SOUTHBOUND			
1622+41	TO	1627+24	2039
1627+24	TO	1629+37	BRIDGE OMISSION
1629+37	TO	1670+95	17556
1670+95	TO	1675+81	1728
1675+81	TO	1690+81	4333
1690+81	TO	1692+64	BRIDGE OMISSION
1692+64	TO	1745+60	15300
SOUTHBOUND COLLECTOR			
1594+00	TO	1608+21	2842
1608+21	TO	1611+20	797
1611+20	TO	1615+66	1487
1615+66	TO	1619+32	BRIDGE OMISSION
1619+32	TO	1622+13	1093
1622+13	TO	1627+36	1046
1627+36	TO	1629+55	BRIDGE OMISSION
1629+55	TO	1654+16	4922
1654+16	TO	1658+27	411
RAMP 3			
332+89	TO	338+00	511
338+00	TO	354+05	3210
RAMP A			
107+60	TO	108+80	120
108+80	TO	118+30	1900
118+30	TO	122+63	1058
RAMP B			
201+60	TO	219+78	3838
219+78	TO	227+73	795
RAMP C			
375+70	TO	377+35	165
377+35	TO	392+28	2986
392+28	TO	397+61	1303
RAMP D			
401+73	TO	420+79	3812
TOTALS			123461

RAISED PAVEMENT MARKERS				
LOCATION		RAISED REFLECTOR PAVEMENT MARKER ONE WAY CRYSTAL	RAISED REFLECTOR PAVEMENT MARKER REMOVAL	
STA	TO	(EACH)	(EACH)	
IL 255				
1598+00	TO	1610+00	80	80
1610+00	TO	1625+00	88	88
1625+00	TO	1640+00	128	128
1640+00	TO	1655+00	150	150
1655+00	TO	1670+00	148	148
1670+00	TO	1685+00	100	100
1685+00	TO	1700+00	82	82
1700+00	TO	1715+00	76	76
1715+00	TO	1730+00	78	78
1730+00	TO	1745+00	76	76
1745+00	TO	1747+00	2	2
SOUTHBOUND COLLECTOR				
1611+00	TO	1611+60	7	7
1651+00	TO	1658+25	37	37
RAMP A				
107+60	TO	112+40	25	25
RAMP C				
374+30	TO	381+40	35	35
TOTAL:			1048	1048

CLASS A PAVEMENT PATCHING 10 INCH SCHEDULE							
LOCATION	LANE	LENGTH	LANE WIDTH	CLASS A PATCH TYPE III	PATCHING REINF.	TIE BARS 3/4 INCH	SAWCUT
		(FT)	(FT)	(SQ YD)	(SQ YD)	(EACH)	(FT)
SB 255 - CD							
1594 + 0	CD	23.0	8.0	20.4	20.4	11	78.0
1594 + 23	CD	23.0	8.0	20.4	20.4	11	78.0
SUBTOTAL:				40.9	40.9	22.0	156.0
ANTICIPATED FAILURES (15%):				6.1	17.0	3.0	23.4
TOTAL:				47	58	25	179

FILE NAME =	USER NAME = burmsdeam	DESIGNED -	REVISED -
c:\pwork\pndot\burmsdeam\8218188\4876e00-shr-plans.dgn	76e00-shr-plans.dgn	DRAWN -	REVISED -
PLOT SCALE = 1/8" = 1' / IN.		CHECKED -	REVISED -
PLOT DATE = 10/19/2010		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
300	60-9RS	MADISON	13	6
CONTRACT NO. 76E00			FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT	

Rev. Sheet 10-19-10