

SUMMARY OF QUANTITIES				90% FED, 10% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODES	
				0003	0010
44004250	PAVED SHOULDER REMOVAL	SQ YD	3,237	3,237	
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	177	177	
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	52	52	
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	108	108	
44201294	CLASS B PATCH - EXPANSION JOINT	FOOT	312	312	
44213100	PAVEMENT FABRIC	SQ YD	160	160	
44213200	SAW CUTS	FOOT	1,358	1,358	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	279	279	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1,250	1,250	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2		2
50157300	PROTECTIVE SHIELD	SQ YD	640		640
50200100	STRUCTURE EXCAVATION	CU YD	163		163
* 50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	618		618
50300100	FLOOR DRAINS	EACH	6		6
50300225	CONCRETE STRUCTURES	CU YD	2,035.0		2,035.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	836.6		836.6
50300260	BRIDGE DECK GROOVING	SQ YD	4,556	1,828	2,728
50300265	SEAL COAT CONCRETE	CU YD	83.6		83.6

SUMMARY OF QUANTITIES				90% FED, 10% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODES	
				0003	0010
50300280	CONCRETE ENCASEMENT	CU YD	24.4		24.4
50300300	PROTECTIVE COAT	SQ YD	3,268		3,268
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	14,820		14,820
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	430,050		430,050
50800515	BAR SPLICERS	EACH	1,846		1,846
51100100	SLOPE WALL 4 INCH	SQ YD	283		283
Z0065704	BITUMINOUS COATED AGGREGATE SLOPEWALL 6"	SQ YD	2,612		2,612
51201600	FURNISHING STEEL PILES HP12X53	FOOT	2,871		2,871
51202305	DRIVING PILES	FOOT	2,871		2,871
51203600	TEST PILE STEEL HP12X53	EACH	4		4
51204650	PILE SHOES	EACH	70		70
51500100	NAME PLATES	EACH	2		2
52000030	PREFORMED JOINT SEAL 2 1/2"	FOOT	214.0		214.0
52000110	PREFORMED JOINT STRIP SEAL	FOOT	374.0		374.0
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	40		40
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	20		20
52100520	ANCHOR BOLTS, 1"	EACH	80		80

* SPECIALTY ITEM

FILE NAME =	USER NAME = moisiegraser	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES I-57 OVER UNION PACIFIC RAILROAD		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
h:\p\25866p2\Technical_Production\Civil\Microstation\Sec283\B1\SoF0283yb.dgn		DRAWN -	REVISED -		SCALE:	SHEET NO. 2 OF 4 SHEETS	STA. TO STA.	57	(28-3-I)VB-1	FRANKLIN	98	5
		CHECKED -	REVISED -									
		DATE -	REVISED -					FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		