

SUMMARY OF QUANTITIES

SPECIALTY ITEM	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
					80% FEDERAL 20% STATE		NP 100% STATE
					ROADWAY 0005 RURAL	BRIDGE 0011 RURAL	ROADWAY 0005 RURAL
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	59	59		
	20200100	EARTH EXCAVATION	CU YD	1,376	1,376		
	20400800	FURNISHED EXCAVATION	CU YD	862	862		
	X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	200		200	
	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	8,470	8,470		
	21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	50	50		
S	25000210	SEEDING, CLASS 2A	ACRE	1.25	1.25		
S	25000310	SEEDING, CLASS 4	ACRE	0.5	0.5		
	25000750	MOWING	ACRE	1.25		1.25	
S	25100630	EROSION CONTROL BLANKET	SQ YD	8,470	8,470		
S	25100900	TURF REINFORCEMENT MAT	SQ YD	80	80		
S	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	714	714		
S	28000305	TEMPORARY DITCH CHECKS	FOOT	240	240		
	28000400	PERIMETER EROSION BARRIER	FOOT	2,762	2,762		
	28100109	STONE RIPRAP, CLASS A5	SQ YD	961		961	
	28200200	FILTER FABRIC	SQ YD	961		961	
	31100100	SUB BASE GRANULAR MATERIAL, TYPE A	TON	2,741	2,741		
	35101400	AGGREGATE BASE COURSE, TYPE B	TON	397	397		
	35600717	HOT-MIX ASPHALT BASE COURSE WIDENING, 10 1/4"	SQ YD	139	139		
	40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6	6		
	40600300	AGGREGATE (PRIME COAT)	TON	22	22		
	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	295	295		
	40600990	TEMPORARY RAMP	SQ YD	79	79		
	40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,002	1,002		
	40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	264	264		
	40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	367	367		
	42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	56	56		
	44000100	PAVEMENT REMOVAL	SQ YD	232	232		
	Z0004552	APPROACH SLAB REMOVAL	SQ YD	223	223		
	44004250	PAVED SHOULDER REMOVAL	SQ YD	483	483		
	Z0004638	PAVEMENT BREAKING	SQ YD	1,390	1,390		
	48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	76	76		

FILE NAME = F:\CBBEL WEST Projects\2009\12\4182_W09_IL48\Civil\Drawings\20284854-01-5001.dgn

WILLS BURKE KELSEY ASSOCIATES LTD.
 118 West Main Street, Suite 201
 St. Charles, Illinois 60174
 (630) 443-7755

USER NAME = #USER#	DESIGNED -	REVISED -
PLOT SCALE =	DRAWN -	REVISED -
PLOT DATE = 8/2/2010	CHECKED -	REVISED -
	DATE - 8/6/10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE:	SHEET NO. 3 OF 90 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
646	BBR-1	WHITESIDE	90	3
CONTRACT NO. 84854				
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				