

# SCHEDULE OF QUANTITIES

**70300100 SHORT-TERM PAVEMENT MARKING**

FOOT	LOCATION	REMARKS
277	LT./RT. STA. 935+23.00 TO 951+70.00	STAGE 3 - SINGLE 4" WHITE
<b>277</b>	<b>TOTAL</b>	

**70300220 TEMPORARY PAVEMENT MARKING - LINE 4"**

FOOT	LOCATION	REMARKS
<b>STAGE 1</b>		
402	LT./RT. STA. 934+99.00 TO 937+00.00	SINGLE EDGE LINE - WHITE
1,200	LT./RT. STA. 937+00.00 TO 943+00.00	SINGLE EDGE LINE - WHITE
1,200	LT./RT. STA. 943+00.00 TO 949+00.00	SINGLE EDGE LINE - WHITE
540	LT./RT. STA. 949+00.00 TO 951+70.00	SINGLE EDGE LINE - WHITE
<b>STAGE 2</b>		
402	LT./RT. STA. 934+99.00 TO 937+00.00	SINGLE EDGE LINE - WHITE
1,200	LT./RT. STA. 937+00.00 TO 943+00.00	SINGLE EDGE LINE - WHITE
1,200	LT./RT. STA. 943+00.00 TO 949+00.00	SINGLE EDGE LINE - WHITE
540	LT./RT. STA. 949+00.00 TO 951+70.00	SINGLE EDGE LINE - WHITE
<b>6,684</b>	<b>TOTAL</b>	

**70300280 TEMPORARY PAVEMENT MARKING - LINE 24"**

FOOT	LOCATION	REMARKS
<b>STAGE 1 &amp; 2</b>		
12	LT./RT. STA. 935+11.00	STAGE 1- STOP BAR -WHITE
12	LT./RT. STA. 951+70.00	STAGE 1- STOP BAR -WHITE
<b>24</b>	<b>TOTAL</b>	

**70301000 WORK ZONE PAVEMENT MARKING REMOVAL**

SQ FT	LOCATION	REMARKS
<b>STAGE 1</b>		
161	LT./RT. STA. 934+99.00 TO 937+00.00	MOT PAVEMENT MARKING REMOVAL 4"
20	LT./RT. STA. 937+00.00 TO 937+25.00	
162	LT./RT. STA. 949+68.00 TO 951+70.00	
<b>STAGE 2</b>		
161	LT./RT. STA. 934+99.00 TO 937+00.00	MOT PAVEMENT MARKING REMOVAL 4"
480	LT./RT. STA. 937+00.00 TO 943+00.00	
480	LT./RT. STA. 943+00.00 TO 949+00.00	
216	LT./RT. STA. 949+00.00 TO 951+70.00	
29	LT./RT. STA. 934+99.00 TO 934+99.00	MOT PAVEMENT MARKING REMOVAL 24"
29	LT./RT. STA. 951+70.00 TO 951+70.00	
<b>STAGE 3</b>		
5	LT./RT. STA. 935+23.00 TO 937+00.00	MOT SHORT TERM PAVEMENT MARKING REMOVAL
12	CL STA. 935+23.00 TO 937+00.00	
16	LT./RT. STA. 937+00.00 TO 943+00.00	
40	CL STA. 937+00.00 TO 943+00.00	
16	LT./RT. STA. 943+00.00 TO 949+00.00	
40	CL STA. 943+00.00 TO 949+00.00	
8	LT./RT. STA. 949+00.00 TO 951+70.00	
18	CL STA. 949+00.00 TO 951+70.00	
<b>1,893</b>	<b>TOTAL</b>	

**70400100 TEMPORARY CONCRETE BARRIER**

FOOT	LOCATION	REMARKS
100	STA. 936+75.00 TO 937+75.00	TAPER SECTION - STAGE 1
1,150	STA. 937+75.00 TO 949+25.00	TANGENT SECTION - STAGE 1
100	STA. 949+25.00 TO 950+25.00	TAPER SECTION - STAGE 1
<b>1,350</b>	<b>TOTAL</b>	

**70400200 RELOCATE TEMPORARY CONCRETE BARRIER**

FOOT	LOCATION	REMARKS
100	STA. 936+75.00 TO 937+75.00	TAPER SECTION - STAGE 2
1,125	STA. 937+75.00 TO 949+00.00	TANGENT SECTION - STAGE 2
100	STA. 949+00.00 TO 950+00.00	TAPER SECTION - STAGE 2
<b>1,325</b>	<b>TOTAL</b>	

**78001110 PAINT PAVEMENT MARKING - LINE 4"**

FOOT	LOCATION	REMARKS
<b>WHITE</b>		
1700	LT. STA. 935+00.00 TO 952+00.00	
1700	RT. STA. 935+00.00 TO 952+00.00	
<b>YELLOW</b>		
425	CL STA. 935+00.00 TO 952+00.00	SKIP DASHES
3400	CL STA. 935+00.00 TO 952+00.00	NO PASSING ZONE AS DETERMINED BY DISTRICT 2
<b>14450</b>	<b>TOTAL</b>	(2 APPLICATIONS)

**78100100 RAISED REFLECTIVE PAVEMENT MARKER**

EACH	LOCATION	REMARKS
9	935+00.00 TO 942+16.10	80 FOOT SPACING
9	944+98.60 TO 952+00.00	
<b>18</b>	<b>TOTAL</b>	

**78100105 RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)**

EACH	LOCATION	REMARKS
4	942+16.10 TO 944+98.60	80 FOOT SPACING
<b>4</b>	<b>TOTAL</b>	

**78200410 GUARDRAIL MARKERS, TYPE A**

EACH	LOCATION	REMARKS
3	RT. STA. 940+11.20 TO 942+31.10	
3	LT. STA. 940+86.20 TO 942+31.10	
3	RT. STA. 944+83.60 TO 946+28.50	
3	LT. STA. 944+83.60 TO 947+03.50	
<b>12</b>	<b>TOTAL</b>	

**78200520 BARRIER WALL MARKERS, TYPE B**

EACH	LOCATION	REMARKS
6	LT. STA. 942+46.10 TO 944+68.60	2 MARKERS AT EACH INTERVAL
6	RT. STA. 942+46.10 TO 944+68.60	
<b>12</b>	<b>TOTAL</b>	

FILE NAME = F:\CBBEL WEST Projects\2009\121800.M09\_IL09\Cvt1\Ugn\Bh\sh\sh-schedule3.dgn



USER NAME = #USER#	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE =	CHECKED -	REVISED -
PLOT DATE = 8/2/2010	DATE - 8/6/10	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES	
SCALE:	SHEET NO. 16 OF 90 SHEETS STA. TO STA.

F.A.P. RTE. 646	SECTION 8BR-1	COUNTY WHITESIDE	TOTAL SHEETS 90	SHEET NO. 16
CONTRACT NO. 84854				
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				