


BITUMINOUS SCHEUDLE (2 OF 2)

LOCATION	OFF.	REMARKS	LENGTH	WIDTH	AREA	35101400	35600717	40600200	40600300	40600982	40600990	40603080	40603310	40603335	48102100	48203021	X0712400	X0919000
						AGGREGATE BASE COURSE, TYPE B	HOT-MIX ASPHALT BASE COURSE WIDENING, 10 1/4"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	AGGREGATE WEDGE SHOULDERS, TYPE B	HOT-MIX ASPHALT SHOULDERS, 6"	TEMPORARY PAVEMENT	TEMPORARY PAVEMENT REMOVAL
			(FT)	(FT)	(SY)	(SY)	(SQ YD)	(TON)	(TON)	(SQ YD)	(SQ YD)	(TON)	(TON)	(TON)	(TON)	(SQ YD)	(SQ YD)	(SQ YD)
Shoulders, HMA, Base																		
938+50.00 - 939+00.00	LT	Mainline	50.00	9'-2"		10.33												
939+00.00 - 939+50.00	LT	Mainline	50.00	9'-2"		15.66												
939+50.00 - 939+99.00	LT	Mainline	49.00	9'-2"		20.90												
946+78.00 - 947+00.00	LT	Mainline	22.00	9'-2"		30.44												
947+00.00 - 947+50.00	LT	Mainline	50.00	9'-2"		37.84												
947+50.00 - 948+00.00	LT	Mainline	50.00	9'-2"		10.49												
948+00.00 - 948+50.00	LT	Mainline	50.00	9'-2"		10.33												
948+50.00 - 949+00.00	LT	Mainline	50.00	9'-2"		10.33												
949+00.00 - 949+50.00	LT	Mainline	50.00	9'-2"		10.33												
949+50.00 - 950+00.00	LT	Mainline	50.00	9'-2"		10.33												
950+00.00 - 950+32.00	LT	Mainline	32.00	9'-2"		6.61												
Stage 1A																		
Temporary Ramps																		
936+40.00 - 936+45.00		At Butt-Joint	5.00	30.00	16.67						16.39							
950+27.00 - 950+32.00		At Butt-Joint	5.00	30.00	16.67						16.47							
942+09.50 - 942+16.00		Bridge	6.50	40.00	28.89						22.89							
944+98.00 - 945+04.50		Bridge	6.50	40.00	28.89						22.63							
Stage 1A																		
Butt Joints																		
936+40.00 - 936+85.00		At Butt-Joint	45.00	30.00	150.00					147.40								
950+47.00 - 950+92.00		At Butt-Joint	45.00	30.00	150.00					147.30								
Stage 1A																		
Shoulders, Wedge																		
936+40.00 - 937+00.00	RT	Adj. to Temp.	60.00	4.0	26.67										4.00			
937+00.00 - 942+44.60	RT	Pvt. and	544.60	4.0	242.04										36.31			
944+95.00 - 949+00.00	RT	Stage 1	405.00	4.0	180.00										27.00			
949+00.00 - 950+32.00	RT	HMA Shoulder	132.00	4.0	58.67										8.80			
Stage 1A																		
Temporary Pavement																		
940+00.00 - 942+44.60	RT		244.60	6.25	169.86												169.86	
944+92.20 - 946+78.00	RT		185.80	6.25	129.03												129.03	
Stage 2																		
Temp. Pavement Removal																		
942+16.13 - 942+44.63	RT																	18.50
944+92.09 - 944+98.60	RT																	3.50
Stage 1A																		
Shoulder, HMA																		
936+40.00 - 940+00.00	RT		360.00	8.00	320.00												320.00	
946+78.00 - 950+32.00	RT		354.00	8.00	314.67												314.67	
Stage 1A																		
Shoulder Base																		
936+40.00 - 940+00.00	RT		360.00	9.00	360.00	72.00												
946+78.00 - 950+32.00	RT		354.00	9.00	354.00	70.80												
Stage 1A																		
Base Course Widening																		
936+40.00 - 940+00.00	RT		360.00	1.75	70.00		70.00											
946+78.00 - 950+32.00	RT		354.00	1.75	68.83		68.83											
Field Entrance																		
936+46.00	RT				93.06	37.22												
SUB-TOTAL						354	139	0	0	295	79	0	0	0	76	635	299	22
TOTAL						397	139	6	22	295	79	1,002	264	367	76	2,299	299	22

FILE NAME = P:\CIBEL WEST Project\2009\121808_N09_IL48_Civil\Draw\Shd\0284054-ant-schedule7.dgn



USER NAME = #USER#	DESIGNED -	REVISED -
PLOT SCALE *	DRAWN -	REVISED -
PLOT DATE = 8/9/2010	CHECKED -	REVISED -
	DATE - 8/6/10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

BITUMINOUS SCHEDULE

SCALE: SHEET NO. 20 OF 90 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
646	8BR-1	WHITESIDE	90	20
CONTRACT NO. 84854				
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				