

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
---	00-P4002-03-BT	PEORIA	53	3
STA. 100+36.27		TO STA. 179+51.94		
FED. ROAD DIST. NO. -		ILLINOIS FED. AID PROJECT		



SUMMARY OF QUANTITIES				
CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE
				Y047
ROCK ISLAND/PIMITEOUI BIKE TRAIL				
20100500	TREE REMOVAL, ACRES	ACRE	0.25	0.25
20200100	EARTH EXCAVATION	CU YD	6680	6680
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	90	90
20300100	CHANNEL EXCAVATION	CU YD	650	650
20400800	FURNISHED EXCAVATION	CU YD	331	331
21101610	TOPSOIL FURNISH AND PLACE, 3"	SO YD	13736	13736
25000200	SEEDING, CLASS 2	ACRE	2.5	2.5
25000300	SEEDING, CLASS 3	ACRE	0.50	0.50
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	255	255
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	255	255
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	255	255
25100115	MULCH, METHOD 2	ACRE	3.00	3.00
25100630	EROSION CONTROL BLANKET	SO YD	1714	1714
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SO YD	2071	2071
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	284	284
28000305	TEMPORARY DITCH CHECKS	FOOT	684	684
28000400	PERIMETER EROSION BARRIER	FOOT	4200	4200
28000500	INLET AND PIPE PROTECTION	EACH	6	6
28100105	STONE RIPRAP, CLASS A3	SO YD	67	67
28100109	STONE RIPRAP, CLASS A5	SO YD	385	385
28200200	FILTER FABRIC	SO YD	452	452
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SO YD	8605	8605
35300500	PORTLAND CEMENT CONCRETE BASE COURSE 10"	SO YD	10	10
35501316	HOT-MIX ASPHALT BASE COURSE 8"	SO YD	13	13
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	12	12
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	965	965
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	1610	1610
42400800	DETECTABLE WARNINGS	SO FT	72	72

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES				
CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE
				Y047
ROCK ISLAND/PIMITEOUI BIKE TRAIL				
44000100	PAVEMENT REMOVAL	SO YD	334	334
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	264	264
44000600	SIDEWALK REMOVAL	SO FT	957	957
44003100	MEDIAN REMOVAL	SO FT	89	89
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1568	1568
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	1	1
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	1	1
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	1	1
54010402	PRECAST CONCRETE BOX CULVERT 4' X 2'	FOOT	96	96
542A1945	PIPE CULVERTS, CLASS A, TYPE 3 60"	FOOT	52	52
542D0217	PIPE CULVERTS, CLASS D, TYPE 1 12"	FOOT	38	38
54213447	END SECTIONS 12"	EACH	2	2
54213705	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 60"	EACH	2	2
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	9	9
60241800	INLETS, TYPE G-1	EACH	1	1
60260100	INLETS TO BE ADJUSTED	EACH	1	1
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	400	400
66400555	CHAIN LINK FENCE, 5' (SPECIAL)	FOOT	1200	1200
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	6	6
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	1
* 72000100	SIGN PANEL - TYPE 1	SO FT	56	56
* 73000100	WOOD SIGN SUPPORT	FOOT	156	156
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	128	128
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	33	33
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	31	31
* 78001150	PAINT PAVEMENT MARKING - LINE 12"	FOOT	20	20
* SPECIALTY ITEMS				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
ROCK ISLAND/PIMITEOUI BIKE TRAIL
SECTION 00-P4002-03-BT
PEORIA COUNTY

SCALE: VERT. _____
HORIZ. _____
DATE _____

DRAWN BY _____
CHECKED BY _____