UNLESS ELEVATIONS ARE SHOWN ---
ALL UTILITY LOCATIONS SHOWN ON THE CROSS SECTIONS ARE BASED ON THE APPROXIMATE DEPTH SUPPLIED BY THE UTILITY COMPANY

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
----	00-P4002-03-BT	PEORIA	53	53
STA. _____	TO STA. _____			
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 89307
PROJECT NO. TE-D4(085)

ORIGINAL SURVEY	SURVEYED	BY	DATE
NOTE BOOK	PLOTTED		
NO.	TEMPLATE AREAS		
	AREAS CHECKED		

MAURER ▲ STUTZ, INC. ENGINEERS SURVEYORS

℄ BIKE TRAIL

178+00.00
CUT AREA = 0.65 SQ. FT.
FILL AREA = 6.34 SQ. FT.

177+00.00
CUT AREA = 2.14 SQ. FT.
FILL AREA = 4.10 SQ. FT.

176+00.00
CUT AREA = 5.57 SQ. FT.
FILL AREA = 1.61 SQ. FT.

175+00.00
CUT AREA = 7.06 SQ. FT.
FILL AREA = 1.34 SQ. FT.

182+00.00

181+00.00
IMPROVEMENT ENDS
STA. 179+51.94
ZERO EARTHWORK
STA. 179+51.94

180+00.00
EXISTING BIKE TRAIL

179+00.00
CUT AREA = 0.00 SQ. FT.
FILL AREA = 19.05 SQ. FT.

Existing R.O.W.

5 Vert. Scale
0
0 10 Horiz. Scale