

SUMMARY OF QUANTITIES		FUNDING TYPE		80% FED. 20% LOCAL	100% LOCAL
		CONSTRUCTION CODE		0014	0043
CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	BRIDGE	WATER MAIN
* 20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	28	28	
* 20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	42	42	
20200100	EARTH EXCAVATION	CU YD	3,475	3,475	
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	320	320	
20300100	CHANNEL EXCAVATION	CU YD	50	50	
* 20300100	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	114	114	
* 21000300	GRANULAR EMBANKMENT, SPECIAL	TON	660	660	
* 21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	950	950	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2,170	2,170	
* 25000110	SEEDING, CLASS 1A	ACRE	0.7	0.7	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	63	63	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	63	63	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	63	63	
* 25100115	MULCH, METHOD 2	ACRE	0.7	0.7	
* 25200200	SUPPLEMENTAL WATERING	UNIT	55	55	
* 25000250	TEMPORARY EROSION CONTROL SEEDING	lb	70	70	
28000400	PERIMETER EROSION BARRIER	FOOT	600	600	
28000500	INLET AND PIPE PROTECTION	EACH	3	3	
28000510	INLET FILTERS	EACH	21	21	
31200100	STABILIZED SUB-BASE 4"	SQ YD	520	520	
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	4,720	4,720	
* 40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	150	150	
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	3,632	3,632	
42001300	PROTECTIVE COAT	SQ YD	4,538	4,538	
* 42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	448	448	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 6 INCH	SQ YD	43	43	
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	6,090	6,090	
42400800	DETECTABLE WARNINGS	SQ FT	88	88	
* 44000100	PAVEMENT REMOVAL	SQ YD	3,973	3,973	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	39	39	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,737	1,737	
44000600	SIDEWALK REMOVAL	SQ FT	5,788	5,788	
* 50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1	1	

* SEE SPECIAL PROVISIONS
 Δ SPECIALTY ITEMS

SUMMARY OF QUANTITIES		FUNDING TYPE		80% FED. 20% LOCAL	100% LOCAL
		CONSTRUCTION CODE		0014	0043
CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	BRIDGE	WATER MAIN
50104650	SLOPE WALL REMOVAL	SQ YD	188	188	
50200100	STRUCTURE EXCAVATION	CU YD	104	104	
50300225	CONCRETE STRUCTURES	CU YD	100.8	100.8	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	597.2	597.2	
50300260	BRIDGE DECK GROOVING	SQ YD	894	894	
* 50300260	PROTECTIVE COAT, SPECIAL	SQ YD	1,250	1,250	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	147,770	147,770	
50800515	BAR SPLICERS	EACH	598	598	
Δ * 5091125	BICYCLE RAILING, SPECIAL	FOOT	162	162	
Δ * 5091155	PARAPET RAILING, SPECIAL	FOOT	133	133	
* 51100300	SLOPE WALL 6 INCH	SQ YD	370	370	
51200700	FURNISHING PRECAST CONCRETE PILES 14"	FOOT	301	301	
51202305	DRIVING PILES	FOOT	301	301	
51203000	TEST PILES PRECAST CONCRETE	EACH	2	2	
* 20026407	TEMPORARY SHEET PILING	SQ FT	170	170	
51500100	NAME PLATES	EACH	1	1	
* 5128510	CONCRETE COLLAR	CUYD	4	4	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	563	563	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	128	128	
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	10	10	
* 55100400	STORM SEWER REMOVAL 10"	FOOT	27	27	
* 55100500	STORM SEWER REMOVAL 12"	FOOT	72	72	
* 55100900	STORM SEWER REMOVAL 18"	FOOT	126	126	
* 55101200	STORM SEWER REMOVAL 24"	FOOT	37	37	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	87	87	
* 59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	257	257	
* 60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	232	232	
* 60224710	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 3V FRAME AND GRATE	EACH	1	1	
* 60225400	RESTRICTED DEPTH MANHOLES, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
* 60236200	INLETS, TYPE A, TYPE B GRATE	EACH	1	1	
* 60242850	INLETS, SPECIAL, TYPE H	EACH	9	9	
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2	
* 60258000	MANHOLES TO BE RECONSTRUCTED (SPECIAL)	EACH	2	2	

* SEE SPECIAL PROVISIONS

FILE NAME = P:\N0240062\Plans\Sheets\04summary.dgn	DESIGNED - JAJ	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT DATE = 8/4/2010 6:00:33 PM	DRAWN - JAJ	REVISED -					6354	06-00230-00-BR	MCLEAN	64	4
	CHECKED - RLH	REVISED -		SCALE : NONE SHEET NO. 4 OF 64 SHEETS STA. 34+05.00 TO STA. 43+05.00			VERNON AVENUE, TOWN OF NORMAL CONTRACT NO. 91430				
	DATE - 06/2010	REVISED -					FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT				