

SUMMARY OF QUANTITIES		FUNDING TYPE		80% FED. 20% LOCAL	100% LOCAL
		CONSTRUCTION CODE		0014	0043
CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	BRIDGE	WATER MAIN
* 60500060	REMOVING INLETS	EACH	4	4	
* 60604800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18 (SPECIAL)	FOOT	1,594	1,594	
Δ * 63000130	STEEL PLATE BEAM GUARDRAIL, TYPE A (SPECIAL)	FOOT	75	75	
Δ 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	1	1	
Δ * 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	
Δ * 63100215	TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL)	EACH	1	1	
* 63200310	GUARDRAIL REMOVAL	FOOT	246	246	
* 66410300	CHAIN LINK FENCE REMOVAL	FOOT	149	149	
* 66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	146	146	
67100100	MOBILIZATION	L SUM	1	1	
* 70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	1	
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	5,445	5,445	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,815	1,815	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	687.5	687.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	287.5	287.5	
Δ 78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	2,490	2,490	
Δ 78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	26	26	
Δ * 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8	
Δ * 78200520	BARRIER WALL MARKERS, TYPE B	EACH	8	8	
Δ * 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2	
* Z0061418	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 12"	FOOT	111	111	
* Z0051460	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE, 15"	FOOT	15	15	
* Z0061472	STORM SEWERS, TYPE 2, WATER MAIN QUALITY PIPE, 24"	FOOT	22	22	
* X0323491	SLOPE WALL CRACK SEALING	FOOT	400	400	
* Z001800Z	DRAINAGE SCUPPERS, DS-11	EACH	4	4	
* X0325365	RESTRICTED DEPTH INLET TYPE B, TYPE 8 GRATE	EACH	2	2	
Δ * X0325846	ABANDONMENT OF EXISTING WATER MAINS	L SUM	1		1
Δ * X0081405	DUCTILE IRON WATER MAIN 10", RESTRAINED JOINT TYPE	FOOT	235		235
Δ * X0469600	CONNECTION TO EXISTING WATER MAIN	EACH	3		3
* X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1	1	
* X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1	1	
Δ * X5640150	FIRE HYDRANT ASSEMBLY COMPLETE	EACH	1		1
* X6020127	RESTRICTED DEPTH INLET TYPE B, TYPE 3V FRAME AND GRATE	EACH	6	6	

* SEE SPECIAL PROVISIONS

Δ SPECIALTY ITEMS

SUMMARY OF QUANTITIES		FUNDING TYPE		80% FED. 20% LOCAL	100% LOCAL
		CONSTRUCTION CODE		0014	0043
CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	BRIDGE	WATER MAIN
* XX004812	VIDEO TAPING OF SEWERS	FOOT	200	200	
* XX007452	RELOCATE BOLLARDS	EACH	2	2	
Δ * XX007524	GATE VALVE AND BOX, 10"	EACH	3		3
* Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	4	4	
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
* Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
* Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1	
* Z0077700	WOOD FENCE TO BE REMOVED AND RE-ERECTED	FOOT	188	188	

* SEE SPECIAL PROVISIONS

FILE NAME = P:\10240062\Plans\Sheets\04summary.dgn	DESIGNED - JAJ	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.U. RTE. 6354	SECTION 06-00230-00-BR	COUNTY MCLEAN	TOTAL SHEETS 64	SHEET NO. 5	
PLOT DATE = 8/4/2010 6:00:34 PM	DRAWN - JAJ	REVISED -		SCALE : NONE	SHEET NO. 5 OF 64 SHEETS	STA. 34+05.00 TO STA. 43+05.00	VERNON AVENUE, TOWN OF NORMAL FED. ROAD DIST. NO. 5 ILLINOIS FED. AID PROJECT				
	CHECKED - RLH	REVISED -									
	DATE - 06/2010	REVISED -									