

STORM SEWER SCHEDULE

STATION	SIDE	ITEM	STANDARD NUMBER	STORM SEWERS, WATER MAIN REQUIREMENTS			STORM SEWERS, SPECIAL	MANHOLES				INLETS				TRENCH BACKFILL
				12 IN	15 IN	18 IN	4 IN	4 FT DIAMETER		TYPE A		TYPE B				
				FOOT			EACH				A-1-C	A W/ SPL F & G	A-11	A W/ SPL F & G	B-11	
LAFAYETTE STREET																
20+88.4	LT	INLET	602306, 602601, 604051												1	
		SS		14												3.7
20+92.8	LT	MANHOLE	602401, 602601, 602701, 604001					1								
		SS		124												16.6
22+18.5	LT	MANHOLE	602401, 602601, 602701						1							
		SS			106											20.8
22+18.5	RT	INLET	602301									1				
		SS		42												5.8
23+28.2	LT	MANHOLE	602401, 602601, 602701, 604001					1								
		SS				58										15.7
23+89.5	LT	MANHOLE	602401, 602601, 602701, 604001					1								
LIBERTY STREET																
11+83.1	LT	INLET														
		SS		78												14.2
12+65.0	LT	INLET	602306, 602601												1	
		SS		42												5.8
12+65.0	RT	INLET	602301									1				
US 24																
3+20.6	RT	INLET														
		SS		202												35.0
5+25.6	RT	INLET														
WASHINGTON STREET																
30+88.8	LT	INLET	602301, 604051									1				
		SS		48												6.3
30+89.2	RT	INLET	602306, 602601, 604051											1		
		SS														
33+03.2	LT	INLET														
		SS														2.9
330+03.2	RT	INLET														
		SS														42
TOTALS				550	106	58	42	3	1	1	2	2	1			126.8
USE				550	106	58	42	3	1	1	2	2	1			127

PORTLAND CEMENT CONCRETE SIDEWALK, 4"

STATION TO STATION	SIDE	PORTLAND CEMENT CONCRETE SIDEWALK, 4"	PROTECTIVE COAT
		SQ FT	SQ YD
U.S. ROUTE 24			
2+68.9	5+42.6	LT	3,184.4
3+07.4	5+05.1	RT	1,319.8
LAFAYETTE STREET			
20+70.3	23+40.8	RT	4,115.9
20+81.8	23+27.1	LT	2,277.9
23+82.0	24+03.9	RT	442.7
WASHINGTON STREET			
30+69.8	33+41.6	LT	3,832.0
30+82.6	33+28.5	RT	2,272.2
33+82.7	34+04.8	LT	532.0
LIBERTY STREET			
11+71.0	14+37.5	LT	1,624.4
12+07.7	14+04.9	RT	3,922.9
TOTALS			23,524.2
USE			2,614

WATER SERVICE LINES

STATION	SIDE	WATER SERVICE LINE 4"	WATER VALVES 4"
		FOOT	EACH
LAFAYETTE STREET			
21+01	RT	10	1
21+21	RT	10	1
21+41	RT	10	1
21+62	RT	10	1
21+84	RT	10	1
22+08	RT	10	1
22+32	RT	10	1
22+54	RT	10	1
22+74	RT	10	1
22+93	RT	10	1
23+11	RT	10	1
LIBERTY STREET			
12+27	RT	10	1
12+59	RT	10	1
12+82	RT	10	1
13+05	RT	10	1
13+29	RT	10	1
13+52	RT	10	1
13+73	RT	10	1
13+92	RT	10	1
14+11	RT	10	1
WASHINGTON STREET			
31+10	LT	10	1
31+40	LT	10	1
31+61	LT	10	1
31+81	LT	10	1
32+01	LT	10	1
32+22	LT	10	1
32+44	LT	10	1
32+65	LT	10	1
32+86	LT	10	1
33+09	LT	10	1
34+03	LT	10	1
TOTALS		310	31
USE		310	31

ITEMS TO BE REMOVED OR ADJUSTED

STATION	OFFSET	VALVE BOXES TO BE ADJUSTED	FIRE HYDRANTS TO BE REMOVED
		EACH	
U.S. ROUTE 24			
3+82.8	29.39' LT	1	
3+93.4	29.39' LT	1	
4+21.2	29.50' LT	1	
4+37.9	29.18' LT	1	
4+71.0	30.08' LT	1	
5+76.3	24.00' LT	1	
5+36.8	27.03' LT	1	
5+90.2	16.73' LT	1	
LIBERTY STREET			
11+07.1	27.9' RT		1
WASHINGTON STREET			
34+03.4	19.3' LT	1	
34+03.4	20.4' LT		1
TOTALS		9	2
USE		9	2

CURB REMOVAL

STATION TO STATION	SIDE	CURB REMOVAL FOOT	
U.S. ROUTE 24			
2+04.0	2+19.0	RT	32.8
3+00.0	5+12.0	RT	212
5+91.0	6+07.0	RT	20.6
LAFAYETTE STREET			
20+95.0	23+05.0	LT	210
WASHINGTON STREET			
30+95.0	33+05.0	RT	208
LIBERTY STREET			
11+04.5	11+21.0	LT	22.7
11+04.5	11+25.0	RT	42.7
0+12.0	33+08.0	LT	212.7
14+76.0	15+07.2	RT	45.7
14+90.0	15+07.2	LT	22.8
TOTAL			1,030.0
USE			1,030

BRICK PAVER REMOVAL

STATION TO STATION	SIDE	BRICK PAVER REMOVAL SQ YD	
LAFAYETTE STREET			
20+93.0	24+09.9	RT & LT	2,290.9
LIBERTY STREET			
11+79.0	14+38.0	RT & LT	1,802.1
WASHINGTON STREET			
31+68.0	34+04.9	RT & LT	1,670.2
TOTAL			5,763.2
USE			5,764

PATCHING SCHEDULE

STATION	SIDE	CLASS C PATCHES, TYPE II, 9"
		SQ YD
U.S. ROUTE 24		
2+15	RT & LT	13.8
5+97	RT & LT	13.3
TOTAL		27.1
USE		28

EARTHWORK SCHEDULE

STATION TO STATION	EXCAVATION	EXCAVATION ADJUSTED FOR SHRINKAGE*	EMBANKMENT	BALANCE WASTE OR SHORTAGE (-)
	CU YD			
LAFAYETTE STREET				
20+89	24+04	881.4	661.1	202.7
LIBERTY STREET				
12+00	14+00	622.7	467.0	111.7
WASHINGTON STREET				
30+89	34+05	246.3	184.7	329.4
TOTALS		1,750.4	1,312.8	643.8
USE		1,751	1,313	644