

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES URBAN	80% FED	80% FED		
				20% STATE	20% STATE		
				0047 BRIDGE 1 SN 016-0343	0047 BRIDGE 2 SN 016-0344		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	6	6		
67100100	MOBILIZATION	L SUM	1	0.5	0.5		
70107025	CHANGEABLE MESSAGE SIGN	CAL DA	120	60	60		
70300904	PAVEMENT MARKING TAPE, TYPE IV 4"	FOOT	11430	5715	5715		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1125	562	563		
70600270	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, WIDE), TEST LEVEL 3	EACH	2	1	1		
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3266	1633	1633		
78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	4730	2365	2365		
78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	300	150	150		
78200011	BARRIER WALL REFLECTORS, TYPE C	EACH	24	12	12		
80320011	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, WIDE), TEST LEVEL 3	EACH	2	1	1		
78300202	PAVEMENT MARKING REMOVAL - WATER BLASTING	SO FT	270	135	135		

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES URBAN	80% FED	80% FED		
				20% STATE	20% STATE		
				0047 BRIDGE 1 SN 016-0343	0047 BRIDGE 2 SN 016-0344		
X2700003	GROOVING FOR RECESSED PAVEMENT MARKING 8"	FOOT	556	278	278		
X2700005	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 7"	FOOT	556	278	278		
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.5	0.5		
X7010410	SPEED DISPLAY TRAILER	CAL MO	8	4	4		
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SO FT	3772	1886	1886		
Z0007101	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1	1			
Z0007102	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 2	L SUM	1		1		
Z0010501	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1	1			
Z0010502	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM	1		1		
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	77	38.5	38.5		
70600260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW, TEST LEVEL 3)	EACH	2	1	1		
70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, WIDE), TEST LEVEL 3	EACH	2	1	1		

FILE NAME =	USER NAME = multimed	DESIGNED -	REVISED -
dw:\planroom\dtd\illinois\p1001\Documents\DOT	Offices\District\Projects\DI\852\NCAD\Design\DI852\sh	DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	2021-096-BP	COOK	29	3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 62P24	

REVISED SHEET 10/14/2021