

| SUMMARY OF QUANTITIES | | | | CONSTRUCTION TYPE CODE | | | | | SUMMARY OF QUANTITIES | | | | CONSTRUCTION TYPE CODE | | | | |
|-----------------------|---|-------|------------------------|------------------------|--|--|--|---|-----------------------|---|--------|------------------------|------------------------|--|--|--|--|
| CODE NO | ITEM | UNIT | TOTAL QUANTITIES URBAN | 100% STATE 0005 | | | | | CODE NO | ITEM | UNIT | TOTAL QUANTITIES URBAN | 100% STATE 0005 | | | | |
| 20200100 | EARTH EXCAVATION | CU YD | 40 | 40 | | | | | 44201794 | CLASS D PATCHES, TYPE III, 12 INCH | SO YD | 388 | 388 | | | | |
| 21101615 | TOPSOIL FURNISH AND PLACE, 4" | SO YD | 160 | 160 | | | | | 44201796 | CLASS D PATCHES, TYPE IV, 12 INCH | SO YD | 245 | 245 | | | | |
| 25200110 | SODDING, SALT TOLERANT | SO YD | 160 | 160 | | | | | 60300305 | FRAMES AND LIDS TO BE ADJUSTED | EACH | 2 | 2 | | | | |
| 40600290 | BITUMINOUS MATERIALS (TACK COAT) | POUND | 93705 | 93705 | | | | * | 66900200 | NON-SPECIAL WASTE DISPOSAL | CU YD | 40 | 40 | | | | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 312 | 312 | | | | * | 66900530 | SOIL DISPOSAL ANALYSIS | EACH | 3 | 3 | | | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SO YD | 685 | 685 | | | | * | 66901001 | REGULATED SUBSTANCES PRE-CONSTRUCTION PLAN | LSUM | 1 | 1 | | | | |
| 40604062 | HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70 | TON | 3783 | 3783 | | | | * | 66901003 | REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT | LSUM | 1 | 1 | | | | |
| 40605026 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, 9.5, MIX "F", N80 | TON | 16627 | 16627 | | | | * | 66901006 | REGULATED SUBSTANCES MONITORING | CAL DA | 10 | 10 | | | | |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SO FT | 2200 | 2200 | | | | | 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 12 | 12 | | | | |
| 42400800 | DETECTABLE WARNINGS | SO FT | 260 | 260 | | | | | 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | |
| 44000156 | HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4" | SO YD | 208233 | 208233 | | | | | 70102625 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701606 | L SUM | 1 | 1 | | | | |
| 44000600 | SIDEWALK REMOVAL | SO FT | 2200 | 2200 | | | | | 70102630 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701601 | L SUM | 1 | 1 | | | | |
| 44201789 | CLASS D PATCHES, TYPE II, 12 INCH | SO YD | 2063 | 2063 | | | | | 70102632 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701602 | L SUM | 1 | 1 | | | | |
| * SPECIALTY ITEMS | | | | | | | | | | | | | | | | | |

REVISED SHEET 10/16/2020

REV-SEP

| | | | |
|---|--|------------|-----------|
| FILE NAME = | USER NAME = alrahamm | DESIGNED - | REVISED - |
| pw:\planroom\dtd\illinois\p1001\Documents\DOT | Offices\District\Projects\043520\CADD\Date\Design\043520-4 | DRAWN - | REVISED - |
| | PLOT SCALE = 100.0000' / 1in | CHECKED - | REVISED - |
| | PLOT DATE = 8/14/2020 | DATE - | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

| | | | |
|-----------------------|-----------|-----------|--------------|
| SUMMARY OF QUANTITIES | | | |
| SCALE: | SHEET NO. | OF SHEETS | STA. TO STA. |

| | | | | |
|---|----------------|--------|--------------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 334 | 2020-052-R5&SW | LAKE | 34 | 3 |
| FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | | | CONTRACT NO. 62L24 | |