

**INDEX OF SHEETS**

SHEET NO	DESCRIPTION
1	COVER SHEET
2	SIGNATURE SHEET
3	INDEX OF SHEETS & HIGHWAY STANDARDS
4	GENERAL NOTES & COMMITMENTS
5	MIX DESIGN
6-13	SUMMARY OF QUANTITIES
14-17	TYPICAL SECTIONS: IL 149 SCHEDULES:
18	PAVEMENT & EARTHWORK SCHEDULES
19	BINDER THICKNESS SCHEDULE
20-21	INLET SCHEDULE
22	STORM SEWER SCHEDULE
23	SIDEWALK & MULTI USE PATH SCHEDULE
24-25	STAMPED COLORED PCC SIDEWALK SCHEDULE
26	CURB AND GUTTER SCHEDULE
27	ENTRANCE GEOMETRICS SCHEDULE
28	SIDEROAD GEOMETRICS SCHEDULE
29-30	ENTRANCE SCHEDULE
31	SIDEROAD SCHEDULE
32-33	PAVEMENT MARKING SCHEDULE
34	SIGN & LIGHTING REMOVAL SCHEDULE
35	SEEDING & EROSION CONTROL, LANDSCAPING & FENCE SCHEDULES
36	MISC. REMOVAL & TREE REMOVAL SCHEDULES
37-38	GEOPAK ELEMENTS IDENTIFICATION
39	TIES & BENCHMARKS
40-46	IL 149 PLAN & PROFILE
47-57	SIDEROADS PLAN & PROFILE
58-63	IL 149 DRAINAGE & UTILITY PLAN
64-67	IL 149 EROSION CONTROL & SEEDING PLAN
68-72	ROW PLAT
73-76	IL 149 PAVEMENT MARKING PLAN
77	BUILDING REMOVAL LOCATION #1
78-79	DETAILS: RETAINING WALLS
80	DISTRICT DETAILS
81	SIDEROAD & ENTRANCE DETAILS
82-171	IL 149 CROSS SECTIONS

**HIGHWAY STANDARDS**

000001-07	Standard Symbols, Abbreviations and Patterns
001001-02	Areas of Reinforcement Bars
001006	Decimal of an Inch and of a Foot
280001-07	Temporary Erosion Control Systems
420001-09	Pavement Joints
420101-06	24' (7.2 m) Jointed PCC Pavement
420701-03	Pavement Welded Wire Reinforcement
424001-11	Perpendicular Curb Ramps for Sidewalks
602306-03	Inlet, Type B
602401-06	Precast Manhole, Type A, 4' (1.22 m) Diameter
602601-06	Precast Reinforced Concrete Flat Slab Top
604001-05	Frame and Lids, Type 1
604006-05	Frame and Grate, Type 3
604066-02	Frame and Lid, Type 15
701001-02	Off-Road Operations, 2L, 2W, More Than 15' Away
701006-05	Off-Road Operations, 2L, 2W, 15' to 24" From Pavement Edge
701011-04	Off-Road Moving Operations, 2L, 2W, Day Only
701101-05	Off-Road Operations, Multilane, 15' (4.5 m) to 24" (600 mm) from Pavement Edge
701106-02	Off-Road Operations, Multilane, More Than 15' (4.5 m) Away
701301-04	Lane Closure, 2L, 2W, Short Time Operations
701311-03	Lane Closure 2L, 2W, Moving Operations - Day Only
701427-05	Lane Closure, Multilane, Intermittent or Moving Oper., for Speeds < 40 MPH
701501-06	Urban Lane Closure, 2L, 2W, Undivided
701502-09	Urban Lane Closure, 2L, 2W, with Bidirectional Left Turn Lane
701601-09	Urban Lane Closure, Multilane, 1W or 2W with Nontraversable Median
701701-10	Urban Lane Closure, Multilane Intersection
701801-06	Sidewalk, Corner or Crosswalk Closure
701901-08	Traffic Control Devices
720001-01	Sign Panel Mounting Details
720006-04	Sign Panel Erection Details
720011-01	Metal Posts for Signs, Markers and Delineators
729001-01	Applications of Types A and B Metal Posts (For Signs & Markers)
780001-05	Typical Pavement Markings
781001-04	Typical Applications Raised Reflective Pavement Markers

MODEL: D:\result  
 FILE NAME: p:\p\planroom\dct\_illinois\gov\p\p\DOT\Documents\DOT\_Offices\District\_9\Projects\7848\1\CADData\CAD\Insects\7848\1\_rfa-cv-sqa\_index.dgn

REV. 10-27-2020

USER NAME = maestil PLOT SCALE = 94,4444' / in. PLOT DATE = 10/27/2020	DESIGNED - DRAWN - CHECKED - DATE -	REVISED - REVISED - REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS & HIGHWAY STANDARDS	SCALE: SHEET OF SHEETS STA. TO STA.	F.A.P. RTE. 873 SECTION 28-5106(W-3,RS-8) COUNTY FRANKLIN TOTAL SHEETS 171 SHEET NO. 3 CONTRACT NO. 78481 ILLINOIS FED. AID PROJECT
--	--	--	---	-------------------------------------	-------------------------------------	---

# SUMMARY OF QUANTITIES - CONT

COUNTY:	FRANKLIN CO	
ROUTE:	IL 149	
FUNDING:	80% FED / 20% STATE	80% FED / 20% CITY
LOCATION:	URBAN	URBAN
TOTAL QUANTITY	ROADWAY 0003	FACILITY 0028

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0003	FACILITY 0028
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	41	41	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	2,675	2,675	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	2,007	2,007	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	42,812	35,151	7,661
42400800	DETECTABLE WARNINGS	SQ FT	650	650	
44000100	PAVEMENT REMOVAL	SQ YD	6,694	6,694	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	1,667	1,667	
<span style="border: 1px dashed black; border-radius: 50%; padding: 2px;">2</span> 44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	8,509	8,509	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,967	2,967	
44000300	CURB REMOVAL	FOOT	1,009	1,009	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,093	3,093	
44000600	SIDEWALK REMOVAL	SQ FT	13,984	13,984	

MODEL: Default  
FILE NAME: p:\pub\mcomon.dwg  
PROJECT: 78481\CAAD\Drawings\DOT\_Offices\Drawings\78481\_shts-cif\_500\_rdx.dwg

△ REV. 10-27-2020

USER NAME = maesbl	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE. 873	SECTION 28-5106(W-3,RS-8)	COUNTY FRANKLIN	TOTAL SHEETS 171	SHEET NO. 8
PLOT SCALE = 100,0000 ' / in.	CHECKED -	REVISED -		SCALE:      SHEET      OF      SHEETS      STA.      TO STA.				CONTRACT NO. 78481				
PLOT DATE = 8/14/2020	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								