



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 28, 2020

SUBJECT: FAI Route 80 (I-80)
Project NHPP-HB1K(096)
Section 2013-008B
Will County
Contract No.60W34
Item No. 64, November 6, 2020 Letting
Addendum C

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices
2. Revised page iv of the Table of Contents to the Special Provisions
3. Revised page 349 of the Special Provisions
4. Revised sheet 24 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

PORTLAND CEMENT CONCRETE – HAUL TIME (BDE)..... 249
 PORTLAND CEMENT CONCRETE BRIDGE DECK CURING (BDE)..... 250
 PREFORMED PLASTIC PAVEMENT MARKING TYPE D - INLAID (BDE) 251
 REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE) 254
 SILT FENCE, INLET FILTERS, GROUND STABILIZATION AND RIPRAP FILTER FABRIC (BDE) .. 265
 STEEL COST ADJUSTMENT (BDE) 271
 STEEL PLATE BEAM GUARDRAIL MANUFACTURING (BDE) 274
 SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) 274
 SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)..... 275
 TEMPORARY PAVEMENT MARKING (BDE)..... 275
 TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (BDE)..... 278
 TRAFFIC CONTROL DEVICES - CONES (BDE) 279
 TRAFFIC SPOTTERS (BDE) 280
 TRAINING SPECIAL PROVISIONS (BDE) 281
 IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION 284
 TRAVERSABLE PIPE GRATE FOR CONCRETE END SECTIONS (BDE)..... 286
 WARM MIX ASPHALT (BDE) 287
 WEEKLY DBE TRUCKING REPORTS (BDE) 288
 WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 289
 CN RIGHT OF ENTRY AGREEMENT 291
 STORM WATER POLLUTION PREVENTION PLAN 308
 404 PERMIT 321
 PROJECT LABOR AGREEMENT 326
 NAVIGATIONAL CONSIDERATIONS AND CONSTRUCTION OVER NAVIGABLE WATERS..... 345
 ELASTOMERIC BEARINGS (BDE)..... 347
 MANHOLES, VALVE VAULTS, AND FLAT SLAB TOPS (BDE)..... 348
 PORTLAND CEMENT CONCRETE PAVEMENT PLACEMENT (BDE) 349
 REMOVE TEMPORARY CONCRETE BARRIER, STATE OWNED 349

Revised 10/28/2020

PORTLAND CEMENT CONCRETE PAVEMENT PLACEMENT (BDE)

Effective: July 1, 2020

Revise the fifth paragraph of Article 420.07 of the Standard Specifications to read:

“The concrete shall be deposited uniformly across the subgrade or subbase as close as possible to its final position. The time elapsing from when the concrete is unloaded until it is incorporated into the work shall not exceed 20 minutes. When required, hand spreading shall be accomplished with shovels.”

REMOVE TEMPORARY CONCRETE BARRIER, STATE OWNED

Description. This work shall include the removal and disposal of existing temporary concrete barrier and appurtenances, at the locations shown on the plans or as directed by the engineer.

This work shall conform to the requirements of Section 440 of the Standard Specifications.

The existing temporary concrete barrier may be pinned into the existing pavement, and removal of the pins shall be included in this work as directed by the Engineer.

Method of Measurement. This work will be measured for payment in feet in place along the centerline of the barrier prior to removal.

Basis of Payment. This work will be paid for at the contract unit price per foot for REMOVE TEMPORARY CONCRETE BARRIER, STATE OWNED.

Revised 10/28/2020