


				CONSTRUCTION CODE						
				90% FEDERAL, 10% STATE						
CODE NO.	ITEM	UNIT	TOTAL QUANTITY			BRIDGE	BRIDGE	BRIDGE	BRIDGE	RET WALL
						0010	0010	0010	0010	0004
				ROADWAY 0004 URBAN	SAFETY 0021 URBAN	SN 099-0062	SN 099-0900	SN 099-0901	SN 099-0904	SN 099-Z##1 SN 099-Z##2 SN 099-W034
X0326687	REMOVE HIGH TENSION CABLE MEDIAN BARRIER TERMINAL	EACH	6	6						
X0327234	LIGHTING UNIT IDENTIFICATION DECAL	EACH	13		13					
X0327392	WOOD POLE, 60 FT, CLASS 4	EACH	9		9					
X6440110	HIGH TENSION CABLE MEDIAN BARRIER (SPECIAL) 	FOOT	1,000		1,000					
X0327979	PAVEMENT MARKING REMOVAL - GRINDING	SQ FT	40,529	40,529						
X0327980	PAVEMENT MARKING REMOVAL - WATER BLASTING	SQ FT	86,484	86,484						
X0324044	EROSION CONTROL, TEMPORARY PIPE SLOPE DRAIN	EACH	1	1						
X0900075	COFFERDAM (TYPE 1) (IN-STREAM/WETLAND WORK)	EACH	6			4			2	
X1400366	TEMPORARY TRAFFIC SIGNAL INSTALLATION (SPECIAL)	LSUM	1	1						
X5210150	HIGH LOAD MULTI-ROTATIONAL BEARINGS, GUIDED EXPANSION, 400K	EACH	24						24	
X6020090	MANHOLES, WITH RESTRICTOR PLATE	EACH	1	1						
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	21	21						
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1						
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1						

\* SPECIALTY ITEMS

USER NAME = default	DESIGNED -	REVISED -
	DRAWN - LAM	REVISED -
PLOT SCALE = #SCALE#	CHECKED - DF	REVISED -
PLOT DATE = 7/15/2020	DATE - 6/25/2020	REVISED -



STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

EB I-80 FROM GARDNER STREET TO ROWELL AVENUE  
SUMMARY OF QUANTITIES

SCALE: N.T.S. SHEET 20 OF 23 SHEETS STA. TO STA.

REVISED SHEET 10/28/2020		REV-SEP	
F.A.I. RTÉ.	SECTION	COUNTY	TOTAL SHEETS
80	2013-008B	WILL	511
		SHEET NO. 24	
		CONTRACT NO. 60W34	
ILLINOIS FED. AID PROJECT			