90% FED 10% STATE

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY (URBAN)	CONSTRUCTION CODE: ROADWAY 0004 URBAN	BRIDGE 0011 016-1713	BRIDGE 0011 016-1716	RETAINING WALL 0040 016-1802	HIGHWAY LIGHTING 0021 URBAN	TRAFFIC SIGNALS 0021 URBAN
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	10,348	10,348 △1					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	230	230					
*	80400100	ELECTRIC SERVICE INSTALLATION	EACH	1					1	
*	80400200	ELECTRIC UTILITY SERVICE CONNECTION	L SUM	1					1	
*	81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	383					383	
*	81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	480					480	
*	81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	1075					1075	
*	81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	591						591
*	81100300	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	113						113
*	81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., PVC COATED GALVANIZED STEEL	FOOT	2420					2420	
*	81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	70						70
*	81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., PVC COATED GALVANIZED STEEL	FOOT	1858 △1					1258 △1	600
*	81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., PVC COATED GALVANIZED STEEL	FOOT	550					550	
*	81101005	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., PVC COATED GALVANIZED STEEL	FOOT	7040					7040	

* DENOTES SPECIALTY ITEM * * DENOTES NON-PARTICIPATING ITEM

△1 Rev. 10-30-13

AECOM
303 EAST WACKER DRIVE, SUITE 1400
CHICAGO, IL 60601-5276
PHONE: (312) 373-7700 FAX: (312) 373-6800

0160W26-sht-900.dgn	DESIGNED - JWM	REVISED -	
USER NAME = chsue	DRAWN - JWM	REVISED -	
PLOT SCALE = 1.0000 ' / in.	CHECKED - DBM	REVISED -	
PLOT DATE = 9/16/2013	DATE - 9/15/13	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET 13 OF 26 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-008R	COOK	559	18

CONTRACT NO. 60W26
ILLINOIS FED. AID PROJECT

FILE PATH = cat\398939-pw01.aecomonline.local\PWAECOM28\Documents\01 Americas\Transportation\60262493B Circle\Phase II\200 CAD\035 Roadway\Sheets\160W26-sht-500.dgn