

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	URBAN					
				ROADWAY	BRIDGE	BRIDGE	RETAINING WALL	HIGHWAY LIGHTING	TRAFFIC SIGNALS
				0004 URBAN	0011 016-1713	0011 016-1716	0040 016-1802	0021 URBAN	0021 URBAN
* X0327004	TEMPORARY WOOD POLE, 60 FT., CLASS 4	EACH	7					7	
X0327357	CONSTRUCTION VIBRATION MONITORING	L SUM	1	1					
X0327371	PLUG EXISTING PIPE	CU YD	0.5	0.5					
* X0327391	WOOD POLE, 45 FT, CLASS 5	EACH	15					15	
X0327615	COMBINED SEWER REMOVAL 8"	FOOT	296	296					
* X0327616	MAINTAINING ITS DURING CONSTRUCTION	CAL MO	12					12	
* X0370013	CONCRETE FOUNDATION FOR TYPE "P" BASE MOUNTED TRAFFIC SIGNAL CONTROLLER (CDOT)	EACH	2						2
* X0370015	CONCRETE FOUNDATION, 30" DIAMETER, 1 1/2" ANCHOR RODS, 16 1/2" BOLT CIRCLE (CDOT)	EACH	2						2
* X0370017	DRILL MANHOLE OR HANDHOLE CHICAGO	EACH	47					43	4
* X0370018	ELECTRIC CABLE IN CONDUIT NO. 14, 19/C (CDOT)	FOOT	1447						1447
* X0370021	ELECTRICAL HANDHOLE, 30", 24" FRAME AND LID (CDOT)	EACH	1						1
* X0370022	ELECTRICAL HANDHOLE, HEAVY DUTY, 36", 24" FRAME AND LID (CDOT)	EACH	2						2
* X0370023	ELECTRICAL MANHOLE, 3' X 4' X 4', 24" FRAME AND LID (CDOT)	EACH	6					4	2
* X0370028	HARNESS CABLE, NO. 16 8/C (CDOT)	FOOT	643						643

\* DENOTES SPECIALTY ITEM

\*\* DENOTES NON-PARTICIPATING ITEM

Rev. 10-30-13



0180W26-shr-500.dgn	DESIGNED - JWM	REVISED -
USER NAME - chue	DRAWN - JWM	REVISED -
PLOT SCALE - 1/8" = 1' in.	CHECKED - DBM	REVISED -
PLOT DATE - 9/16/2013	DATE - 9/15/13	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE:	SHEET 18	OF 26	SHEETS	STA.	TO STA.
--------	----------	-------	--------	------	---------

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-008R	COOK	559	23
CONTRACT NO. 60W26			ILLINOIS FED. AID PROJECT	

FILE PATH: p:\11388229\pmit\amesonline\local\p\ue\c003\document\101\transportation\52259938\_Curc1a\Phase 1\1028\_C0V006\_Roadway\Sheet\60W26\_Contract\0180W26-shr-500.dgn