REMOVAL SCHEDULE

LOCATION	STATION	TO	STATION	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	TREE REMOVAL, ACRES	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	PAVEMENT REMOVAL	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	DRIVEWAY PAVEMENT REMOVAL	CURB REMOVAL	GUTTER REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL	CONCRETE BARRIER REMOVAL	MEDIAN REMOVAL	PAVED SHOULDER REMOVAL	REMOVE EXISTING GATE	REMOVE IMPACT ATTENUATORS, NO SALVAGE	APPROACH SLAB REMOVAL	FENCE REMOVAL	REMOVE GATE POSTS
				INCH	UNIT	ACRE	SQ YD	SQ YD	SQ YD	SQ YD	FOOT	FOOT	FOOT	SQ FT	FOOT	SQ FT	SQ YD	EACH	EACH	SQ YD	FOOT	EACH
HALSTED STREET	3830+15.00	TO	3839+05.00	-	-	-	197	3497	55	24	-	-	955	6970	-	282	-	-	-	680	-	-
HARRISON STREET	7807+25.00	TO	7811+33.00	41	-	0.45	-	702	-	116	74	-	319	2323	-	-	-	1	-	523	237	3
I-290 WESTBOUND				-	-	-	-	109	A -	-	-	-	-	-	169	-	-	-	-	-	-	A -
I-290 EASTBOUND				-	-	-	-	294	-	-	-	-	-	-	262	-	198	-	-	-	-	-
I-90/94 SOUTHBOUND				-	-	-	-	-	A -	-	-	-	-	-	108	-	137	-	-	-	-	-
RAMP ES	105+51.22	TO	110+50.00	411	48	-	-	579	-	-	-	150	119	-	400	-	175	-	1	-	172	-
RAMP ES	110+50.00	TO	112+95.78	-	-	-	-	-	-	-	-	-	-	-	350	148	374	-	-	-	-	-
RAMP SW				70	34	-	-	214	-	-	-	242	-	-	234	-	134	-	-	-	-	-
RAMP NW				-	-	-	-	-	-	-	-	-	-	-	-	-	200	-	-	-	-	-
RAMP EN				-	-	-	-	-	-	-	-	-	-	-	162	-	-	-	-	-	-	-
ROUNDED TOTAL				522	82	0.5	197	5395	55	140	74	392	1393	9293	1685	430	1218	1	1	1203	409	3

A A

FILE PATH = pw:\\388839-pwint.aecomonline.local:PWAECOM20\Documents\B) Americas\Transportation\EE26998 Circle\Phase II\000 CAD\095 Roadway\Sheets\60W26 Contract\D160W26-sht-Schedule-01

AECOM . TranSystems	D160W26-sht-Schedule-01	DESIGNED - OPS	REVISED - A 10/15/2013
	USER NAME = chiua	DRAWN - OPS	REVISED -
	PLOT SCALE = 50.0000 ' / in.	CHECKED - DBM	REVISED -
	PLOT DATE = 10/15/2013	DATE - 9/15/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: | SHEET 1 OF 4 SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-008R	COOK	559	34

CONTRACT NO. 60W26

ILLINOIS FED. AID PROJECT