EARTHWORK SCHEDULE

FROM STATION	TO STATION	EARTH EXCAVATION (20200100)			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS (20201200)				* EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) [EARTH EXCAVATION * 0.85]			* EMBANKMENT			* EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)			FURNISHED EXCAVATION (20400800)
					EXISTING TOPSOIL			UNDERCUT										
		CUYD			CUYD			CUYD	CUYD			CUYD			CUYD			CU YD
		STG 1	STG 2	STG 3	STG 1	STG 2	STG 3	ALL STG	STG 1	STG 2	STG 3	STG 1	STG 2	STG 3	STG 1	STG 2	STG 3	TOTAL
HALSTED STREET																		
3830+00.00	3830+15.00	2	2	0	1	0	0	-	2	2	0	0	0	0	2	2	0	
3830+15.00	3830+50.00	6	10	0	3	0	0	-	5	9	0	6	8	0	-1	1	0	
3830+50.00	3830+97.05	3	17	0	0	0	0	-	3	14	0	30	20	0	-27	-6	0	
3830+97.05	3831+00.00	0	1	0	0	0	0	-	0	1	0	3	1	0	-3	0	0	
3831+00.00	3831+50.00	4	8	0	0	0	0	-	3	7	0	35	76	14	-32	-69	-14	
3831+50.00	3832+00.00	6	14	2	0	6	3	-	5	12	2	31	78	19	-26	-66	-17	
3832+00.00	3832+50.00	3	6	2	2	12	3	-	3	5	2	57	32	6	-54	-27	-4	
3832+50.00	3832+87.05	0	0	0	3	5	0	-	0	0	0	97	62	0	-97	-62	0	
BRIDGE OMISSION																		
3837+82.72	3838+00.00	1	10	0	0	3	0	-	1	9	0	19	45	0	-18	-37	0	
3838+00.00	3838+50.00	4	20	1	10	9	0	-	3	17	1	158	119	6	-155	-102	-5	
3838+50.00	3838+56.25	1	1	0	2	0	0	-	1	1	0	26	0	1	-25	1	-1	
3838+56.25	3839+00.00	3	6	2	7	0	0	-	3	5	2	66	1	5	-63	4	-3	
3839+00.00	3839+05.00	0	1	0	0	0	0	-	0	1	0	0	0	0	0	1	0	
3839+05.00	3839+50.00	0	3	3	0	0	0	-	0	3	3	2	0	0	-2	3	3	
HALSTED STREET PIER 1		0	0	0	0	0	0	-	0	0	0	27	22	0	-27	-22	0	
HALSTED STREET PIER 2		45	45	0	0	0	0	-	38	38	0	133	146	0	-95	-108	0	
HALSTED STREET PIER 3		0	0	0	0	0	0	-	0	0	0	92	91	0	-92	-91	0	
HALSTED STREET PIER 4		0	0	0	0	0	0	-	0	0	0	111	102	0	-111	-102	0	
HALSTED STREET PIER 5		0	0	0	0	0	0	-	0	0	0	63	53	0	-63	-53	0	
HALSTED STREET PIER 6		0	0	0	0	0	0	-	0	0	0	44	57	0	-44	-57	0	
HALSTED STREET NORTH ABUTMENT		430	425	0	0	0	0	-	366	361	0	740	675	0	-375	-314	0	
SUBTOTAL		508	569	10	28	35	6	145	432	484	9	1740	1588	51	-1309	-1105	-43	2457
HARRISON STREET				A										A				
7805+00.00	7805+15.00	3	4	0	0	1	0	0	3	3	0	0	0	0	3	3	0	
7805+15.00	7805+50.00	14	15	0	0	2	0	0	12	13	0	0	9	0	12	4	0	
7805+50.00	7806+00.00	14	35	0	0	1	0	0	12	30	0	0	26	0	12	4	0	
HALSTED STREET OMISSION																		
7807+00.00	7807+25.00	14	9	0	4	3	0	3	12	8	0	1	1	0	11	7	0	
7807+25.00	7807+41.56	11	8	0	1	1	0	3	10	6	0	0	1	0	9	6	0	
7807+41.56	7807+73.85	28	19	0	3	2	0	6	24	16	0	6	8	0	18	8	0	
7807+73.85	7808+03.85	36	24	0	2	1	0	7	31	20	0	6	9	0	25	11	0	
BRIDGE OMISSION																		
7810+88.50	7810+95.70	8	5	0	1	0	0	2	7	4	0	1	1	0	6	3	0	
7810+95.70	7811+18.00	25	17	0	4	2	0	5	21	14	0	3	5	0	18	9	0	
7811+18.00	7811+50.00	20	13	0	4	2	0	4	17	11	0	3	5	0	14	6	0	
SUBTOTAL		174	149	0	18	16	0	30	148	127	0	20	65	0	128	62	0	0

* NOT A PAY ITEM.

NOTE: THE UNDERCUT QUANTITY IS ESTIMATED TO BE 10% OF THE EARTH MOVED. (EARTH MOVED = EARTH EXCAVATION + UNDERCUT)