

EARTHWORK SCHEDULE

FROM STATION	TO STATION	EARTH EXCAVATION (20200100)			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS (20201200)				EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) (EARTH EXCAVATION * 0.85)			EMBANKMENT			EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)			FURNISHED EXCAVATION (20400800)			
		CUYD			EXISTING TOPSOIL CUYD			UNDERCUT CUYD	CUYD			CUYD			CUYD			CU YD			
		STG 1	STG 2	STG 3	STG 1	STG 2	STG 3	ALL STG	STG 1	STG 2	STG 3	STG 1	STG 2	STG 3	STG 1	STG 2	STG 3	STG 1	STG 2	STG 3	TOTAL
I-90/94 SOUTHBOUND																					
8+84.73	9+00.00	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0		
9+00.00	9+13.10	1	1	0	2	1	0	1	1	1	0	0	0	0	0	1	1	0			
9+13.10	9+27.56	6	2	0	4	2	0	1	5	2	0	32	14	0	-27	-11	0				
9+27.56	9+37.97	5	2	0	4	2	0	1	4	2	0	44	19	0	-40	-17	0				
9+37.97	9+50.00	5	2	0	5	2	0	1	4	2	0	49	21	0	-45	-19	0				
9+50.00	9+92.82	20	9	0	20	8	0	4	17	7	0	176	76	0	-159	-68	0				
9+92.82	10+00.00	4	2	0	4	2	0	1	4	2	0	22	10	0	-19	-8	0				
10+00.00	10+10.17	4	2	0	7	3	0	1	3	1	0	11	5	0	-8	-3	0				
10+10.17	10+19.21	1	1	0	4	2	0	1	1	1	0	0	0	0	1	1	0				
10+19.21	10+50.00	2	1	0	0	0	0	1	2	1	0	0	0	0	2	1	0				
SUBTOTAL		49	21	0	49	21	0	12	42	18	0	334	144	0	-293	-126	0			419	
RAMP ES (INCLUDING HALSTED STREET SOUTH ABUTMENT, RETAINING WALL 016-1802, AND HARRISON STREET WEST ABUTMENT)																					
7304+50.00	7304+82.65	2	2	0	0	0	0	1	1	2	0	0	0	0	1	2	0				
7304+82.65	7305+00.00	2	2	0	0	0	0	1	1	2	0	0	0	0	1	2	0				
7305+00.00	7305+50.00	6	8	0	0	0	0	2	5	7	0	0	0	0	5	7	0				
7305+50.00	7305+87.31	50	76	0	1	2	0	14	43	64	0	74	126	11	-31	-62	-11				
7305+87.31	7306+00.00	96	143	0	2	3	0	27	81	122	0	37	64	5	44	58	-5				
7306+00.00	7306+18.11	264	397	0	4	7	0	74	225	337	0	38	65	5	187	272	-5				
7306+18.11	7306+24.65	105	157	0	2	3	0	30	89	134	0	13	23	2	76	111	-2				
7306+24.65	7306+50.00	324	487	0	7	11	0	91	276	414	0	39	66	6	237	348	-6				
7306+50.00	7307+00.00	365	547	0	11	17	0	102	310	465	0	49	83	7	261	382	-7				
7307+00.00	7307+11.99	70	105	0	6	9	0	20	60	89	0	27	47	4	32	42	-4				
7307+11.99	7307+19.63	58	88	0	5	7	0	17	50	74	0	18	30	3	32	44	-3				
7307+19.63	7307+50.00	209	313	0	11	17	0	58	177	266	0	22	38	3	155	228	-3				
7307+50.00	7308+00.00	347	521	0	26	38	0	97	295	443	0	46	79	7	249	364	-7				
7308+00.00	7308+50.00	425	638	0	29	43	0	119	361	542	0	50	85	7	312	457	-7				
7308+50.00	7308+69.01	162	242	0	10	14	0	45	137	206	0	22	37	3	116	169	-3				
7308+69.01	7308+74.74	45	68	0	3	4	0	13	38	58	0	8	14	1	30	43	-1				
7308+74.74	7308+95.62	177	266	0	9	13	0	50	151	226	0	28	49	4	122	177	-4				
7308+95.62	7309+00.00	41	62	0	2	3	0	12	35	53	0	6	10	1	29	43	-1				
7309+00.00	7309+05.02	52	79	0	3	5	0	15	45	67	0	15	26	2	29	41	-2				
7309+05.02	7309+50.00	449	674	0	22	34	0	125	382	573	0	168	288	24	214	285	-24				
7309+50.00	7309+75.79	217	326	0	6	10	0	61	185	277	0	83	142	12	102	135	-12				
7309+75.79	7309+77.87	17	26	0	1	1	0	5	15	22	0	8	13	1	7	9	-1				
7309+77.87	7309+94.44	182	272	0	6	8	0	51	154	232	0	54	92	8	100	139	-8				
7309+94.44	7310+00.00	50	75	0	2	3	0	14	43	64	0	10	17	1	33	47	-1				
7310+00.00	7310+50.00	111	167	0	6	9	0	31	95	142	0	18	31	3	76	111	-3				
7310+50.00	7311+00.00	2	2	0	0	0	0	1	1	2	0	0	0	0	1	2	0				
7311+00.00	7311+32.13	1	2	0	0	0	0	1	1	2	0	0	0	0	1	2	0				
7311+32.13	7311+50.00	0	1	0	0	0	0	1	0	1	0	0	0	0	0	1	0				
SUBTOTAL		3830	5745	0	174	261	0	1078	3256	4884	0	832	1427	119	2424	3458	-119			119	
		STG 1	STG 2	STG 3	STG 1	STG 2	STG 3	ALL STG	STG 1	STG 2	STG 3	STG 1	STG 2	STG 3	STG 1	STG 2	STG 3	TOTAL			
	TOTAL	4561	6484	10	269	333	6	1265	3878	5513	9	2926	3224	170	950	2289	-162	2995			
	ROUNDED TOTAL	11055			1875				9400			6320			3080			2995			

* NOT A PAY ITEM.

NOTE: THE UNDERCUT QUANTITY IS ESTIMATED TO BE 10% OF THE EARTH MOVED.
(EARTH MOVED = EARTH EXCAVATION + UNDERCUT)