EXISTING UTILITY STRUCTURE SCHEDULE

STATION	OFFSET	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	REMOVE EXISTING HANDHOLE	REMOVE EXISTING VALVE AND VAULT	FILLING VALVE VAULTS	FIRE HYDRANTS TO BE REMOVED	COMMENTS
		(EA)	(EA)	(EA)	(EA)	(EA)	
HALSTED STREET							
3830+10.76	45.85 RT	1					CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3830+15.64	13.79 RT	1					CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3830+20.33	10.95 LT	1					CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3830+21.27	38.52 LT		1				CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3830+25.91	17.56 LT	1					CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3830+37.59	23.22 LT	1					CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3830+72.79	14.70 RT		1				CITY OF CHICAGO ELEC MH OR HH - TO BE RECONSTRUCTED
3830+85.34	14.92 LT		1				CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3831+48.44	28.80 LT		1				CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3831+50.80	14.92 LT	1					CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3831+53.94	36.94 LT	1					CITY OF CHICAGO WATER MAIN STRUCTURE
3832+34.01	32.77 RT			1			CITY OF CHICAGO WATER MAIN STRUCTURE
3832+41.41	14.03 LT	1					CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3832+98.23	27.02 LT					1	CITY OF CHICAGO FIRE HYDRANT
3833+01.61	26.46 LT			1			CITY OF CHICAGO HYDRANT VALVE
3833+16.71	12.37 LT		1				CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3834+39.73	12.89 LT		1				CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3834+40.54	24.44 RT		1				CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3836+68.02	24.50 RT		1				CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3836+68.87	12.93 LT		1				CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3838+15.28	13.72 LT	1					CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3838+62.15	7.72 RT	1					ELECTRICAL STRUCTURE - UNKNOWN OWNER
3839+00.27	14.28 LT	1					CITY OF CHICAGO ELECTRICAL MANHOLE OR HANDHOLE
3839+16.61	21.10 LT	1					CITY OF CHICAGO WATER MAIN STRUCTURE
TOTALS		17	14	11	2	3	

A

NOTES:
THE TOTAL QUANTITY INCLUDES QUANTITY FROM SHT NO. 40.