TEMPORARY EROSION CONTROL SCHEDULE

STAGES	MULCH, METHOD 2	MULCH, METHOD 4	TEMPORARY EROSION CONTROL SEEDING	PERIMETER EROSION BARRIER	INLET FILTERS
	ACRE	ACRE	POUND	FOOT	EACH
STAGE 1A	1.44	-	288	1506	81
STAGE 1B	1.61	-	322	1947	4
STAGE 2A	-	1.57	-	2504	12
STAGE 2B	-	1.58	-	2529	-
STAGE 3	-	1.24	-	1552	-
ROUNDED TOTAL	3.25	4.50	610	10,038	97

A

A

TEMPORARY DRAINAGE SCHEDULE

STAGE	STATION	TO	STATION	UPSTREAM INVERT	DOWNSTREAM INVERT	TRENCH BACK FILL	COMBINED SEWER (EXTRA STRENGTH VITRIFIED CLAY PIPE) 8 INCH (CDOT)	COMBINED SEWER REMOVAL 8"
						CU YD	FOOT	FOOT
PRE-STAGE 1	3832+96	TO	3832+48	590.11	589.84	3.9	53	53
	3837+89	TO	3838+44	588.80	588.50	25.1	60	60
STAGE 1B	10746.08	TO	10741.88	570.21	570.29	1.5	18	18
					ROUNDED TOTAL	30.5	131	131

A

PERMANENT EROSION CONTROL SCHEDULE

	NITROGEN FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MOWING	TOPSOIL FURNISH AND PLACE, 4"	SEEDING, CLASS 2A	EROSION CONTROL BLANKET	SODDING, SALT TOLERANT	SUPPLEMENTAL WATERING
	POUND	POUND	ACRE	SQ YD	ACRE	SQ YD	SQ YD	UNIT
PERMANENT CONDITION	272	272	1.25	9078	1.25	6030	2048	20.5
ROUNDED TOTAL	272	272	1.25	9078	1.25	6030	2048	20.5