

SIGNING SCHEDULE

LOCATION	SIGN NO.	LEGEND / DESCRIPTION	CODE	ACTION	LOCATION (STATION / OFFSET)		EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		NUMBER OF POSTS	REMOVE SIGN PANEL - TYPE 1 (SQ FT)	REMOVE SIGN PANEL - TYPE 2 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY - TYPE A (EACH)	REMOVE SIGN PANEL - TYPE 3 (SQ FT)	RELOCATE SIGN PANEL - TYPE 3 (SQ FT)	SIGN PANEL - TYPE 1 (SQ FT)	SIGN PANEL - TYPE 2 (SQ FT)	SIGN PANEL - TYPE 3 (SQ FT)	SIGN PANEL - TYPE 1 (SPECIAL) (SQ FT)	
					EXISTING	PROPOSED	WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)											
EB I-290	IKE-01-BM	HALSTED STREET 800 W	CUSTOM	REMOVE AND REPLACE SIGN	351+81.16	40.1' RT	351+81.45	45.4' RT	6.50	2.00	7.00	2.00	2	13.00					14.00		
	IKE-02-TS	SPEED LIMIT	R2-1	REMOVE AND REPLACE SIGN	351+35.03	40.3' RT	351+35.03	40.3' RT	3.00	4.00	3.00	4.00	1	12.00					12.00		
WB I-290	IKE-03-BM	HALSTED STREET 800 W	CUSTOM	REMOVE AND REPLACE SIGN	352+46.58	39.5' LT	352+50.83	36.2' LT	6.50	2.00	7.00	2.00	2	13.00					14.00		
SOUTHWEST RAMP	SW-01-BS	UNIVERSITY OF ILLINOIS AT CHICAGO NEXT 2 EXITS	CUSTOM	RELOCATED ON NEW POSTS	19+70.95	33.9' RT	19+75.92	33.0' RT	12.00	9.00	12.00	9.00	2			108.00	108.00				
EASTSOUTH RAMP	ES-03-TM	RAMP SPEED LIMIT 30	W13-3	REMOVE AND REPLACE SIGN	106+51.75	49.9' LT	106+37.41	46.8' LT	3.00	4.00	3.00	4.00		12.00						12.00	
	ES-04-BM	DOUBLE ARROWS	W12-1	REMOVE AND REPLACE SIGN	106+85.82	18.9' LT	106+80.99	16.0' LT	4.00	4.00	4.00	4.00	2	16.00							16.00
TAYLOR EXIT RAMP	EXIT NO.	EXIT 52A	CUSTOM	PROPOSED SIGN	-	-	7308+51.00	148.3' LT	-	-	11.50	2.50	-							28.75	
	ES-01-GM	TAYLOR STREET/ROOSEVELT ROAD 1/4 MILE	CUSTOM	PROPOSED SIGN	-	-	7308+50.00	148.3' LT	-	-	16.00	11.00	2							176.00	
	-	EXIT 52A - TAYLOR STREET/ROOSEVELT ROAD 1/4 MILE	CUSTOM	RELOCATE SIGN	7809+00.00	33.0' LT	7308+50.00	12.7' LT	16.50	11.00	-	-	2				181.50				
NORTHWEST RAMP	NW-01-BM	ADDED LANE	W4-3R	REMOVE AND REPLACE SIGN	21+78.14	16.1' RT	21+79.19	15.9' RT	4.00	4.00	4.00	4.00	2	16.00						16.00	
ROUNDED SUBTOTAL												0	82	0	108	290	0	84	205	0	
TOTAL												85	82	1	108	290	59	84	205	46	

LOCATION	SIGN NO.	LEGEND / DESCRIPTION	CODE	ACTION	LOCATION (STATION / OFFSET)		EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		NUMBER OF POSTS	TELESCOPING STEEL SIGN SUPPORT (FT)	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY (LBS)	STEEL POST, SPECIAL (EACH)	REMOVE GROUND MOUNTED SIGN SUPPORT (EACH)	REMOVE CONCRETE FOUNDATION - GROUND MOUNT (EACH)	CONCRETE FOUNDATIONS (CU YDS)	WOOD SIGN SUPPORT (FT)		
					EXISTING	PROPOSED	WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)										
EB I-290	IKE-01-BM	HALSTED STREET 800 W	CUSTOM	REMOVE AND REPLACE SIGN	351+81.16	40.1' RT	351+81.45	45.4' RT	6.50	2.00	7.00	2.00	2	28.00						
	IKE-02-TS	SPEED LIMIT	R2-1	REMOVE AND REPLACE SIGN	351+35.03	40.3' RT	351+35.03	40.3' RT	3.00	4.00	3.00	4.00	1	16.00			1			
WB I-290	IKE-03-BM	HALSTED STREET 800 W	CUSTOM	REMOVE AND REPLACE SIGN	352+46.58	39.5' LT	352+50.83	36.2' LT	6.50	2.00	7.00	2.00	2	28.00						
SOUTHWEST RAMP	SW-01-BS	UNIVERSITY OF ILLINOIS AT CHICAGO NEXT 2 EXITS	CUSTOM	RELOCATED ON NEW POSTS	19+70.95	33.9' RT	19+75.92	33.0' RT	12.00	9.00	12.00	9.00	2				2	2	0.3	35.60
EASTSOUTH RAMP	ES-03-TM	RAMP SPEED LIMIT 30	W13-3	REMOVE AND REPLACE SIGN	106+51.75	49.9' LT	106+37.41	46.8' LT	3.00	4.00	3.00	4.00								
	ES-04-BM	DOUBLE ARROWS	W12-1	REMOVE AND REPLACE SIGN	106+85.82	18.9' LT	106+80.99	16.0' LT	4.00	4.00	4.00	4.00	2	32.00						
TAYLOR EXIT RAMP	EXIT NO.	EXIT 52A	CUSTOM	PROPOSED SIGN	-	-	7308+51.00	148.3' LT	-	-	11.50	2.50	-							
	ES-01-GM	TAYLOR STREET/ROOSEVELT ROAD 1/4 MILE	CUSTOM	PROPOSED SIGN	-	-	7308+50.00	148.3' LT	-	-	16.00	11.00	2		1170.00				2.54	
	-	EXIT 52A - TAYLOR STREET/ROOSEVELT ROAD 1/4 MILE	CUSTOM	RELOCATE SIGN	7809+00.00	33.0' LT	7308+50.00	12.7' LT	16.50	11.00	-	-	2		1144.00				2.54	
NORTHWEST RAMP	NW-01-BM	ADDED LANE	W4-3R	REMOVE AND REPLACE SIGN	21+78.14	16.1' RT	21+79.19	15.9' RT	4.00	4.00	4.00	4.00	2	32.00						
ROUNDED SUBTOTAL												136	2314	0	3	2	5.4	36		
TOTAL												151	2314	4	5	2	5.4	36		



D168W26-shr-Sign-Schedule-824
 USER NAME = pimsarno
 PLOT SCALE = 50.0000' / 1"
 PLOT DATE = 10/13/2013

DESIGNED - OPS
 DRAWN - OPS
 CHECKED - DBM
 DATE - 9/15/13

REVISED - 10/15/2013
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SIGNING SCHEDULE

SCALE: SHEET 2A OF 6 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94/290	2013-008R	COOK	559	184A
CONTRACT NO. 60W26				
ILLINOIS FED. AID PROJECT				