



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 29, 2013

SUBJECT: FAI Route 57(I-57)  
Section 2013-025-I  
Cook County  
Contract No. 60W60  
Item No. 4, November 8, 2013 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Added pages 133-134 to the Special Provisions.
4. Revised sheets 1, 2 & 3 of the Plans.
5. Added sheets 19A-19F to the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in cursive script, appearing to read "Ted B. Walschleger" followed by a small "P.E." to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: John Fortmann, Region 1, District 1; Tim Kell; D. Carl Puzey; Estimates

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES

CONTRACT  
NUMBER -

60W60

State Job # - C-91-343-13

Project Number

Route

County Name - COOK - -

FAI 57

Code - 31 - -

\*REVISED: OCTOBER 29, 2013

District - 1 - -

Section Number - 2013-025-I

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
*ADD X7010216	TRAF CONT & PROT SPL	L SUM	1.000				
X7011015	TR C-PROT EXPRESSWAYS	L SUM	1.000				
X7013820	TR CONT SURVEIL EXPWY	CAL DA	35.000				
X7030030	WET REF TEM TAPE T3 4	FOOT	13,118.000				
X7030035	WET REF TEM TAPE T3 5	FOOT	1,640.000				
Z0001800	APPROACH SL REP (PD)	SQ YD	16.000				
Z0016001	DECK SLAB REP (FD-T1)	SQ YD	51.000				
Z0016200	DECK SLAB REP (PART)	SQ YD	182.000				
Z0018010	DRAINAGE SCUPPR DS-33	EACH	6.000				
*ADD Z0030850	TEMP INFO SIGNING	SQ FT	1,342.000				
40603340	HMA SC "D" N70	TON	74.000				
44000157	HMA SURF REM 2	SQ YD	653.000				
44200610	CL A PATCH T2 13	SQ YD	8.000				
44213000	PATCH REINFORCEMENT	SQ YD	8.000				
50102400	CONC REM	CU YD	41.700				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

60W60

State Job # - C-91-343-13

Project Number

Route

County Name - COOK - -

FAI 57

Code - 31 - -

\*REVISED: OCTOBER 29, 2013

District - 1 - -

Section Number - 2013-025-I

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
50300255	CONC SUP-STR	CU YD	42.500				
50800205	REINF BARS, EPOXY CTD	POUND	9,100.000				
50800515	BAR SPLICERS	EACH	72.000				
52000110	PREF JT STRIP SEAL	FOOT	240.000				
64200116	SHOULDER RUM STRIP 16	FOOT	4,402.000				
67000400	ENGR FIELD OFFICE A	CAL MO	6.000				
67100100	MOBILIZATION	L SUM	1.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	2.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	5,057.000				
70400100	TEMP CONC BARRIER	FOOT	1,450.000				
70400200	REL TEMP CONC BARRIER	FOOT	1,450.000				
70600250	IMP ATTN TEMP NRD TL3	EACH	2.000				
70600350	IMP ATTN REL NRD TL3	EACH	2.000				
*ADD 72700100	STR STL SIN SUP BA	POUND	8,684.000				
*ADD 73400100	CONC FOUNDATION	CU YD	19.240				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SCHEDULE OF PRICES

CONTRACT  
NUMBER -

60W60

State Job # - C-91-343-13

Project Number

Route

County Name - COOK - -

FAI 57

Code - 31 - -

\*REVISED: OCTOBER 29, 2013

District - 1 - -

Section Number - 2013-025-I

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78008210	POLYUREA PM T1 LN 4	FOOT	6,559.000				
78008220	POLYUREA PM T1 LN 5	FOOT	1,640.000				
78008250	POLYUREA PM T1 LN 12	FOOT	686.000				
78100300	REPLACEMENT REFLECTOR	EACH	165.000				
78200530	BAR WALL MKR TYPE C	EACH	110.000				
78300100	PAVT MARKING REMOVAL	SQ FT	6,413.000				

UTILITY COORDINATION AND CONFLICTS (BDE)..... 119  
WARM MIX ASPHALT (BDE) ..... 125  
WEEKLY DBE TRUCKING REPORTS (BDE)..... 128  
WORKING DAYS (BDE) ..... 129  
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) ..... 129  
TEMPORARY INFORMATION SIGNING ..... 133  
TRAFFIC CONTROL AND PROTECTION (ARTERIALS) ..... 134

Revised 10/29/13

## TEMPORARY INFORMATION SIGNING

Effective: November 13, 1996

Revised: January 2, 2007

### Description.

This work shall consist of furnishing, installing, maintaining, relocating for various states of construction and eventually removing temporary informational signs. Included in this item may be ground mount signs, skid mount signs, truss mount signs, bridge mount signs, and overlay sign panels which cover portions of existing signs.

### Materials.

Materials shall be according to the following Articles of Section 1000 - Materials:

	<u>Item</u>	<u>Article/Section</u>
a.)	Sign Base (Notes 1 & 2)	1090
b.)	Sign Face ( Note 3)	1091
c.)	Sign Legends	1092
d.)	Sign Supports	1093
e.)	Overlay Panels (Note 4)	1090.02

Note 1. The Contractor may use 5/8 inch (16 mm) instead of 3/4 inch (19 mm) thick plywood.

Note 2. Type A sheeting can be used on the plywood base.

Note 3. All sign faces shall be Type A except all orange signs shall meet the requirements of Article 1106.01.

Note 4. The overlay panels shall be 0.08 inch (2 mm) thick.

## GENERAL CONSTRUCTION REQUIREMENTS

### Installation.

The sign sizes and legend sizes shall be verified by the Contractor prior to fabrication.

Signs which are placed along the roadway and/or within the construction zone shall be installed according to the requirements of Article 701.14 and Article 720.04. The signs shall be 7 ft (2.1 m) above the near edge of the pavement and shall be a minimum of 2 ft (600 mm) beyond the edge of the paved shoulder. A minimum of two (2) posts shall be used.

The attachment of temporary signs to existing sign structures or sign panels shall be approved by the Engineer. Any damage to the existing signs due to the Contractor's operations shall be repaired or signs replaced, as determined by the Engineer, at the Contractor's expense.

Signs which are placed on overhead bridge structures shall be fastened to the handrail with stainless steel bands. These signs shall rest on the concrete parapet where possible. The Contractor shall furnish mounting details for approval by the Engineer.

### Method Of Measurement.

This work shall be measured for payment in square feet (square meters) edge to edge (horizontally and vertically).

Added 10/29/13

All hardware, posts or skids, supports, bases for ground mounted signs, connections, which are required for mounting these signs will be included as part of this pay item.

Basis Of Payment.

This work shall be paid for at the contract unit price per square foot (square meter) for TEMPORARY INFORMATION SIGNING.

**TRAFFIC CONTROL AND PROTECTION (ARTERIALS)**

Effective: February 1, 1996

Revised: March 1, 2011

Specific traffic control plan details and Special Provisions have been prepared for this contract. This work shall include all labor, materials, transportation, handling and incidental work necessary to furnish, install, maintain and remove all traffic control devices required as indicated in the plans and as approved by the Engineer.

When traffic is to be directed over a detour route, the Contractor shall furnish, erect, maintain and remove all applicable traffic control devices along the detour route according to the details shown in the plans.

Method of Measurement: All traffic control (except "Traffic Control and Protection (Expressways)" and temporary pavement markings) indicated on the traffic control plan details and specified in the Special Provisions will be measured for payment on a lump sum basis.

Basis of Payment: All traffic control and protection will be paid for at the contract lump sum price for TRAFFIC CONTROL AND PROTECTION (SPECIAL).

Temporary pavement markings will be paid for separately unless shown on a Standard.