

PAVEMENT SCHEDULE

LOCATION	OFFSET	21001000	30300112	30300121	30300124	30300127	40600200	40603080	40603310	42000301	42000416	42400200	X4200500	Z0028415	
		GEO FABRIC FOR GROUND STABILIZATION	AGG SUBGRADE IMPR 12"	AGG SUBGRADE IMPR 21"	AGG SUBGRADE IMPR 24"	AGG SUBGRADE IMPR 27"	BIT MATLS PR CT	HMA BIND, IL-19.0, N50	HMA SC "C" N50	PCC PVT 8 JOINTED	PCC PVT 9 3/4 JOINTED	PCC SIDEWALKS 5"	HES PCC PVT 9 3/4 JOINTED	GEOTECHNICAL REINF	
STATION TO STATION		SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	SQ YD	SQ YD	SQ FT	SQ YD	SQ YD	
PERRYVILLE ROAD															
243+47	248+92	RT	501.3								460.9			501.3	
243+47	248+92	LT	457.3								361.4			457.3	
251+86	255+47	RT	918.2								668.6			918.2	
251+86	255+47	LT	1,031.2								948.8			1,031.2	
MITCHELL ROAD															
232+01.19	234+00	RT	508.1				0.68	80.0	53.3					508.1	
232+01.19	234+00	LT	488.4				0.60	70.6	47.1					488.4	
234+00	238+75	RT	901.8				1.25	147.1	98.0					901.8	
234+00	238+75	LT	909.5				1.25	146.6	97.7					909.5	
CONTRACTORS DRIVE /															
KRASSE DRIVE															
6+35	9+01.50	RT	385.9				0.53	62.0	41.5					449.5	
6+35	9+01.50	LT	1,226.8				1.64	192.3	128.2					1,274.9	
11+29	12+45	RT	189.2				0.22	26.4	17.6					189.2	
11+29	12+45	LT	358.2				0.46	54.2	36.1					358.2	
IL 173 SPEEDWAY															
NORTH ENTRANCE															
298+38	298+90.88	RT	86.3				0.11	12.9	8.6					86.3	
298+38	298+90.88	LT	107.1				0.13	14.7	9.8					107.1	
MENARDS															
SOUTH ENTRANCE															
131+02.74	132+00	RT	177.9				0.21	24.4	16.2					177.9	
131+02.74	132+00	LT	173.6				0.20	23.6	15.7					173.6	
SPEEDWAY															
EAST ENTRANCE															
97+30	99+60.00	RT	558.1				0.64	75.2	50.1					558.1	
97+30	99+60.00	LT	554.8				0.65	76.0	50.6					554.8	
IL 173 OSF ENTRANCE															
38+00	38+70.08	RT	121.7				0.15	17.1	11.4			342.2		121.7	
38+00	38+70.08	LT	133.0				0.16	18.9	12.6			313.7		133.0	
ANJALI WAY															
1236+73.80	1236+18.00	LT	304.2				0.40	44.3	29.6					304.2	
SUBTOTAL (SHEET 3)			0.00	10,092.7	0.0	0.0	0.0	9.28	1,086.3	724.2	0.0	2,439.7	656.0	0.0	10,204.4
TOTALS			62,446	113,091	52,086	2,724	4,750	12	1,391	927	25,059	108,263	725	8,494	111,210

FILE NAME = ...\\CADD SHEETS\Z00793CVR-S003.dgn
THE UPCHURCH GROUP, INC.

USER NAME = Elgin 110
 DESIGNED - MJS
 DRAWN - JAU
 CHECKED - RLH
 DATE -
 PLOT SCALE = 2.0000' / IN.
 PLOT DATE = 7/22/2013 1:21:43 PM

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
 PAVEMENT SCHEDULE**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129R	WINNEBAGO	968	62
ILLINOIS FED. AID PROJECT			CONTRACT NO. 64988	