

## PIPE CULVERTS

STATIONING	OFFSET	542A0223	542A0229	542A1069	542A1081	542A1093	542A1105	542A8221	542A8233	542A8245	542C8221
		PIPE CULVERTS, CLASS A, TYPE 1, 18"	PIPE CULVERTS, CLASS A, TYPE 1, 24"	PIPE CULVERTS, CLASS A, TYPE 2, 24"	PIPE CULVERTS, CLASS A, TYPE 2, 36"	PIPE CULVERTS, CLASS A, TYPE 2, 48"	PIPE CULVERTS, CLASS A, TYPE 2, 60"	PIPE CULVERTS, CLASS A, TYPE 2 EQUIVALENT ROUND - SIZE 36"	PIPE CULVERTS, CLASS A, TYPE 2 EQUIVALENT ROUND - SIZE 48"	PIPE CULVERTS, CLASS A, TYPE 2 EQUIVALENT ROUND - SIZE 60"	PIPE CULVERTS, CLASS C, TYPE 2 EQUIVALENT ROUND - SIZE 36"
		L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.	L.F.
<b>IL 173</b>											
1066+80	79.2' RT TO 88.0' LT								167		
1073+16	90.3' RT TO 119.3 LT							210			
1075+34.83	149.1' RT TO 120.9' RT							30			
1075+47	82.0' RT TO 81.5' LT								164		
1078+14	65.0' RT TO 75.4' LT						141				
1095+44	61.0' RT TO 61.8' LT								123		
1109+01	62.0' RT TO 63.7' LT					126					
1113+13.90	72.0' RT TO 72.0' RT				24						
1119+05	70.0' RT TO 74.0' LT									144	
1125+39	58.3' RT TO 68.5' LT								146		
1130+86	60.0' RT TO 63.0' LT								123		
1142+84.81	19.50' RT TO 0.50' LT							20			
<b>PERRYVILLE ROAD</b>											
252+26.73	113.13' RT TO 73.5' RT							73			
<b>FOREST HILLS ROAD</b>											
376+67.44	20.2' LT TO 21.9' LT	2									
386+88	32.2' RT TO 42.2' LT		75								
396+61	75.6' RT TO 57.3' LT		133								
453+70.26	59.0' RT TO 63.2' RT		36								
455+56.53	60.5' RT TO 57.1' RT		71								
460+53	40.0' RT TO 46.15' LT	93									
465+98.76	30.3' LT TO 34.4' LT										4
<b>MITCHELL ROAD</b>											
234+83.73	54.5' RT TO 52.9' RT		52								
234+83.73	64.24' LT TO 58.0' LT			85							
236+79.19	46.4' LT TO 44.4' LT		45								
<b>OSF NORTH ENTRANCE</b>											
38+73	40.1' LT TO 33.8' RT			74							
<b>TOTALS</b>		95	412	159	24	126	141	333	723	144	4

FILE NAME = ...\\CADD SHEETS\2007\93CVR-S008.dgn	USER NAME = Elgin 110	DESIGNED - MJS	REVISED -
		DRAWN - JAU	REVISED -
		CHECKED - RLH	REVISED -
		DATE - APRIL 30, 2013	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES PIPE CULVERTS			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129R	WINNEBAGO	968	67
CONTRACT NO. 64988				
ILLINOIS FED. AID PROJECT				

**THE UPCHURCH GROUP, INC.**