

DRAINAGE STRUCTURE SCHEDULE

SHEET	DESC.	STATION	OFFSET	PAY ITEM NUMBER															Note: See Sheet 186 FOR LOCATION OF PIPE UNDERDRAIN				60107600		DESC.									
				60218400	60219300	60222000	60223800	60224443	60224459	60234200	60240310	60246805	X6024240	X6024246	X6024248	X6024250	X6024254	54261415	54261418	54261430														
				INLETS AND MANHOLES												END SECTIONS																		
				MAN TA 4 DIA T1F CL	MAN TA 4 DIA T11F&G	MAN TA 5 DIA T11F&G	MAN TA 6 DIA T1F CL	MAN TA 7 DIA T11 F&G	MAN TA 8 DIA T1F CL	INLETS TA T1F OL	INLETS TB T11F&G	MEDIAN INLET (604106)	INLETS, SPECIAL	INLETS SPL N3	INLETS SPL N4	INLETS SPL N5	INLETS SPL N7	CONC END SEC STD 542001 15" 1:4	CONC END SEC STD 542001 18" 1:4	CONC END SEC STD 542001 30" 1:4	COMMENT / OTHER				RIMELEV	INVERT ELEV				PIPE UNDER DRAIN 4"				
				EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH	EACH			N	S	E	W								
IL 173																																		
D2	107	1022+63.68	8' RT								1																				107			
D2	108	1024+55.64	42.83' LT													1															E W 108			
D2	109	1024+54.84	2.17' LT		1																										109			
D2	110	1024+52.54	50.31' RT													1															E W 110			
D2	111	1025+35	4.15' LT								1																				734.82 E 111			
D2	112	1026+46.35	40' LT													1															W 112			
D2	113	1026+45.80	8' LT		1																										E W 113			
D2	114	1026+43.77	52' RT													1															E W 114			
D3	115	1027+55.03	8.0' LT								1																				W 115			
D3	116	1029+75	34.0' LT						1																S.P. PreStage Drainage	741.06	736.31	730.97		730.77		116		
D3	117	1029+30	8' RT								1																					E 117		
D3	118	1029+75	52' LT													1																E 118		
D3	119	1029+75	8' RT					1																	S.P. PreStage Drainage	741.42	731.01	731.11	736.36	736.36		E W 119		
D3	120	1029+75	42.67' RT														1								S.P. PreStage Drainage	740.86	731.14		732.18			E 120		
D3	121	1030+40	8' RT								1																					E W 121		
D3	122	1031+10	52' LT													1																E W 122		
D3	123	1031+10	8' RT								1															S.P. PreStage Drainage	741.85	734.51	734.51				E W 123	
D3	124	1031+10	40' RT														1									S.P. PreStage Drainage	741.37	734.35		732.74	732.31		E W 124	
D3	125	1032+65	49.04' LT													1																E W 125		
D3	126	1032+65	3.37' RT								1															S.P. PreStage Drainage	742.60	736.20	736.10				E 126	
D3	127	1032+65	49.04' RT														1									S.P. PreStage Drainage	741.72	735.86		733.66	732.85		E W 127	
D4	128	1034+20	40' LT													1																E W 128		
D4	129	1034+20	8' LT								1																S.P. PreStage Drainage	743.36	738.47	737.37				E W 129
D4	130	1034+20	52' RT														1									S.P. PreStage Drainage	742.58	737.06		735.32	733.77		E W 130	
D4	131	1035+70.12	42.19' LT													1																E W 131		
D4	132	1035+70	8' LT								1																S.P. PreStage Drainage	744.64	739.37	739.27				W 132
D4	133	1035+70	52.89' RT														1									S.P. PreStage Drainage	743.82	738.96		736.21	735.51		W 133	
D4	137	1037+12.92	79.41' RT													1																N 137		
D4	138	1037+22.90	96.12' LT													1																S 138		
D4	139	1038+00	52' LT													1																E W 139		
D4	140	1038+00	8' RT								1																S.P. PreStage Drainage	747.01	739.73	739.73				E 140
D4	141	1037+99.70	43.13' RT														1										S.P. PreStage Drainage	746.47	739.55	739.90	738.48	736.44		E W 141
D4	142	1038+00	59.9' RT									1																				740.14 142		
SUBTOTAL (SHEET 1)				0	2	0	0	1	1	0	10	1	0	0	0	12	6	0	0	0														

* CONTRACTOR TO VERIFY INVERTS

FILE NAME = ... \CADD SHEETS\Z00793CVR-S001.dgn	USER NAME = Elgin 110	DESIGNED - MJS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES DRAINAGE STRUCTURE SCHEDULE	F.A.P. RTE. 303	SECTION 129R	COUNTY WINNEBAGO	TOTAL SHEETS 968	SHEET NO. 84	
PLOT SCALE = 2.0000' / IN.	CHECKED - RLH	REVISED -	REVISED -			SCALE:	SHEET NO. OF SHEETS STA. TO STA.	CONTRACT NO. 64988			
PLOT DATE = 5/3/2013 4:26:32 PM	DATE - APRIL 30, 2013	REVISED -	REVISED -			ILLINOIS FED. AID PROJECT					