

NEW MEDIAN AND ISLAND SCHEDULE

			35100700	60618300	60618800	X0540000	X6061100	XX008705
LOCATION			AGGREGATE BASE COURSE, TYPE A, 8"	CONCRETE MEDIAN SURFACE, 4"	CONCRETE MEDIAN, TYPE SB	BRICK PAVERS	CONCRETE MEDIAN, TYPE SB (SPECIAL)	CONCRETE ISLAND (SPECIAL)
STATION TO STATION	OFFSET		SQ YD	SQ FT	SQ FT	SQ FT	SQ FT	SQ FT
IL 173								
1009+00	1015+00	RT				508	963	
1009+00	1015+00	LT						
1015+00	1021+00	RT				670	1,216	
1015+00	1021+00	LT				1,136	2,153	
1021+00	1027+00	RT				1,538	2,945	
1021+00	1027+00	LT				1,020	1,865	
1027+00	1033+00	RT				1,949	2,781	894
1027+00	1033+00	LT				823	972	920
1033+00	1039+00	RT				904	1,284	626
1033+00	1039+00	LT				1,776	2,457	923
1039+00	1045+00	RT				1,091	2,013	
1039+00	1045+00	LT				1,467	2,797	
1045+00	1051+00	RT				1,966	3,381	578
1045+00	1051+00	LT				480	429	517
1051+00	1057+00	RT				744	1,290	
1051+00	1057+00	LT				2,294	3,520	711
1057+00	1063+00	RT				2,483	2,200	1,875
1057+00	1063+00	LT				1,632	1,198	2,019
1063+00	1069+00	RT				2,082	3,088	636
1063+00	1069+00	LT				954	1,726	
1069+00	1072+00	RT						
1069+00	1072+00	LT				1,151	2,402	
1072+00	1078+00	RT				1,929	2,243	1,412
1072+00	1078+00	LT				949	1,171	969
1078+00	1084+00	RT	211			2,651	1,795	
1078+00	1084+00	LT	128			996		
1084+00	1090+00	RT	152			1,247		
1084+00	1090+00	LT	286			2,251		
1090+00	1093+00	RT	117			900		
1090+00	1093+00	LT	117			900		
1093+00	1099+00	RT	210			1,687		
1093+00	1099+00	LT	274			2,090		
1099+00	1105+00	RT	189			1,460		
1099+00	1105+00	LT	243			1,939		
1105+00	1111+00	RT	171			1,323		
1105+00	1111+00	LT	252			2,042	930	
1111+00	1117+00	RT	113			875		
1111+00	1117+00	LT	149			2,735	1,596	1,446
1117+00	1123+00	RT	234			1,806		
SUBTOTAL			2,846	-	-	54,448	48,414	13,525

			35100700	60618300	60618800	X0540000	X6061100	XX008705
LOCATION			AGGREGATE BASE COURSE, TYPE A, 8"	CONCRETE MEDIAN SURFACE, 4"	CONCRETE MEDIAN, TYPE SB	BRICK PAVERS	CONCRETE MEDIAN, TYPE SB (SPECIAL)	CONCRETE ISLAND (SPECIAL)
STATION TO STATION	OFFSET		SQ YD	SQ FT	SQ FT	SQ FT	SQ FT	SQ FT
1117+00	1123+00	LT	233			1,795		
1123+00	1129+00	RT	165			1,345		
1123+00	1129+00	LT	284			2,228		
1129+00	1135+00	RT	228			1,774		
1129+00	1135+00	LT	240			1,810		
1135+00	1141+00	RT	172			1,377		
1135+00	1141+00	LT	280			2,216		
1141+00	1147+00	RT	218			1,729		
1141+00	1147+00	LT	249			1,800		
1147+00	1153+00	RT	181			1,417		
1147+00	1153+00	LT	268			2,155		
1153+00	1154+50	RT	58			450		
1153+00	1154+50	LT	58			450		
1154+50	156+00	RT	69			538		
1154+50	156+00	LT	73			547		
FOREST HILLS ROAD								
380+96	399+13	RT		2,743	1,337			
380+96	399+13	LT		305	3,619			
450+91	466+17	RT			2,852			
460+91	466+17	LT			1,818			
PERRYVILLE ROAD								
243+47	245+43	RT		1,327				
243+47	245+43	LT		2,467				
245+43	249+50	LT			2,697			
251+30	255+06	RT			2,832			
255+06	255+47	RT		359				
FOREST HILLS LODGE ENTRANCE								
214+25	214+52.37				103			
SUBTOTAL			2,776	7,201	15,258	21,631	-	-
TOTAL			5,622	7,201	15,258	76,079	48,414	13,525

FILE NAME = ...\\CADD SHEETS\Z00793CVR-S007.dgn	USER NAME = Elgin 110	DESIGNED - MJS	REVISED -
		DRAWN - JAU	REVISED -
		CHECKED - RLH	REVISED -
		DATE - APRIL 30, 2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES MEDIAN SCHEDULE			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129R	WINNEBAGO	968	97
				CONTRACT NO. 64988
ILLINOIS FED. AID PROJECT				

THE UPCHURCH GROUP, INC.