

FURNISHING AND ERECTING RIGHT OF WAY MARKERS (6660105)

IL 173 FROM ALPINE ROAD TO I-90			
STATION	OFFSET		EACH
1027+59.30	63.58'	LT	1
1027+75.00	75.00'	RT	1
1027+86.09	85.00'	LT	1
1029+00.00	76.40'	RT	1
1029+43.57	65.00'	LT	1
1029+50.00	60.00'	RT	1
1032+50.00	60.00'	RT	1
1032+50.00	61.00'	RT	1
1034+55.00	62.00'	LT	1
1035+50.00	65.00'	RT	1
1036+05.00	75.00'	RT	1
1036+06.32	32.00'	LT	1
1036+16.04	85.00'	RT	1
1036+20.40	100.00'	RT	1
1036+45.98	81.72'	LT	1
1037+45.25	100.00'	LT	1
1037+63.09	65.00'	LT	1
1038+00.00	90.00'	RT	1
1038+89.28	65.00'	LT	1
1038+89.35	75.00'	LT	1
1041+50.00	80.00'	RT	1
1043+00.00	70.00'	RT	1
1044+00.00	75.00'	RT	1
1045+00.00	75.00'	LT	1
1046+99.99	70.00'	LT	1
1050+75.00	75.00'	RT	1
1053+00.00	85.00'	RT	1
1053+40.00	70.00'	LT	1
1053+50.64	100.00'	LT	1
1053+90.64	100.00'	LT	1
1054+05.00	70.00'	LT	1
1054+71.74	65.00'	LT	1
1058+00.00	100.00'	RT	1
1058+55.00	142.88'	LT	1
1061+00.00	110.00'	LT	1
1062+29.70	121.92'	LT	1
1062+99.59	64.84'	RT	1
1063+45.00	118.94'	LT	1
1063+50.00	82.00'	RT	1
1064+00.00	160.00'	LT	1
1065+00.00	110.00'	RT	1
1067+00.00	145.00'	LT	1
1067+18.23	115.00'	RT	1
1067+78.98	115.00'	RT	1
1069+00.00	118.00'	RT	1
1070+94.65	117.83'	RT	1
1071+04.64	161.13'	LT	1
1072+81.45	115.00'	RT	1
1072+87.86	178.69'	LT	1
1073+15.00	185.00'	LT	1
1076+35.00	151.28'	LT	1
1079+50.00	150.00'	LT	1
1080+00.00	145.00'	LT	1
1080+60.00	86.00'	LT	1
1099+63.40	101.00'	LT	1

1100+00.42	100.99'	LT	1
1101+00.42	90.98'	LT	1
1106+00.00	85.00'	LT	1
1108+75.00	75.00'	LT	1
1108+85.00	120.00'	LT	1
1109+15.00	120.00'	LT	1
1109+25.00	95.12'	LT	1
1111+00.00	90.00'	LT	1
1112+00.00	95.00'	LT	1
1112+40.00	100.00'	LT	1
1115+00.00	155.00'	LT	1
1116+00.00	150.00'	LT	1
1118+00.00	150.00'	LT	1
1121+00.00	145.00'	LT	1
1124+00.00	150.00'	LT	1
1125+00.00	140.00'	LT	1
1132+00.00	145.00'	LT	1
1134+00.00	140.00'	LT	1
1136+00.00	140.00'	LT	1
1137+50.00	165.00'	LT	1
1139+00.00	170.00'	LT	1
1140+50.00	170.00'	LT	1
1143+00.00	90.44'	LT	1
TOTAL			78

CONTINENTAL DRIVE			
STATION	OFFSET		EACH
88+75.00	22.56'	RT	1
88+75.00	55.83'	LT	1
89+00.00	60.00'	LT	1
89+00.62	22.58'	RT	1
90+98.25	36.60'	LT	1
91+17.00	40.11'	RT	1
91+17.07	31.99'	LT	1
91+40.52	31.90'	LT	1
91+40.48	33.83'	RT	1
TOTAL			9

KIMBER DRIVE			
STATION	OFFSET		EACH
101+08.00	47.59'	RT	1
101+08.51	29.59'	LT	1
TOTAL			2

BURDEN ROAD			
STATION	OFFSET		EACH
216+00.00	55.00'	LT	1
216+30.00	60.00'	RT	1
217+25.00	60.00'	RT	1
217+45.00	50.00'	LT	1
217+50.00	40.07'	LT	1
217+50.00	49.93'	RT	1
TOTAL			6

FOREST HILLS ROAD			
STATION	OFFSET		EACH
382+80.00	50.01'	LT	1
382+98.83	60.00'	LT	1
383+64.88	60.00'	LT	1
385+37.87	60.00'	LT	1
389+65.64	70.00'	RT	1
390+50.00	80.00'	LT	1
395+00.00	70.00'	RT	1
395+50.00	80.00'	RT	1
396+00.00	80.00'	RT	1
396+00.00	80.00'	LT	1
396+50.00	90.00'	RT	1
397+25.00	91.69'	RT	1
398+00.00	80.00'	LT	1
398+50.00	93.00'	LT	1
451+50.00	85.00'	RT	1
452+00.00	70.00'	RT	1
453+00.00	68.46'	LT	1
453+00.00	70.00'	RT	1
453+35.00	65.00'	LT	1
453+50.00	80.00'	RT	1
454+00.00	90.00'	LT	1
454+99.59	80.00'	RT	1
455+00.00	90.00'	LT	1
456+00.00	60.00'	RT	1
456+00.00	90.00'	LT	1
456+50.00	60.00'	RT	1
457+00.00	60.00'	RT	1
457+50.00	60.00'	RT	1
457+50.00	90.00'	LT	1
457+96.85	60.00'	LT	1
458+00.58	60.00'	RT	1
458+62.55	79.98'	RT	1
458+85.00	65.00'	RT	1
459+00.00	70.00'	LT	1
460+15.00	70.00'	RT	1
460+50.00	56.00'	RT	1
462+00.00	55.00'	RT	1
462+45.00	70.00'	LT	1
462+54.37	39.38'	RT	1
463+00.00	39.39'	RT	1
463+50.00	50.00'	LT	1
463+50.00	70.00'	RT	1
464+01.71	70.00'	RT	1
464+64.84	69.96'	RT	1
466+00.00	50.00'	LT	1
466+00.00	70.00'	RT	1
466+39.54	39.54'	RT	1
466+25.00	40.46'	LT	1
TOTAL			48

PERRYVILLE ROAD			
STATION	OFFSET		EACH
245+85.00	149.95'	LT	1
245+85.00	150.01'	RT	1
252+40.00	100.00'	LT	1
253+73.93	100.00'	LT	1
253+73.93	100.00'	RT	1
TOTAL			5

MITCHELL ROAD			
STATION	OFFSET		EACH
232+00.00	100.00'	LT	1
233+00.00	70.00'	RT	1
233+51.49	100.00'	LT	1
233+79.55	70.00'	RT	1
234+49.95	75.00'	LT	1
235+16.04	85.00'	LT	1
235+50.00	70.00'	RT	1
236+00.00	75.00'	LT	1
236+50.00	67.50'	RT	1
237+00.00	55.00'	LT	1
238+22.96	70.44'	RT	1
238+25.00	55.00'	LT	1
238+45.00	35.98'	LT	1
238+50.00	65.00'	RT	1
239+00.00	47.31'	RT	1
TOTAL			15

CONTRACTORS DRIVE & KRASS ROAD			
STATION	OFFSET		EACH
7+50.00	28.06'	LT	1
8+40.00	95.00'	LT	1
8+85.00	80.00'	LT	1
11+48.04	20.00'	RT	1
TOTAL			4

GRAND TOTAL		EACH
IL 173 FROM ALPINE ROAD TO I-90		78
CONTINENTAL DRIVE		9
KIMBER DRIVE		2
BURDEN ROAD		6
FOREST HILLS ROAD		48
PERRYVILLE ROAD		5
MITCHELL ROAD		15
CONTRACTORS DRIVE & KRASS ROAD		4
TOTAL		167

FILE NAME : S:\Projects\2010 JOBS\10-21 Upchurch PTB 155 30 D2 P11 Alpine Rd\CADD\CADD Sheets\2007\3RME5.Schedule.dgn
 MODEL : \$MODEL\$
 PLOT DRIVER : \$PLTDRVS\$



USER NAME : rgoertz	DESIGNED - TW	REVISED -
PLOT SCALE : 2.0000' / in.	DRAWN - TW	REVISED -
PLOT DATE : 7/26/2013 3:20:18 PM	CHECKED - MTM	REVISED -
	DATE - APRIL 30, 2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
ROW MARKERS**

SCALE: SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129R	WINNEBAGO	968	98
CONTRACT NO. 64988				
ILLINOIS FED. AID PROJECT				