

## GROUND MOUNTED SIGN SCHEDULE

SIGN NUMBER	LOCATION		SIGN WIDTH FOOT	SIGN HEIGHT FOOT	72000100	72000200	72800100	73000100	COMMENTS
					SIGN PANEL, TYPE 1 SQ FT	SIGN PANEL, TYPE 2 SQ FT	TELESCOPING STEEL SIGN SUPPORT FOOT	WOOD SIGN SUPPORT (4" X 6") FOOT	
R4-7	1013+60	RT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
W3-3	1014+00	RT	4.0	4.0		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Alpine Road	1014+00	RT	4.0	1.5	6.0				AZ SHEETING - YELLOW
R2-1	1018+15	LT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
R4-7	1018+65	LT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R4-7	1019+78	LT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R4-7	1019+53	RT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R4-7	1020+90	RT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
W3-3	1023+10	RT	4.0	4.0		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Continental Drive	1023+10	RT	4.0	1.5	6.0				AZ SHEETING - YELLOW
W3-3	1025+60	LT	4.0	4.0		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Alpine Road	1025+60	LT	4.0	1.5	6.0				AZ SHEETING - YELLOW
R4-7	1027+62	LT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R4-7	1029+28	RT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
W3-3	1031+20	RT	4.0	4.0		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Kimber Drive	1031+20	RT	4.0	1.5	6.0				AZ SHEETING - YELLOW
W3-3	1033+60	LT	4.0	4.0		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Continental Drive	1033+60	LT	4.0	1.5	6.0				AZ SHEETING - YELLOW
R2-1	1035+10	LT	3.0	4.0		12.0	15.0		AP SHEETING - WHITE
R4-7	1035+87	LT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R4-7	1037+60	RT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R2-1	1038+40	RT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
W3-3	1041+00	RT	4.0	4.0		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Burden Road	1041+00	RT	4.0	1.5	6.0				AZ SHEETING - YELLOW
W3-3	1042+40	LT	4.0	4.0		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Kimber Drive	1042+40	LT	4.0	1.5	6.0				AZ SHEETING - YELLOW
R2-1	1044+40	LT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
R4-7	1045+40	LT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R4-7	1047+00	RT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R2-1	1047+40	RT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
R3-2	1050+44	RT	2.5	2.5	6.25		13.5		AP SHEETING - WHITE
R1-1	1050+82	RT	2.5	2.5	5.18		15.5		ZZ SHEETING - RED
R6-2R	1050+82	RT	1.5	2.0	3.0				AP SHEETING - WHITE
<b>SUBTOTAL</b>					<b>111.4</b>	<b>172.0</b>	<b>192.5</b>	<b>220.0</b>	

FILE NAME = ... \CADD SHEETS\200793CVR-S020.dgn	USER NAME = Elgin 110	DESIGNED - MJS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES GROUND MOUNTED SIGN SCHEDULE</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN - JAU	REVISED -			303	129R	WINNEBAGO	968	99	
		CHECKED - RLH	REVISED -			CONTRACT NO. 64988					
		DATE - APRIL 30, 2013	REVISED -			ILLINOIS FED. AID PROJECT					
<b>THE UPCHURCH GROUP, INC.</b>	PLOT SCALE = 2.0000' / IN. PLOT DATE = 5/3/2013 4:33:07 PM			SCALE:	SHEET NO. OF SHEETS STA. TO STA.						