

GROUND MOUNTED SIGN SCHEDULE

SIGN NUMBER	LOCATION		SIGN WIDTH FOOT	SIGN HEIGHT FOOT	72000100	72000200	72800100	73000100	COMMENTS
					SIGN PANEL, TYPE 1 SQ FT	SIGN PANEL, TYPE 2 SQ FT	TELESCOPING STEEL SIGN SUPPORT FOOT	WOOD SIGN SUPPORT (4" X 6") FOOT	
W3-3	1107+00	RT	4.0	4.0		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Mitchell Road	1107+00	RT	4.0	1.5	6.0				AZ SHEETING - YELLOW
R2-1	1108+00	LT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
R4-7	1112+85	LT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R4-7	1114+10	LT	2.0	2.5	5.0		13.5		AP SHEETING - WHITE
R2-1	1117+00	RT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
W3-3	1120+50	LT	4.0	4.0		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Mitchell Road	1120+50	LT	4.0	1.5	6.0				AZ SHEETING - YELLOW
R2-1	1132+00	LT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
R2-1	1132+00	RT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
R2-1	1150+00	LT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
R2-1	1150+00	RT	3.0	4.0		12.0		20.0	AP SHEETING - WHITE
<u>PERRYVILLE ROAD</u>									
W-3	243+50	RT	4	4		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Illinois 173	243+50	RT	4	1	4.0				AZ SHEETING - YELLOW
W3-3	256+50	LT	4	4		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Illinois 173	256+50	LT	4	1	4.0				AZ SHEETING - YELLOW
<u>MITCHELL ROAD</u>									
W3-3	236+00	LT	4	4		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Illinois 173	236+00	LT	4	1	4.0				AZ SHEETING - YELLOW
<u>FOREST HILLS ROAD</u>									
W3-3	385-50	RT	4	4		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Contractors Dr Krasse Dr	385-50	RT	4	1.5	6.0				AZ SHEETING - YELLOW
R4-7	390+90	RT	2	2.5	5.0		13.5		AP SHEETING - WHITE
W3-3	393+50	RT	4	4		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Illinois 173	393+50	RT	4	1	4.0				AZ SHEETING - YELLOW
W3-3	396+50	LT	4	4		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Krasse Dr Contractors Dr	396+50	LT	4	1.5	6.0				AZ SHEETING - YELLOW
R4-7	453+10	RT	2	2.5	5.0		13.5		AP SHEETING - WHITE
R4-7	454+28	RT	2	2.5	5.0		13.5		AP SHEETING - WHITE
W3-3	455+90	LT	4	4		16.0		20.0	AZ SHEETING - YELLOW
W16-8 Illinois 173	455+90	LT	4	1	4.0				AZ SHEETING - YELLOW
R4-7	457+60	LT	2	2.5	5.0		13.5		AP SHEETING - WHITE
SUBTOTAL					74.0	216.0	81.0	300.0	
TOTAL					294	564	464	780	
NOTES:									
1. DISTANCE FROM GROUND LEVEL TO BOTTOM OF SIGN SHALL BE 5 FEET.									
2. EACH WOOD POLE SHALL BE 20 FEET IN LENGTH. CUT OFF ANY EXCESS WOOD FROM THE TOP OF THE POST.									