

**78009000 MODIFIED URETHANE MARKING - LETTER AND SYMBOLS**

STATION	TO	STATION	SPACING	NO.	EACH SQ. FT.	TOTAL SQ. FT.	DESCRIPTION
<b>ILLINOIS ROUTE 173</b>							
1009+21		1011+05	60	4	15.6	62.4	RT TURN LANE
1009+73		1011+13	66	6	15.6	93.6	LT TURN LANES
1013+51		1015+87	72	4	15.6	62.4	LT TURN LANE
1013+87		1015+83	58	4	15.6	62.4	RT TURN LANE
1016+07		1018+87	70	4	15.6	62.4	RT TURN LANE
1017+73		1018+87	75	4	15.6	62.4	LT TURN LANES
1020+61		1023+11	70	8	15.6	124.8	LT TURN LANES
1020+61		1023+11	70	4	15.6	62.4	RT TURN LANE
1024+95		1027+84	83	4	15.6	62.4	LT TURN LANE
1025+11		1027+59	68	4	15.6	62.4	RT TURN LANE
1029+11		1032+33	94	4	15.6	62.4	LT TURN LANE
1029+36		1031+88	69	4	15.6	62.4	RT TURN LANE
1032+88		1036+09	70	5	15.6	78	LT TURN LANE
1033+43		1035+96	69	4	15.6	62.4	RT TURN LANE
1037+37		1041+23	87	5	15.6	78	LT TURN LANE
1037+63		1040+14	69	4	15.6	62.4	RT TURN LANE
1041+78		1045+44	84	5	15.6	78	LT TURN LANE
1046+75		1052+33	86	7	15.6	109.2	LT TURN LANE
1046+76		1050+35	81	5	15.6	78	RT TURN LANE
1048+63		1050+07	52	3	15.6	46.8	RT TURN LANE
1052+88		1058+53	87	7	15.6	109.2	LT TURN LANE
1053+54		1058+16	84	6	15.6	93.6	RT TURN LANE
1054+05		1056+28	85	3	15.6	46.8	RT TURN LANE
1060+23		1065+29	93	12	15.6	187.2	LT TURN LANES
1060+57		1064+42	85	5	15.6	78	RT TURN LANE
1062+47		1067+07	85	6	15.6	93.6	RT TURN LANE
1067+26		1071+50	150	3	41.5	124.5	RT TURN (LANE DROP)
1068+41		1073+49	93	12	15.6	187.2	LT TURN LANES
1069+43		1073+13	81	5	15.6	78	RT TURN LANE
1075+16		1079+18	90	10	15.6	156	LT TURN LANES
1075+40		1079+18	90	5	15.6	78	RT TURN LANE
1109+55		1113+05	77	5	15.6	78	LT TURN LANE
1114+50		1116+69	87	3	15.6	46.8	RT TURN LANE
<b>CONTINENTAL DRIVE</b>							
87+75		89+36	63	3	15.6	46.8	LT TURN LANE
90+62		92+39	66	3	15.6	46.8	LT TURN LANE
90+62		92+39	65	3	26	78	COMB. RT/THRU LANE
91+30		92+39	66	4	15.6	62.4	LT/RT TURN LANES
<b>KIMBER DRIVE</b>							
96+50		97+10	45	2	15.6	31.2	LT TURN LANE
98+10		99+36	44	3	15.6	46.8	LT TURN LANE
100+52		102+34	65	3	26	78	COMB. RT/THRU LANE
100+62		102+34	65	3	15.6	46.8	LT TURN LANE
101+30		102+34	66	4	15.6	62.4	LT/RT TURN LANES
<b>BURDEN ROAD</b>							
215+70		217+40	62	3	15.6	46.8	LT TURN LANE
215+96		217+40	60	3	15.6	46.8	RT TURN LANE
216+80		217+70	66	2	15.6	31.2	RT TURN LANE
<b>FOREST HILLS ROAD</b>							
388+07		389+22	75	2	15.6	31.2	LT TURN LANE
390+66		394+66	90	5	15.6	78	LT TURN LANE
395+75		399+12	75	10	15.6	156	LT TURN LANES
396+38		398+83	69	8	15.6	124.8	RT TURN LANES
450+92		453+22	64	8	15.6	124.8	LT TURN LANES
451+15		453+22	64	4	15.6	62.4	RT TURN LANE
455+73		457+75	82	3	15.6	46.8	LT TURN LANE
458+69		460+77	85	3	15.6	46.8	LT TURN LANE
<b>KRASSE DRIVE</b>							
10+69		12+45	0	1	15.6	15.6	LT TURN LANE
10+69		12+45	0	1	26	26	COMB. RT/THRU LANE
<b>PERRYVILLE ROAD</b>							
246+35		249+49	92	8	15.6	124.8	LT TURN LANES
246+97		249+29	71	4	15.6	62.4	RT TURN LANE
251+30		253+50	60	8	15.6	124.8	LT TURN LANES
251+33		253+50	60	4	15.6	62.4	RT TURN LANE
258+50		259+73	62	2	15.6	31.2	LT TURN LANE
<b>MITCHELL ROAD</b>							
231+24		232+41	77	4	15.6	62.4	LT/RT TURN LANE
234+06		234+44	0	1	15.6	15.6	LT TURN LANE
<b>TOTAL</b>						<b>4,612.1</b>	
<b>USE</b>						<b>4,613</b>	

**78009004 MODIFIED URETHANE PAVEMENT MARKING - LINE 4"**

LOCATION		WHITE (FOOT)	YELLOW (FOOT)	DESCRIPTION
STATION TO STATION	LT/RT			
<b>ILLINOIS ROUTE 173</b>				
1003+67	1011+38		771	RT MEDIAN EDGE LINE
1013+27			5	MEDIAN EDGE LINE
1013+27	1018+66		539	LT MEDIAN EDGE LINE
1013+27	1018+73		546	RT MEDIAN EDGE LINE
1018+73	1018+91		47	MEDIAN EDGE LINE
1020+60	1020+90		35	MEDIAN EDGE LINE
1020+60	1027+62		702	LT MEDIAN EDGE LINE
1020+90	1027+85		695	RT MEDIAN EDGE LINE
1027+62	1027+85		30	MEDIAN EDGE LINE
1029+10	1029+33		30	MEDIAN EDGE LINE
1029+10	1035+87		677	LT MEDIAN EDGE LINE
1029+33	1036+10		677	RT MEDIAN EDGE LINE
1035+87	1036+10		30	MEDIAN EDGE LINE
1037+37	1037+60		30	MEDIAN EDGE LINE
1037+37	1045+42		805	LT MEDIAN EDGE LINE
1037+60	1045+55		795	RT MEDIAN EDGE LINE
1045+42	1045+55		19	MEDIAN EDGE LINE
1046+73	1046+99		31	MEDIAN EDGE LINE
1046+73	1058+28		1,155	LT MEDIAN EDGE LINE
1046+99	1058+54		1,155	RT MEDIAN EDGE LINE
1058+28	1058+54		32	MEDIAN EDGE LINE
1060+20	1060+48		33	MEDIAN EDGE LINE
1060+20	1073+24		1,304	LT MEDIAN EDGE LINE
1060+48	1073+51		1,303	RT MEDIAN EDGE LINE
1073+24	1073+51		33	MEDIAN EDGE LINE
1075+15	1075+43		33	MEDIAN EDGE LINE
1075+15	1113+05	LT	3,790	LT MEDIAN EDGE LINE
1075+43	1112+79	RT	3,736	RT MEDIAN EDGE LINE
1085+80	1092+41	LT	661	EDGE LINE
1112+79	1113+05		31	LT/RT MEDIAN EDGE LINE
1113+81	1114+99		136	LT/RT MEDIAN EDGE LINE
1113+81	1156+00		4,219	LT MEDIAN EDGE LINE
1114+99	1156+00		4,101	RT MEDIAN EDGE LINE
1124+38	1130+89	LT	651	EDGE LINE
1135+56	1142+88	LT	732	EDGE LINE
1145+99	1156+00	RT	1,001	EDGE LINE
1148+29	1156+00	LT	771	EDGE LINE
154+90	155+35		45	LT MEDIAN EDGE LINE
154+90	155+35		45	RT MEDIAN EDGE LINE
154+90	155+35	LT	45	EDGE LINE
154+90	155+35	RT	45	EDGE LINE
<b>CONTINENTAL DRIVE</b>				
87+75	89+36	LT		DOUBLE
90+62	92+39	LT/RT		DOUBLE
<b>KIMBER DRIVE</b>				
96+50	99+36	LT		DOUBLE
100+62	102+34	LT/RT		DOUBLE
<b>BURDEN ROAD</b>				
215+70	217+40	RT		DOUBLE
<b>FOREST HILLS ROAD</b>				
376+10	382+68	RT	658	EDGE LINE
376+10	382+72	LT	662	EDGE LINE
376+10	382+72	LT/RT		DOUBLE
382+68	383+23	RT	79	EDGE LINE
383+49	384+22	RT	93	EDGE LINE
384+22	388+07	RT	385	EDGE LINE
384+04	388+73	LT	469	EDGE LINE
383+81	388+07	LT/RT		DOUBLE
388+07	389+22	LT		DOUBLE
390+65			5	MEDIAN EDGE LINE
390+65	398+86		822	LT MEDIAN EDGE LINE
390+65	399+13		849	RT MEDIAN EDGE LINE
398+86	399+13		33	MEDIAN EDGE LINE
450+91	451+18		34	MEDIAN EDGE LINE
450+91	453+23		232	LT MEDIAN EDGE LINE
451+18	453+08		190	RT MEDIAN EDGE LINE
453+08	453+23		22	MEDIAN EDGE LINE
454+11	454+35		28	MEDIAN EDGE LINE
454+11	457+71		360	LT MEDIAN EDGE LINE

FILE NAME = Z00793CVR - 5013.dgn  
 MODEL = Default  
 PLOT DRIVER = Vb...IDOT...PDF...11x17.plt



USER NAME = rgoertz	DESIGNED - RG	REVISED -
PLOT SCALE = 20.0000' / in.	DRAWN - TRF	REVISED -
PLOT DATE = 5/3/2013	CHECKED - CMS	REVISED -
	DATE - APRIL 30, 2013	REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**

SCALE: NONE	SHEET NO.	OF	SHEETS	STA.	TO STA.
-------------	-----------	----	--------	------	---------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129R	WINNEBAGO	968	102
			CONTRACT NO. 64988	
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				