

EARTHWORK SCHEDULE - SHARED USE PATH							
STA	TO	STA	EARTH EXCAVATION SHRINKAGE 25% CU YD	EMBANKMENT (FILL) CU YD	FURNISHED EXCAVATION CU YD	EARTH EXCAVATION (CUT) CU YD	FURNISH & PLACE TOPSOIL, 4" SQ YD
ROCK CUT - BIKE PATH							
501+28.15		589+83.39	5,702.4	8,733.6	(3,031.3)	7,603.2	25,610.0
ROCK CUT - MITCHELL STUB							
600+90.90		602+38.37	94.4	23.3	71.1	125.9	324.3
PERRYVILLE ROAD							
253+50.00		257+30.29	100.2	3.4	96.8	133.6	156.8
TOTALS			5,897	8,761	(2,864)	7,863	26,092

SEEDING SCHEDULE - SHARED USE PATH									
STATION	STATION	LT/RT	SEEDING, CLASS 1	SEEDING, CLASS 3	TEMPORARY EROSION CONTROL SEEDING	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH, METHOD 3
			ACRE	ACRE	POUND	POUND	POUND	POUND	ACRE
ROCK CUT									
501+28	589+83.39	LT/RT		5.28	2,112	475.2	475.2	475.2	5.28
MITCHELL STUB									
600+91	602+38.37	LT/RT		0.07	28	6.3	6.3	6.3	0.07
PERRYVILLE									
253+50	257+30.00	LT/RT	0.08		32	7.2	7.2	7.2	0.19
TOTALS			0.08	5.35	2172.00	488.70	488.70	488.70	5.54
USE			0.25	5.50	2,172	490	490	490	6

PIPE CULVERTS - SHARED USE PATH											
STA	OFFSET	54213447	54213450	54213453	54213459	54213459	542D0217	542D0220	542D0223	542D0226	542D0229
		END SECTIONS 12"	END SECTIONS 15"	END SECTIONS 18"	END SECTIONS 21"	END SECTIONS 24"	PIPE CULVERTS, CLASS D TY 1, 12"	PIPE CULVERTS, CLASS D TY 1, 15"	PIPE CULVERTS, CLASS D TY 1, 18"	PIPE CULVERTS, CLASS D TY 1, 21"	PIPE CULVERTS, CLASS D TY 1, 24"
		EACH	EACH	EACH	EACH	EACH	FOOT	FOOT	FOOT	FOOT	FOOT
BIKE PATH											
504+70.00	CL			2					33.00		
511+50.00	CL		2					27.00			
517+95.00	CL		2					44.00			
521+10.00	CL		2					36.00			
522+70.00	CL		2					31.00			
524+40.00	CL		2					28.00			
530+20.00	CL		2					30.50			
535+90.00	CL			2					36.00		
538+80.00	CL	2					21.00				
542+05.00	CL				2					35.00	
548+20.00	CL			2				59.50			
555+33.00	CL				2				61.00		
559+60.00	CL		2					27.00			
564+10.00	CL		2					26.00			
574+90.00	CL		2					40.00			
580+39.00	CL					2					30.00
589+74.52	CL	2					26.00				
TOTALS		4	18	6	4	2	47	290	129	96	30

- 80% FED 20% VMP
- ** 80% FED 20% COUNTY



USER NAME = \$USER*	DESIGNED - THW	REVISED -
DRAWN - THW	CHECKED - AJK	REVISED -
PLOT SCALE = \$SCALE*	DATE - 4.30 2013	REVISED -
PLOT DATE = \$DATE*		

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES			
SHARED USE PATH			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129R	WINNEBAGO	968	111
				CONTRACT NO. 64988
ILLINOIS FED. AID PROJECT				