

TEMPORARY PAVEMENT MARKING SCHEDULE							
LOCATION	TEMPORARY PAVEMENT MARKING						WORK ZONE REMOVAL (SQ FT)
	L & S	4"	6"	8"	12"	24"	
PRESTAGE 1							
IL 173		5,290		579			
PRESTAGE 1A							
IL 173	219	9,332		1,333		78	4,374
WINTER SHUT-DOWN 2013							
IL 173		3,988					1,329
FOREST HILLS ROAD		3,287					1,096
STAGE 1							
IL 173	865	33,529		3,145	740	277	
FOREST HILLS ROAD	167	17,040		391		78	
PERRYVILLE ROAD	208	6,931		799		67	
STAGE 1A							
KIMBER DRIVE		275					92
BURDEN ROAD		1,401					467
MENARDS		450					150
KRASSE DRIVE		799					266
PERRYVILLE ROAD		1,445					482
STAGE 1B							
IL 173		899				35	370
PERRYVILLE ROAD	208	7,379		559			3,040
STAGE 1C							
CONTINENTAL DRIVE		145					48
FOREST HILLS ROAD		205					68
PERRYVILLE ROAD		1,160					387
PRESTAGE 2							
CONTINENTAL	32	254					117
KIMBER DRIVE		175					58
PRESTAGE 2A							
CONTINENTAL	115	878		417		58	802
KIMBER DRIVE		228					76
STAGE 2							
IL 173	749	27,359		5,672		366	14,382
KIMBER DRIVE	193	673		380		67	805
BURDEN ROAD	63	390		282		45	471
MENARDS						18	36
KRASSE DRIVE	42	353		180		56	392
FOREST HILLS ROAD	125	13,998		374		71	5,182
PERRYVILLE ROAD	208	6,950		620		56	3,050
SPEEDWAY		516					172

TEMPORARY PAVEMENT MARKING SCHEDULE							
LOCATION	TEMPORARY PAVEMENT MARKING						WORK ZONE REMOVAL (SQ FT)
	L & S	4"	6"	8"	12"	24"	
STAGE 2							
IL 173	749	27,359		5,672		366	14,382
KIMBER DRIVE	193	673		380		67	805
BURDEN ROAD	63	390		282		45	471
MENARDS						18	36
KRASSE DRIVE	42	353		180		56	392
FOREST HILLS ROAD	125	13,998		374		71	5,182
PERRYVILLE ROAD	208	6,950		620		56	3,050
SPEEDWAY		516					
STAGE 2A							
IL 173		1,671					557
SPEEDWAY		565					188
CONTRACTORS DRIVE		1,270					423
PERRYVILLE ROAD		989					330
STAGE 2B							
PERRYVILLE ROAD	208	7,495		520		45	3,143
STAGE 2C							
PERRYVILLE ROAD		1,329					443
STAGE 3							
IL 173	2,668	11,446	3,126	17,686		721	572
CONTINENTAL DRIVE	234	676	57	459		84	
KIMBER DRIVE	265	916	17	510		84	
BURDEN ROAD	125	340		234		30	
FOREST HILLS ROAD	671	12,717	779	3,449		252	636
KRASSE DRIVE	42	354		177		90	
SPEEDWAY EAST				177		18	
SPEEDWAY NORTH						18	
PERRYVILLE ROAD	375	6,745	943	1,678		132	337
WINTER SHUT-DOWN 2014							
IL 173	437	9,782		5,154	2,313	106	9,659
PERRYVILLE ROAD	219	7,108		1,143	413	108	3,979
STAGE 4							
IL 173	130	8,135		712		78	3,472
STAGE 5							
IL 173	208	27,537		5,436		93	13,197
PERRYVILLE ROAD	104	179					164
MITCHELL ROAD	78	1,852		162	38	30	901
STAGE 6							
IL 173	842	22,374	5,362	5,957		231	1,119
TOTALS							
	11,180	319,048	10,284	65,693	3,504	4,071	101,150

PAVEMENT MARKING REMOVAL		
DESCRIPTION / LOCATION	(FT)	(SQ FT)
ILLINOIS ROUTE 173		
LETTERS AND SYMBOLS		1,022
SOLID 4"	15606	5,202
SOLID 6"	1563	782
SOLID 8"	8211	5,474
SOLID 12"	1628	1,628
SOLID 24"	361	722
CONTINENTAL DRIVE		
LETTERS AND SYMBOLS		117
SOLID 4"	338	113
SOLID 6"	28	14
SOLID 8"	230	153
SOLID 24"	42	84
KIMBER DRIVE		
LETTERS AND SYMBOLS		133
SOLID 4"	458	153
SOLID 6"	8	4
SOLID 8"	255	170
SOLID 12"	1628	1,628
SOLID 24"	42	84
BURDEN ROAD		
LETTERS AND SYMBOLS		62
SOLID 4"	170	57
SOLID 8"	117	78
SOLID 24"	15	30
FOREST HILLS ROAD		
LETTERS AND SYMBOLS		336
SOLID 4"	6358	2,119
SOLID 6"	389	195
SOLID 8"	1725	1,150
SOLID 12"	71	71
SOLID 24"	126	252
KRASSE DRIVE		
LETTERS AND SYMBOLS		21
SOLID 4"	177	59
SOLID 8"	89	59
SOLID 24"	45	90
PERRYVILLE ROAD		
LETTERS AND SYMBOLS		187
SOLID 4"	3373	1,124
SOLID 6"	472	236
SOLID 8"	839	559
SOLID 24"	66	132
TOTAL		24,300

TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER			
LOCATION	78100200		DESCRIPTION
	FLEXIBLE DELINEATORS		
STATION TO STATION	(EACH)		
PERRYVILLE ROAD			
243+50.00	247+50.00	21	STAGE 1 & 1A
254+00.00	259+50.00	29	
244+00.00	248+00.00	21	STAGE 1B, 1C, 2 & 2A
252+00.00	256+00.00	21	
244+00.00	248+00.00	21	STAGE 2B & 2C
254+00.00	259+00.00	26	
NOTE: RAISED REFLECTIVE PAVEMENT MARKERS ARE ON 20' CENTERS.			
TOTAL		139	

70300100 SHORT TERM PAVEMENT MARKING		
STAGE	LENGTH (FT)	DESCRIPTION
Pre 1	1,500	THE QUANTITY PROVIDED IS ESTIMATED AND CAN BE USED WITH APPROVAL OF THE ENGINEER IN SITUATIONS WHERE SHORT TERM MARKINGS MAKE MORE SENSE THAN TEMPORARY PAVEMENT MARKINGS.
1	1,000	
2	3,500	
3	1,500	
4	1,000	
5	3,500	
6	1,500	
TOTAL		13,500

FILE NAME = Z00793CVR - 5013.dgn
 MODEL = Default
 PLOT DRIVER = Vb...IDOT...PDF...1x17...e1c1g



USER NAME = rgoertz	DESIGNED - RG	REVISED -
PLOT SCALE = 20.0000' / in.	DRAWN - TRF	REVISED -
PLOT DATE = 5/6/2013	CHECKED - CMS	REVISED -
	DATE - APRIL 30, 2013	REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 303	SECTION 129R	COUNTY WINNEBAGO	TOTAL SHEETS 968	SHEET NO. 116
CONTRACT NO. 64988			FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT	