

FILE NAME : S:\Projects\2012\JOBS\12-95-S10206 Upchurch Loves Park 02 Ph. II\Cad\CADD Sheets\Z00793CVR - S013.dgn  
 MODEL : \$MODEL\$  
 PLOT DRIVER : \$PLTDVRS\$

Z0062456 TEMPORARY PAVEMENT					
LOCATION		AREAS		DESCRIPTION	
STATION TO STATION	OFFSET	(SQ FT)	(SQ YD)		
<b>PRE-STAGE 1</b>					
<b>ILLINOIS ROUTE 173</b>					
1021+94	1027+85	RT	6,665	740.6	PAVEMENT WIDENING
1029+06	1035+96	RT	9,791	1,087.9	PAVEMENT WIDENING
1037+30	1059+12	RT	51,416	5,712.9	PAVEMENT WIDENING
1059+62	1059+88	RT	307	34.1	ISLAND
1059+76	1064+26	RT	6,819	757.7	PAVEMENT WIDENING
1064+22	1069+97	RT	7,240	804.4	MEDIAN
1074+83	1075+00	RT	179	19.9	ISLAND
<b>FOREST HILLS ROAD</b>					
376+10	394+00	LT	35,479	3,942.1	PAVEMENT WIDENING
455+55	469+48	LT	22,326	2,480.7	PAVEMENT WIDENING
<b>PERRYVILLE ROAD</b>					
243+46	248+92	LT	5,347	594.1	MEDIAN
251+28	255+47	RT	1,891	210.1	MEDIAN
<b>STAGE 1</b>					
<b>ILLINOIS ROUTE 173</b>					
1024+67	1026+50	LT	1,572	174.7	MEDIAN
1032+60	1034+50	LT	1,656	184.0	MEDIAN
1041+51	1045+60	LT	4,270	474.4	MEDIAN
1045+61	1045+97	LT	517	57.4	ISLAND
1051+48	1056+26	LT/RT	4,606	511.8	MEDIAN
1052+60	1053+74	LT	750	83.3	MEDIAN
1053+47	1053+74	LT	428	47.6	ISLAND
1055+24	1058+54	LT	3,915	435.0	MEDIAN
1066+65	1073+51	LT	7,762	862.4	MEDIAN
1073+50	1073+85	LT	473	52.6	ISLAND
1073+52	1073+75	RT	279	31.0	ISLAND
1073+65	1073+87	LT/RT	135	15.0	ISLAND
1079+00	1086+01	LT/RT	26,185	2,909.4	CROSS OVER
<b>PERRYVILLE ROAD</b>					
248+91	249+45	LT	162	18.0	MEDIAN
<b>STAGE 1A</b>					
<b>ILLINOIS ROUTE 173</b>					
1035+10	1036+15	LT	1,185	131.7	MEDIAN
1036+30	1036+56	LT	277	30.8	ISLAND
1037+03	1037+34	LT	646	71.8	ISLAND
1053+74	1053+89	LT	283	31.4	ISLAND
1053+74	1055+24	LT	1,754	194.9	MEDIAN

Z0062456 TEMPORARY PAVEMENT					
LOCATION		AREAS		DESCRIPTION	
STATION TO STATION	OFFSET	(SQ FT)	(SQ YD)		
<b>STAGE 1B</b>					
<b>ILLINOIS ROUTE 173</b>					
1034+50	1036+15	LT	1,943	215.9	MEDIAN
1074+61	1075+01	LT/RT	139	15.4	ISLAND
1074+85	1075+11	LT	497	55.2	ISLAND
<b>PERRYVILLE ROAD</b>					
251+29	253+50	RT	1,657	184.1	MEDIAN
<b>STAGE 1C</b>					
<b>ILLINOIS ROUTE 173</b>					
1026+50	1027+85	LT	1,592	176.9	MEDIAN
1058+52	1058+99	LT	916	101.8	ISLAND
1059+69	1060+29	LT	1,107	123.0	ISLAND
<b>FOREST HILLS ROAD</b>					
450+90	453+22	RT	1,814	201.6	MEDIAN
<b>PRE-STAGE 2</b>					
<b>ILLINOIS ROUTE 173</b>					
1059+76	1060+13	RT	656	72.9	ISLAND
<b>STAGE 2</b>					
<b>ILLINOIS ROUTE 173</b>					
1067+40	1067+76	RT	499	55.4	ISLAND
1069+64	1071+74	LT/RT	1,434	159.3	MEDIAN
1074+82	1075+18	RT	487	54.1	ISLAND
1076+00	1076+35	RT	2,078	230.9	TEMPORARY RAMP
<b>FOREST HILLS ROAD</b>					
394+00	395+74	LT/RT	1,644	182.7	MEDIAN
395+01	395+36	LT	450	50.0	ISLAND
<b>CONTRACTORS DRIVE</b>					
5+35	6+36	LT	2,092	232.4	PAVEMENT WIDENING
<b>STAGE 2A</b>					
<b>ILLINOIS ROUTE 173</b>					
1067+29	1067+47	RT	138	15.3	ISLAND
1075+15	1076+00	RT	642	71.3	MEDIAN
<b>STAGE 2B</b>					
<b>ILLINOIS ROUTE 173</b>					
1073+45	1073+84	RT	925	102.8	ISLAND
<b>STAGE 4</b>					
<b>ILLINOIS ROUTE 173</b>					
1147+81	1149+48	LT	2,005	222.8	MEDIAN
<b>TOTAL</b>				<b>25,225.5</b>	
<b>USE</b>				<b>25,226</b>	

X4200500 HIGH-EARLY-STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)			
STAGE	AREA		DESCRIPTION
	(SQ FT)	(SQ YD)	
<b>FOREST HILLS ROAD INTERSECTION</b>			
1C	27,088.0	3,009.8	PCC PLACED WHILE NORTH LEG OF INTERSECTION IS CLOSED
PRE 2	31,053.2	3,450.4	PCC PLACED WHILE SOUTH LEG OF INTERSECTION IS CLOSED
<b>PERRYVILLE ROAD INTERSECTION</b>			
1A	1,623.5	180.4	PCC PLACED TO COMPLETE CENTER PORTION OF INTERSECTION
1C	2,586.6	287.4	PCC PLACED TO COMPLETE CENTER PORTION OF INTERSECTION
2A	4,914.5	546.1	PCC PLACED TO COMPLETE CENTER PORTION OF INTERSECTION
2C	5,454.4	606.0	PCC PLACED TO COMPLETE CENTER PORTION OF INTERSECTION
<b>IL 173 (EASTBOUND LANES AT END OF IMPROVEMENT)</b>			
6	3,720.6	413.4	
<b>TOTAL</b>		<b>8,493.5</b>	
<b>USE</b>		<b>8,494</b>	



USER NAME : rgoertz  
 PLOT SCALE : 20.0000' / 1"  
 PLOT DATE : 7/26/2013

DESIGNED - RG  
 DRAWN - TRF  
 CHECKED - CMS  
 DATE - APRIL 30, 2013

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129R	WINNEBAGO	968	117
CONTRACT NO. 64988				
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				