

FILE NAME : S:\Projects\2012\JOBS\12-95-S10206 Upchurch Loves Park 02 Ph. II\Cad\CADD Sheets\202793CVR - S013.dgn  
 MODEL : \$MODEL\$  
 PLOT DRIVER : \$PLTDVRS\$

| RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE |                                   |        |             |
|--|-----------------------------------|--------|-------------|
| LOCATION                                   | 78100100                          |        | DESCRIPTION |
|  | RAISED REFLECTIVE PAVEMENT MARKER |        |             |
| STATION TO STATION                         |                                   | (EACH) |             |
| <b>STAGE 1</b>                             |                                   |        |             |
| <b>PERRYVILLE ROAD</b>                     |                                   |        |             |
| 242+72.00                                  | 247+90.00                         | 14     | CRYSTAL     |
| 243+92.00                                  | 247+90.00                         | 11     | AMBER       |
| 253+07.00                                  | 259+36.00                         | 17     | CRYSTAL     |
| 253+07.00                                  | 257+05.00                         | 11     | AMBER       |
| 258+16.00                                  | 260+52.00                         | 7      | AMBER       |
| <b>PRE-STAGE 1A</b>                        |                                   |        |             |
| <b>ILLINOIS ROUTE 173</b>                  |                                   |        |             |
| 1023+12.00                                 | 1027+50.00                        | 12     | CRYSTAL     |
| 1023+12.00                                 | 1027+50.00                        | 12     | AMBER       |
| <b>STAGE 1A</b>                            |                                   |        |             |
| <b>PERRYVILLE ROAD</b>                     |                                   |        |             |
| 252+96.00                                  | 259+28.00                         | 17     | AMBER       |
| 254+14.00                                  | 259+23.00                         | 14     | CRYSTAL     |
| <b>STAGE 1B</b>                            |                                   |        |             |
| <b>PERRYVILLE ROAD</b>                     |                                   |        |             |
| 243+92.00                                  | 247+51.00                         | 10     | AMBER       |
| 244+15.00                                  | 247+73.00                         | 10     | CRYSTAL     |
| 252+25.00                                  | 256+25.00                         | 11     | AMBER       |
| 252+25.00                                  | 256+25.00                         | 11     | CRYSTAL     |
| <b>STAGE 1C</b>                            |                                   |        |             |
| <b>PERRYVILLE ROAD</b>                     |                                   |        |             |
| 252+25.00                                  | 256+25.00                         | 11     | AMBER       |
| 252+25.00                                  | 256+25.00                         | 11     | CRYSTAL     |
| <b>PRE-STAGE 2</b>                         |                                   |        |             |
| <b>ILLINOIS ROUTE 173</b>                  |                                   |        |             |
| 1014+51.00                                 | 1018+49.00                        | 11     | AMBER       |
| 1014+55.00                                 | 1018+53.00                        | 11     | CRYSTAL     |
| <b>STAGE 2</b>                             |                                   |        |             |
| <b>ILLINOIS ROUTE 173</b>                  |                                   |        |             |
| 1014+11.00                                 | 1018+49.00                        | 12     | AMBER       |
| 1014+55.00                                 | 1018+53.00                        | 11     | CRYSTAL     |
| <b>PERRYVILLE ROAD</b>                     |                                   |        |             |
| 252+83.00                                  | 256+39.00                         | 10     | AMBER       |
| 252+87.00                                  | 256+44.00                         | 10     | CRYSTAL     |

| RAISED REFLECTIVE PAVEMENT MARKER SCHEDULE                   |                                   |            |             |
|--|-----------------------------------|------------|-------------|
| LOCATION   | 78100100                          |            | DESCRIPTION |
|  | RAISED REFLECTIVE PAVEMENT MARKER |            |             |
| STATION TO STATION   |                                   | (EACH)     |             |
| <b>STAGE 2A</b>  |                                   |            |             |
| <b>PERRYVILLE ROAD</b>                                       |                                   |            |             |
| 243+92.00  | 247+50.00                         | 10         | AMBER       |
| 244+15.00  | 247+73.00                         | 10         | CRYSTAL     |
| 252+83.00  | 256+39.00                         | 10         | AMBER       |
| 252+87.00  | 256+44.00                         | 10         | CRYSTAL     |
| <b>STAGE 2B</b>  |                                   |            |             |
| <b>PERRYVILLE ROAD</b>                                       |                                   |            |             |
| 244+33.00  | 247+91.00                         | 10         | CRYSTAL     |
| 244+33.00  | 247+91.00                         | 10         | AMBER       |
| 253+80.00  | 259+30.00                         | 15         | CRYSTAL     |
| 253+88.00  | 257+05.00                         | 9          | AMBER       |
| 258+38.00  | 260+35.00                         | 6          | AMBER       |
| <b>STAGE 2C</b>  |                                   |            |             |
| <b>PERRYVILLE ROAD</b>                                       |                                   |            |             |
| 244+33.00  | 247+91.00                         | 10         | CRYSTAL     |
| 244+33.00  | 247+91.00                         | 10         | AMBER       |
| 253+80.00  | 259+30.00                         | 15         | CRYSTAL     |
| 253+88.00  | 257+05.00                         | 9          | AMBER       |
| 258+38.00  | 260+35.00                         | 6          | AMBER       |
| <b>STAGE 3</b>   |                                   |            |             |
| <b>ILLINOIS ROUTE 173</b>                                    |                                   |            |             |
| 1080+71.00   | 1086+66.00                        | 16         | AMBER       |
| 1080+71.00   | 1086+66.00                        | 16         | CRYSTAL     |
| <b>STAGE 4</b>   |                                   |            |             |
| <b>ILLINOIS ROUTE 173</b>                                    |                                   |            |             |
| 1068+76.00   | 1072+72.00                        | 11         | AMBER       |
| 1068+76.00   | 1072+72.00                        | 11         | CRYSTAL     |
| <b>STAGE 5</b>   |                                   |            |             |
| <b>ILLINOIS ROUTE 173</b>                                    |                                   |            |             |
| 1067+25.00   | 1071+25.00                        | 11         | AMBER       |
| 1067+25.00   | 1071+25.00                        | 11         | CRYSTAL     |
| 1147+66.00   | 1152+42.00                        | 13         | AMBER       |
| 1147+66.00   | 1152+42.00                        | 13         | CRYSTAL     |
| NOTE: RAISED REFLECTIVE PAVEMENT MARKERS ARE ON 40' CENTERS. |                                   |            |             |
| <b>TOTAL</b>   |                                   | <b>483</b> |             |



|                             |                       |           |
|-----------------------------|-----------------------|-----------|
| USER NAME : rgoertz         | DESIGNED - RG         | REVISED - |
| PLOT SCALE : 20.0000' / in. | DRAWN - TRF           | REVISED - |
| PLOT DATE : 7/26/2013       | CHECKED - CMS         | REVISED - |
|                             | DATE - APRIL 30, 2013 | REVISED - |

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

| F.A.P. RTE.                                     | SECTION | COUNTY    | TOTAL SHEETS | SHEET NO. |
|---|---------|-----------|--------------|-----------|
| 303   | 129R    | WINNEBAGO | 968          | 118A      |
| CONTRACT NO. 64988                              |         |           |              |           |
| FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT |         |           |              |           |