

TEMPORARY IMPACT ATTENUATORS SCHEDULE

LOCATION	70600250	70600251	70600260	70600350	70600352	70600332	DESCRIPTION
	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	
STATION	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	
STAGE 1 CONSTRUCTION...							
ILLINOIS ROUTE 173							
1021+13.00	1						STAGE 1
1026+82.80			1				STAGE 1
1029+78.90		1					STAGE 1
1034+72.10			1				STAGE 1
1038+03.60		1					STAGE 1
1044+22.80			1				STAGE 1
1047+34.80		1					STAGE 1
1052+15.60			1				STAGE 1
1055+05.20		1					STAGE 1
1057+83.90			1				STAGE 1
1060+97.00		1					STAGE 1
1072+74.20	1						STAGE 1
1069+58.60				1			STAGE 1B
FOREST HILLS ROAD							
453+15.10			1				STAGE 1
456+18.80	1						STAGE 1
STAGE 2 CONSTRUCTION...							
ILLINOIS ROUTE 173							
1021+50.40				1			PRE STAGE 2
1035+43.80					1		PRE STAGE 2
1039+34.20						1	PRE STAGE 2
1062+13.60						1	PRE STAGE 2
1066+44.70					1		PRE STAGE 2
1027+07.80				1			PRE STAGE 2A
1029+85.90	1						PRE STAGE 2A
1035+43.80					1		STAGE 2
1046+56.50					1		STAGE 2
1048+54.70						1	STAGE 2
1049+55.90					1		STAGE 2
1050+95.70						1	STAGE 2
1058+56.00	1						STAGE 2
1066+44.70					1		STAGE 2
1068+00.00						1	STAGE 2
1072+81.30					1		STAGE 2
1045+04.50					1		STAGE 2A
1046+90.90						1	STAGE 2A
1048+54.50					1		STAGE 2A
1049+94.40						1	STAGE 2A
1065+17.90					1		STAGE 2A
1067+11.30						1	STAGE 2A
1069+64.60	1						STAGE 2B
FOREST HILLS ROAD							
453+18.70		1					STAGE 2
456+18.70						1	STAGE 2
TOTAL	6	6	6	3	10	9	
USE	6	6	6	3	10	9	

FILE NAME : S:\Projects\2012\JOBS\12-95-S10006 Upchurch Loves Park 02 Ph. II\Cad\CADD Sheets\200793CVR - S013.dgn
 MODEL : \$MODEL\$
 PLOT DRIVER : \$PLTDRVS\$



USER NAME : rgoertz
 PLOT SCALE : 20.0000' / in.
 PLOT DATE : 7/26/2013

DESIGNED - RG
 DRAWN - TRF
 CHECKED - CMS
 DATE - APRIL 30, 2013

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129R	WINNEBAGO	968	118B
CONTRACT NO. 64988				
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				