1 2 3 4 5 6 7 8 9 10 11 12 13 14 15

SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED 20% STATE	100% VMP	80% FED 10% STATE 10% VMP	80% FED 10% STATE 5% VMP 5% CLP	80% FED 13.3% STATE 6.67% VMP	80% FED 20% CLP	80% FED 10% STATE 10% COUNTY	80% FED 20% STATE	80% FED 20% COUNTY	80% FED 20% VMP	80% FED 20% STATE	100% VMP	100% VMP	100% NPPWD
					CONSTRUCTION CODE													
					ROADWAY	ROADWAY	SAFETY	SAFETY	SAFETY	SAFETY	SAFETY	BIKES / PEDS	BIKES / PEDS	BIKES / PEDS	SPECIAL BRIDGE	SPECIAL BRIDGE	UTILITIES	UTILITIES
					0003	0003	0021	0021	0021	0021	0021	0028	0028	0028	0040	0040	0043	0043
					URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN	URBAN
					M001L	07P0L	M001L,01	M001L,02	M001L,03	M001L,04	M001L,05	M001L,01	M001L,02	M001L,03	M001L,01	07P0L	07P0L,01	07P0L,02
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	770	770													
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1,812	1,812													
	20100500	TREE REMOVAL, ACRES	ACRE	21.00	13.75							7.25						
	20101000	TEMPORARY FENCE	FOOT	4,850	4,850													
	20101100	TREE TRUNK PROTECTION	EACH	16	18													
	20200100	EARTH EXCAVATION	CU YD	73,032	65,067	102						7,863						
*	20200200	ROCK EXCAVATION	CU YD	750	750													
	20300100	CHANNEL EXCAVATION	CU YD	41,847	41,847													
	20300200	ROCK EXCAVATION IN CHANNEL	CU YD	11,214	11,214													
*	20400800	FURNISHED EXCAVATION	CU YD	82,904	79,355	686						2,863						
	20700110	POROUS GRANULAR EMBANKMENT	TON	3,544											2,256	1,288		
	20800150	TRENCH BACKFILL	CU YD	5,834	5,834													
	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	62,446	62,446													
	21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	19,647	19,569	78												
	21101615	FURNISH AND PLACE TOPSOIL, 4"	SQ YD	28,850								28,850						
	25000100	SEEDING, CLASS 1	ACRE	0.25								0.25						

* DENOTES SPECIALTY ITEMS

1 Rev. 9-4-13

FILE NAME = ...\CADD SHEETS\Z00793CVR-S00.dgn	USER NAME = Elgin 110	DESIGNED - MJS	REVISED -
		DRAWN - JAU	REVISED -
	PLOT SCALE = 2.0000 ' / IN.	CHECKED - RLH	REVISED -
THE UPCHURCH GROUP, INC.	PLOT DATE = 5/7/2013 9:27:45 AM	DATE - APRIL 30, 2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303	129R	WINNEBAGO	968	6
		CONTRACT NO. 64988		
		ILLINOIS FED. AID PROJECT		