

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE													
				80% FED 20% STATE	100% VMP	80% FED 10% STATE 10% VMP	80% FED 10% STATE 5% VMP 5% CLP	80% FED 13.3% STATE 6.67% VMP	80% FED 20% CLP	80% FED 10% STATE 10% COUNTY	80% FED 20% STATE	80% FED 20% COUNTY	80% FED 20% VMP	80% FED 20% STATE	100% VMP	100% VMP	100% NPPWD
				ROADWAY	ROADWAY	SAFETY	SAFETY	SAFETY	SAFETY	SAFETY	BIKES / PEDS	BIKES / PEDS	BIKES / PEDS	SPECIAL BRIDGE	SPECIAL BRIDGE	UTILITIES	UTILITIES
				0003 URBAN	0003 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0028 URBAN	0028 URBAN	0028 URBAN	0040 URBAN	0040 URBAN	0043 URBAN	0043 URBAN
25200200	SUPPLEMENTAL WATERING	UNIT	2,265	2,265													
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	13,706	11,534							2,172						
28000305	TEMPORARY DITCH CHECKS	FOOT	4,016	2,051							1,965						
28000400	PERIMETER EROSION BARRIER	FOOT	30,095	11,328							17,712	760	295				
28000500	INLET AND PIPE PROTECTION	EACH	319	301							18						
28000510	INLET FILTERS	EACH	232	232													
28100107	STONE RIPRAP, CLASS A4	SQ YD	1,674	1,674													
28200200	FILTER FABRIC	SQ YD	1,674	1,674													
28400100	GABIONS	CU YD	26	26													
30300112	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	113,320	110,435	2,885												
30300121	AGGREGATE SUBGRADE IMPROVEMENT 21"	SQ YD	52,086	52,006	80												
30300124	AGGREGATE SUBGRADE IMPROVEMENT 24"	SQ YD	2,724	2,724													
30300127	AGGREGATE SUBGRADE IMPROVEMENT 27"	SQ YD	4,750	4,750													
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	5,622	5,622													
35101400	AGGREGATE BASE COURSE, TYPE B	TON	426	426													
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	10,175								12,879	993	2303				

• DENOTES SPECIALTY ITEMS

FILE NAME * ...CAD00 SHEETS\280793CVR-500.dgn	USER NAME * E1gin 110	DESIGNED - NJS	REVISED -
		DRAWN - JAU	REVISED -
	PLOT SCALE = 2.0000' / IN.	CHECKED - RLH	REVISED -
	PLOT DATE = 5/15/2013 9:48:31 AM	DATE - APRIL 30, 2013	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

Rev. 9-4-13

F.A.P. RTE. 303	SECTION 129R	COUNTY WINNEBAGO	TOTAL SHEETS 968	SHEET NO. 8
CONTRACT NO. 64988			ILLINOIS FED. AID PROJECT	