

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE														
				80% FED 20% STATE	100% VMP	80% FED 10% STATE 10% VMP	80% FED 10% STATE 5% VMP 5% CLP	80% FED 13.3% STATE 6.67% VMP	80% FED 20% CLP	80% FED 10% STATE 10% COUNTY	80% FED 20% STATE	80% FED 20% COUNTY	80% FED 20% VMP	80% FED 20% STATE	100% VMP	100% VMP	100% NPPWD	
				ROADWAY	ROADWAY	SAFETY	SAFETY	SAFETY	SAFETY	SAFETY	BIKES / PEDS	BIKES / PEDS	BIKES / PEDS	SPECIAL BRIDGE	SPECIAL BRIDGE	UTILITIES	UTILITIES	
				0003 URBAN	0003 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0026 URBAN	0026 URBAN	0026 URBAN	0040 URBAN	0040 URBAN	0043 URBAN	0043 URBAN	
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	3	3														
60240310	INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	39	39														
60246805	MEDIAN INLET (604106)	EACH	44	44														
60248900	VALVE VAULTS, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5														
60249010	VALVE VAULTS, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2														
60255500	MANHOLES TO BE ADJUSTED	EACH	5	5														
60260100	INLETS TO BE ADJUSTED	EACH	11	11														
60265900	VALVE VAULTS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1														
60266300	VALVE VAULTS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	5	2													3	
60266600	VALVE BOXES TO BE ADJUSTED	EACH	18	8														10
60403400	GRATES, TYPE A	EACH	4	4														
60500040	REMOVING MANHOLES	EACH	11	11														
60500050	REMOVING CATCH BASINS	EACH	1	1														
60500080	REMOVING INLETS	EACH	8	8														
60500105	FILLING MANHOLES	EACH	1	1														
60500405	FILLING VALVE VAULTS	EACH	2	2														

* DENOTES SPECIALTY ITEMS

FILE NAME : ...SHEETS\2007\3CVR-500.dgn	USER NAME : Elgin 110	DESIGNED - MJS	REVISED -
		DRAWN - JAU	REVISED -
	PLOT SCALE : 2.0000 / IN.	CHECKED - RLH	REVISED -
	PLOT DATE : 5/7/2013 9:42:17 AM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 303	SECTION 129R	COUNTY WINNEBAGO	TOTAL SHEETS 968	SHEET NO. 17
	CONTRACT NO. 64988			
ILLINOIS FED. AID PROJECT				

Rev. 9-4-13

THE UPCHURCH GROUP, INC.