

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE												100% VMP	100% NPPWD		
				80% FED 20% STATE	100% VMP	80% FED 10% STATE 10% VMP	80% FED 10% STATE 5% VMP 5% CLP	80% FED 13.3% STATE 6.67% VMP	80% FED 20% CLP	80% FED 10% STATE 10% COUNTY	80% FED 20% STATE	80% FED 20% COUNTY	80% FED 20% VMP	80% FED 20% STATE					
				ROADWAY	ROADWAY	SAFETY	SAFETY	SAFETY	SAFETY	SAFETY	BIKES / PEDS	BIKES / PEDS	BIKES / PEDS	SPECIAL BRIDGE	SPECIAL BRIDGE			UTILITIES	UTILITIES
				0003 URBAN	0003 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0021 URBAN	0028 URBAN	0028 URBAN	0028 URBAN	0040 URBAN	0040 URBAN			0043 URBAN	0043 URBAN
* 81028790	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 4" DIA.	FOOT	3,367			782	1,143	346	526	570									
* 81400100	HANDHOLE	EACH	57	5		15	15	4	5	13									
* 81400300	DOUBLE HANDHOLE	EACH	7			2	2	1	1	1									
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	6,497			1,828	2,075	521	1,012	1,061									
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	27			8	8	3	4	4									
* 85000400	MAINTENANCE OF TEMPORARY TRAFFIC INSTALLATION	EACH	1			1													
* 85700300	FULL-ACTUATED CONTROLLER AND TYPE V CABINET	EACH	7			2	2	1	1	1									
* 86200200	UNINTERRUPTED POWER SUPPLY, STANDARD	EACH	8			3	2	1	1	1									
* 87100110	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 6F	FOOT	10,672			2,147	3,267	424	893	3,941									
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO 14 2C	FOOT	1,588				560	235		793									
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1,637				574	249		814									
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	22,718			4,437	8,174	1,122	4,111	4,874									
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	12,316			5,071	4,550	1,160		1,535									
* 87301295	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 20 3C	FOOT	6,490			1,880	1,895	480	1,075	1,160									
* 87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3 C	FOOT	218			57	70	34	29	28									
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	5,325			1,418	1,738	616	635	918									

* DENOTES SPECIALTY ITEMS