


PAVEMENT SCHEDULE - SHARED USE PATH								
STA	STA	LT/RT	SQ YD	35101800	40600200	40603415	44000300	44213200
				AGG BASE CSE TY B 6"	BITUMINOUS MATERIALS (PRIME COAT)	HMA SURFACE COURSE, IL- 9.5FG, N50	CURB REMOVAL	SAW CUTS
				TON	TON	FOOT	FOOT	
IL 173			sq yd					
1057+00.00	1063+00.00	RT	188.3	0.27	26.2			
1063+00.00	1069+00.00	RT	150.1	0.21	20.7			
IL 173			sq yd					
1057+00.00	1063+00.00	LT	365.8	0.50	51.2			
1063+00.00	1069+00.00	LT	799.1	1.14	111.9			
1069+00.00	1072+00.00	LT	402.3	0.57	56.3			
1072+00.00	1078+00.00	LT	215.9	0.31	30.2			
1111+00.00	1117+00.00	RT	65.2	0.10	9.1			
FOREST HILLS RD								
391+50.00	397+50.00	RT	235.9	0.34	32.4			
PERRYVILLE RD								
248+00.00	253+50.00	RT	611.11	485.7	68.1			
253+50.00	257+30.29	RT	422.54	507.1	71.0			
257+30.00						12	12	
MITCHELL ROAD								
231+00.00	234+00.00	LT	399.6	0.57	55.9			
234+00.00	238+75.00	LT	527.78	121.1	16.8			
MITCHELL STUB								
600+42.90	602+38.37	RT/LT	217.19	260.6	36.5			
BIKE PATH								
500+00.00	589+83.74	RT/LT	9981.93	11978.3	20.9	1677.0		
TOTALS				16,175	28	2,264	12	12



TREE REMOVAL - SHARED USE PATH			
STA	TO	STA	20100500 TREE REMOVAL ACRES
ROCK CUT - BIKE PATH			
500+28.15		589+83.39	7.09
ROCK CUT - MITCHELL STUB			
600+90.90		602+38.37	0.12
TOTALS			7.26

EROSION CONTROL DITCH LINING SCHEDULE SHARED USE PATH					
STA	STA	LT/RT	LENGTH	25100630	25100900
				EROSION CONTROL BLANKET SQ YD	TURF REINFORCEMENT MAT SQ YD
ROCK CUT					
501+28.15	503+00.00	RT	171.85	152.8	
504+00.00	509+62.00	RT	562	499.6	
513+50.00	515+00.00	RT	150		133.3
517+23.00	521+00.00	RT	377	335.1	
522+70.00	535+00.00	RT	1230	1093.3	
535+90.00	537+12.00	RT	122	108.4	
540+50.00	541+00.00	RT	50	44.4	
542+00.00	543+00.00	RT	100	88.9	
548+20.00	549+00.00	RT	80		71.1
549+00.00	551+00.00	RT	200	177.8	
553+00.00	554+00.00	RT	100	88.9	
554+00.00	555+33.00	RT	133		118.2
555+33.00	559+60.00	RT	427	379.6	
565+00.00	567+55.00	RT	255	228.7	
569+00.00	573+70.00	RT	470	417.8	
574+90.00	579+00.00	RT	410	364.4	
580+00.00	589+60.00	RT	960	853.3	
589+60.00	589+75.00	RT	15		13.3
589+60.00	589+75.00	LT	15	13.3	
TOTALS				4,845	336

Rev. Sheet 9-4-13

- 80% FED 20% VMP
- 80% FED 20% COUNTY