



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

October 30, 2013

SUBJECT: FAP Route 301 (US 20 Bypass)
Project ACNHPP-0301(076)
Section 3BR & BR-1
Winnebago County
Contract No. 64D19
Item No. 16, November 8, 2013 Letting
Addendum B

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised sheets 7, 9, 10, 11 & 17 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Paul Loete, Region 2, District 2; Tim Kell; D. Carl Puzey; Estimates

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64D19

State Job # - C-92-004-13

County Name - WINNEBAGO -
 Code - 201 - -
 District - 2 - -
 Section Number - 3BR & 3BR-1

Project Number
 ACNHPP-0301/076/

Route
 FAP 301

** REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
A2000114	T-ACERX FREM AB 1-3/4	EACH	31.000				
A2001714	T-ACER SACR 1-3/4	EACH	31.000				
A2002914	T-CELTIS OCCID 1-3/4	EACH	31.000				
A2006514	T-QUERCUS BICOL 1-3/4	EACH	31.000				
A2006714	T-QUERCUS MACR 1-3/4	EACH	31.000				
B2004114	T-MALUS PF TF 1-3/4	EACH	32.000				
B2005014	T-MALUS SND TF 1-3/4	EACH	31.000				
K1005421	SEEDING SPL	ACRE	0.250				
X0322288	**	EACH	2.000				
X0322392	BEVEL PIPE AND GUARD	EACH	3.000				
X0322936	REMOV EX FLAR END SEC	EACH	1.000				
X0327640	REAL-TIME TR CONT CBU	CAL MO	17.000				
X0327641	REAL-TIME TR CONT SU	CAL MO	78.000				
X2011000	TEMPORARY FENCE SPL	FOOT	325.000				
X4400110	TEMP PAVT REMOVAL	SQ YD	2,018.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64D19

State Job # - C-92-004-13

County Name - WINNEBAGO -

Code - 201 - -

District - 2 - -

Section Number - 3BR & 3BR-1

Project Number
 ACNHPP-0301/076/

Route
 FAP 301

** REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
**REV X5030290	STAIN CONC STRUCTURES	SQ FT	21,575.000				
**REV X5860110	GRANULAR BACKFILL STR	CU YD	1,269.000				
X6380205	TEMP MOD GLARE SCREEN	FOOT	900.000				
X7050167	TEMP TRBT T1 SPL TAN	EACH	2.000				
X7050169	TEMP TRBT T1 SPL FLAR	EACH	1.000				
X8410102	TEMP LIGHTING SYSTEM	L SUM	1.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0018002	DRAINAGE SCUPPR DS-11	EACH	16.000				
Z0028415	GEOTECHNICAL REINF	SQ YD	2,185.000				
Z0046304	P UNDR FOR STRUCT 4	FOOT	630.000				
Z0062456	TEMP PAVEMENT	SQ YD	2,018.000				
Z0065752	SLOT DR 12" W/6" SLOT	FOOT	57.000				
Z0065765	SLOT DR 18" W/VAR SL	FOOT	154.000				
**REV Z0073002	TEMP SOIL RETEN SYSTM	SQ FT	2,890.000				
Z0076600	TRAINEES	HOOR	2,000.000		0.800		1,600.000

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64D19

State Job # - C-92-004-13

Project Number
 ACNHPP-0301/076/

Route
 FAP 301

County Name - WINNEBAGO - -

Code - 201 - -

District - 2 - -

Section Number - 3BR & 3BR-1

** REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
Z0076604	TRAINEES TPG	HOURL	2,000.000		10.000		20,000.000
20100500	TREE REMOV ACRES	ACRE	2.000				
20200100	EARTH EXCAVATION	CU YD	6,255.000				
20400800	FURNISHED EXCAVATION	CU YD	14,205.000				
21101505	TOPSOIL EXC & PLAC	CU YD	4,731.000				
25000210	SEEDING CL 2A	ACRE	7.500				
25000310	SEEDING CL 4	ACRE	0.750				
25000400	NITROGEN FERT NUTR	POUND	722.000				
25000500	PHOSPHORUS FERT NUTR	POUND	722.000				
25000600	POTASSIUM FERT NUTR	POUND	722.000				
25000750	MOWING	ACRE	8.250				
25100125	MULCH METHOD 3	ACRE	8.250				
25100630	EROSION CONTR BLANKET	SQ YD	39,145.000				
28000200	EARTH EXC - EROS CONT	CU YD	200.000				
28000250	TEMP EROS CONTR SEED	POUND	1,722.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64D19

State Job # - C-92-004-13

Project Number
 ACNHPP-0301/076/

Route
 FAP 301

County Name - WINNEBAGO - -

Code - 201 - -

District - 2 - -

Section Number - 3BR & 3BR-1

** REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
28000305	TEMP DITCH CHECKS	FOOT	1,005.000				
28000400	PERIMETER EROS BAR	FOOT	3,247.000				
28000500	INLET & PIPE PROTECT	EACH	9.000				
28001000	AGGREGATE - EROS CONT	TON	114.000				
28100105	STONE RIPRAP CL A3	SQ YD	70.000				
**REV 28100109	STONE RIPRAP CL A5	SQ YD	3,305.000				
**REV 28200200	FILTER FABRIC	SQ YD	3,375.000				
30300112	AGG SUBGRADE IMPR 12	SQ YD	11,348.000				
31100910	SUB GRAN MAT A 12	SQ YD	2,470.000				
31200100	STAB SUBBASE 4	SQ YD	1,158.000				
40600200	BIT MATLS PR CT	TON	12.000				
40600837	P LEV BIND MM N70	TON	2,433.000				
40600982	HMA SURF REM BUTT JT	SQ YD	1,833.000				
40603310	HMA SC "C" N50	TON	1,006.000				
40603540	P HMA SC "D" N70	TON	1,859.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64D19

State Job # - C-92-004-13

County Name - WINNEBAGO -
 Code - 201 - -
 District - 2 - -
 Section Number - 3BR & 3BR-1

Project Number
 ACNHPP-0301/076/

Route
 FAP 301

** REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
42000501	PCC PVT 10 JOINTED	SQ YD	2,303.000				
42001420	BR APPR PVT CON (PCC)	SQ YD	2,802.000				
42001430	BR APPR PVT CON (FLX)	SQ YD	56.000				
42100315	CONT R PCC PVT 10 3/4	SQ YD	1,029.000				
42100615	PAVT REINFORCEMENT	SQ YD	1,029.000				
44000100	PAVEMENT REM	SQ YD	6,406.000				
44000155	HMA SURF REM 1 1/2	SQ YD	15,722.000				
44003100	MEDIAN REMOVAL	SQ FT	82.000				
44004250	PAVED SHLD REMOVAL	SQ YD	6,794.000				
44201025	CL B PATCH T4 14	SQ YD	152.000				
44201299	DOWEL BARS 1 1/2	EACH	34.000				
44213100	PAVEMENT FABRIC	SQ YD	152.000				
44213200	SAW CUTS	FOOT	336.000				
44213208	TIE BARS 1 1/4	EACH	34.000				
48101200	AGGREGATE SHLDS B	TON	88.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64D19

State Job # - C-92-004-13

County Name - WINNEBAGO -
 Code - 201 - -
 District - 2 - -
 Section Number - 3BR & 3BR-1

Project Number
 ACNHPP-0301/076/

Route
 FAP 301

** REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
48203021	HMA SHOULDERS 6	SQ YD	1,404.000				
48203029	HMA SHOULDERS 8	SQ YD	8,304.000				
48300515	PCC SHOULDERS 10 3/4	SQ YD	752.000				
50100300	REM EXIST STRUCT N1	EACH	1.000				
50100400	REM EXIST STRUCT N2	EACH	1.000				
50100500	REM EXIST STRUCT N3	EACH	1.000				
50100600	REM EXIST STRUCT N4	EACH	1.000				
50105220	PIPE CULVERT REMOV	FOOT	128.000				
**REV 50200100	STRUCTURE EXCAVATION	CU YD	1,326.000				
50200300	COFFERDAM EXCAVATION	CU YD	2,220.000				
50201121	COFFERDAM TYP 2 LOC 1	EACH	1.000				
50201122	COFFERDAM TYP 2 LOC 2	EACH	1.000				
**REV 50300225	CONC STRUCT	CU YD	2,395.000				
**REV 50300255	CONC SUP-STR	CU YD	2,994.400				
50300260	BR DECK GROOVING	SQ YD	8,512.200				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64D19

State Job # - C-92-004-13

County Name - WINNEBAGO -
 Code - 201 - -
 District - 2 - -
 Section Number - 3BR & 3BR-1

Project Number
 ACNHPP-0301/076/

Route
 FAP 301

** REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
**REV 50300265	SEAL COAT CONC	CU YD	709.400				
50300280	CONCRETE ENCASMENT	CU YD	33.800				
**REV 50300285	FORM LINER TEX SURF	SQ FT	21,575.000				
**REV 50300300	PROTECTIVE COAT	SQ YD	10,876.000				
50500105	F & E STRUCT STEEL	L SUM	1.000				
50500505	STUD SHEAR CONNECTORS	EACH	21,456.000				
50800205	REINF BARS, EPOXY CTD	POUND	1,076,080.000				
50800515	BAR SPLICERS	EACH	364.000				
51200959	FUR M S PILE 14X0.312	FOOT	17,584.000				
51202100	FUR STL PILE HP14X117	FOOT	3,600.000				
51202305	DRIVING PILES	FOOT	21,184.000				
51203200	TEST PILE MET SHELLS	EACH	10.000				
51204100	TEST PILE ST HP14X117	EACH	2.000				
51204650	PILE SHOES	EACH	512.000				
51500100	NAME PLATES	EACH	4.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64D19

State Job # - C-92-004-13

County Name - WINNEBAGO -
 Code - 201 - -
 District - 2 - -
 Section Number - 3BR & 3BR-1

Project Number
 ACNHPP-0301/076/

Route
 FAP 301

** REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
52000110	PREF JT STRIP SEAL	FOOT	373.000				
52100020	ELAST BEARING ASSY T2	EACH	48.000				
52100520	ANCHOR BOLTS 1	EACH	96.000				
52100540	ANCHOR BOLTS 1 1/2	EACH	48.000				
542A0229	P CUL CL A 1 24	FOOT	49.000				
542A1069	P CUL CL A 2 24	FOOT	366.000				
54244405	FL INLT BX MED 542546	EACH	4.000				
54245405	INLET BOX 542506	EACH	1.000				
54261324	CONC ES 542001 24 1:3	EACH	4.000				
54261424	CONC ES 542001 24 1:4	EACH	1.000				
**REV 58700300	CONCRETE SEALER	SQ FT	7,598.000				
59100100	GEOCOMPOSITE WALL DR	SQ YD	490.000				
60100060	CONC HDWL FOR P DRAIN	EACH	8.000				
60103500	PIPE DRAINS CS 12	FOOT	111.000				
60103700	PIPE DRAINS CS 18	FOOT	235.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64D19

State Job # - C-92-004-13

County Name - WINNEBAGO -
 Code - 201 - -
 District - 2 - -
 Section Number - 3BR & 3BR-1

Project Number
 ACNHPP-0301/076/

Route
 FAP 301

** REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
60107600	PIPE UNDERDRAINS 4	FOOT	1,844.000				
60108100	PIPE UNDERDRAIN 4 SP	FOOT	240.000				
60221100	MAN TA 5 DIA T1F CL	EACH	3.000				
60620000	CONC MED TSB6.24	SQ FT	370.000				
63000003	SPBGR TY A 9FT POSTS	FOOT	2,238.000				
63100045	TRAF BAR TERM T2	EACH	2.000				
63100070	TRAF BAR TERM T5	EACH	5.000				
63100085	TRAF BAR TERM T6	EACH	9.000				
63100167	TR BAR TRM T1 SPL TAN	EACH	4.000				
63200310	GUARDRAIL REMOV	FOOT	4,454.000				
63500105	DELINEATORS	EACH	30.000				
64200116	SHOULDER RUM STRIP 16	FOOT	6,505.000				
66700305	PERM SURV MKRS T2	EACH	2.000				
66900200	NON SPL WASTE DISPOSL	CU YD	7,800.000				
66900450	SPL WASTE PLNS/REPORT	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64D19

State Job # - C-92-004-13

County Name - WINNEBAGO -
 Code - 201 - -
 District - 2 - -
 Section Number - 3BR & 3BR-1

Project Number
 ACNHPP-0301/076/

Route
 FAP 301

** REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
66900530	SOIL DISPOSAL ANALY	EACH	1.000				
67000400	ENGR FIELD OFFICE A	CAL MO	26.000				
67100100	MOBILIZATION	L SUM	1.000				
70100315	TRAF CONT-PROT 701422	EACH	1.000				
70100410	TRAF CONT-PROT 701416	EACH	2.000				
70100420	TRAF CONT-PROT 701411	EACH	5.000				
70100800	TRAF CONT-PROT 701401	L SUM	1.000				
70100820	TRAF CONT-PROT 701451	L SUM	1.000				
70102635	TR CONT & PROT 701701	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	43.000				
70106800	CHANGEABLE MESSAGE SN	CAL MO	8.000				
70200100	NIGHT WORK ZONE LIGHT	L SUM	1.000				
70300100	SHORT TERM PAVT MKING	FOOT	337.000				
70300210	TEMP PVT MK LTR & SYM	SQ FT	78.000				
70300220	TEMP PVT MK LINE 4	FOOT	104,791.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64D19

State Job # - C-92-004-13

County Name - WINNEBAGO -
 Code - 201 - -
 District - 2 - -
 Section Number - 3BR & 3BR-1

Project Number
 ACNHPP-0301/076/

Route
 FAP 301

** REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70300250	TEMP PVT MK LINE 8	FOOT	1,949.000				
70300260	TEMP PVT MK LINE 12	FOOT	364.000				
70300280	TEMP PVT MK LINE 24	FOOT	247.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	24,266.000				
70400100	TEMP CONC BARRIER	FOOT	3,712.500				
70400200	REL TEMP CONC BARRIER	FOOT	3,675.000				
70500100	TEMP SPBGR TY A	FOOT	675.000				
70500665	TEMP TR BAR TERM T6	EACH	3.000				
72000100	SIGN PANEL T1	SQ FT	52.000				
72000200	SIGN PANEL T2	SQ FT	12.000				
72800100	TELES STL SIN SUPPORT	FOOT	140.000				
78009004	MOD URETH PM LINE 4	FOOT	29,875.000				
78009006	MOD URETH PM LINE 6	FOOT	4,013.000				
78009008	MOD URETH PM LINE 8	FOOT	2,077.000				
78009012	MOD URETH PM LINE 12	FOOT	786.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

64D19

State Job # - C-92-004-13

Project Number
 ACNHPP-0301/076/

Route
 FAP 301

County Name - WINNEBAGO - -

Code - 201 - -

District - 2 - -

Section Number - 3BR & 3BR-1

** REVISED: OCTOBER 29, 2013

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
78009024	MOD URETH PM LINE 24	FOOT	29.000				
78100100	RAISED REFL PAVT MKR	EACH	393.000				
78100200	TEMP RAIS REF PVT MKR	EACH	240.000				
78200410	GUARDRAIL MKR TYPE A	EACH	102.000				
78200520	BAR WALL MKR TYPE B	EACH	16.000				
78201000	TERMINAL MARKER - DA	EACH	6.000				
78300100	PAVT MARKING REMOVAL	SQ FT	6,386.000				
78300200	RAISED REF PVT MK REM	EACH	380.000				
89000200	TEMP TR SIG INSTALL	L SUM	1.000				