

60103500	PIPE DRAINS, CORRUGATED STEEL, 12"		REMARKS
FOOT	LOCATION	US 20	
111	944+68.50	945+79.00	EAST CROSSOVER
111	TOTAL		

60103700	PIPE DRAINS, CORRUGATED STEEL, 18"		REMARKS
FOOT	LOCATION	US 20	
113	910+27.00	911+39.80	WEST CROSSOVER
122	912+93.80	914+15.00	WEST CROSSOVER
235	TOTAL		

60107600	PIPE UNDERDRAINS 4"		OFFSET	REMARKS
FOOT	LOCATION	US 20		
257	924+61.00	927+18.00	EB OUTSIDE	
239	924+79.00	927+18.00	EB INSIDE	
218	925+00.00	927+18.00	WB INSIDE	
202	925+16.00	927+18.00	WB OUTSIDE	
144	927+18.00	928+62.00	EB OUTSIDE	
144	927+18.00	928+62.00	EB INSIDE	
144	927+18.00	928+62.00	WB INSIDE	
144	927+18.00	928+62.00	WB OUTSIDE	
88	933+70.00	934+58.00	EB OUTSIDE	
88	933+70.00	934+58.00	EB INSIDE	
88	933+70.00	934+58.00	WB INSIDE	
88	933+70.00	934+58.00	WB OUTSIDE	
1,844	TOTAL			

60108100	PIPE UNDERDRAINS 4" (SPECIAL)		OFFSET	REMARKS
FOOT	LOCATION	US 20		
44	927+18.00		EB OUTSIDE	
36	927+18.00		EB INSIDE	
36	927+18.00		WB INSIDE	
44	927+18.00		WB OUTSIDE	
22	933+70.00		EB OUTSIDE	
18	933+70.00		EB INSIDE	
18	933+70.00		WB INSIDE	
22	933+70.00		WB OUTSIDE	
240	TOTAL			

60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID		OFFSET	REMARKS
EACH	LOCATION	US 20		
1	919+50.00	75.45' RT	ITEM REQUIRES FLAT SLAB TOP	
1	927+50.00	75.83' RT	ITEM REQUIRES FLAT SLAB TOP	
1	934+00.00	75.83' RT	ITEM REQUIRES FLAT SLAB TOP	
3	TOTAL			

60620000	CONCRETE MEDIAN, TYPE SB-6.24		OFFSET	LENGTH	WIDTH	AREA	REMARKS
SO FT	LOCATION	IL 2					
370	243+49.60	244+31.80	RT	82.20	4.5	369.90	STAGE 3
370	TOTAL						

63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS		OFFSET	STAGE	REMARKS
FOOT	LOCATION	US 20 (EB)			
212.5	917+58.10	919+70.60	17' RT	1	EB APPR - LT SIDE
162.5	917+86.70	919+49.20	60' RT	1	EB APPR - RT SIDE
12.5	933+67.86	933+80.36	60' RT	1	EB DEPART - RT SIDE
350.0	925+00.07	928+40.67	17' RT	POST 2	EB BTW STR - LT SIDE
400.0	924+47.24	928+40.67	60' RT	1	EB BTW STR - RT SIDE
12.5	920+29.63	920+42.13	60' LT	2	WB DEPART - RT SIDE
162.5	933+98.71	935+61.21	60' LT	2	WB APPR - RT SIDE
225.0	933+98.71	936+23.71	17' LT	2	WB APPR - LT SIDE
362.5	925+18.20	928+71.52	17' LT	2	WB BTW STR - LT SIDE
337.5	925+40.17	928+71.52	60' LT	2	WB BTW STR - RT SIDE
2,237.5	TOTAL				

63100045	TRAFFIC BARRIER TERMINAL, TYPE 2		OFFSET	STAGE	REMARKS
EACH	LOCATION	US 20			
1	920+14.84	920+29.63	60' LT	2	WB DEPART - RT SIDE
1	933+80.36	933+95.15	60' RT	1	EB DEPART - RT SIDE
2	TOTAL				

63100070	TRAFFIC BARRIER TERMINAL, TYPE 5		OFFSET	STAGE	REMARKS
EACH	LOCATION	US 20			
1	933+53.19	933+67.86	60' RT	1	EB DEPART - RT
1	920+42.13	920+56.80	60' LT	2	WB DEPART - RT
1	924+32.57	924+47.24	60' RT	1	EB BTW STR DEP - RT SIDE
1	928+71.52	928+86.19	17' LT	2	WB BTW STR DEP - LT SIDE
1	928+71.52	928+86.19	60' LT	2	WB BTW STR DEP - RT SIDE
5	TOTAL				

63100085	TRAFFIC BARRIER TERMINAL, TYPE 6		OFFSET	STAGE	REMARKS
EACH	LOCATION	US 20			
1	919+49.20	919+94.72	60' RT	1	EB APPR - RT SIDE
1	919+70.60	920+16.12	17' RT	1	EB APPR - LT SIDE
1	933+53.19	933+98.71	17' LT	2	WB APPR - LT SIDE
1	933+53.19	933+98.71	60' LT	2	WB APPR - RT SIDE
1	928+40.67	928+86.19	60' RT	1	EB BTW STR - RT
1	928+40.67	928+86.19	17' RT	POST 2	EB BTW STR - LT
1	924+54.55	925+00.07	17' RT	POST 2	EB BTW STR - LT
1	924+72.68	925+18.20	17' LT	2	WB BTW STR - LT
1	924+94.65	925+40.17	60' LT	2	WB BTW STR - RT
9	TOTAL				

63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT		OFFSET	STAGE	REMARKS
EACH	LOCATION	US 20			
1	917+36.70	917+86.70	60' RT	1	EB APPR - RT SIDE
1	917+08.10	917+58.10	17' RT	1	EB APPR - LT SIDE
1	936+23.71	936+73.71	17' LT	2	WB APPR - LT SIDE
1	935+61.21	936+11.21	60' LT	2	WB APPR - RT SIDE
4	TOTAL				

63200310	GUARDRAIL REMOVAL		OFFSET	STAGE	REMARKS
FOOT	LOCATION	US 20			
382	916+88.25	920+69.76	49' RT	1	EX GR EB APP - RT
426	916+63.56	920+89.78	16' RT	1	EX GR EB APP - LT
532	924+04.42	929+36.32	56' RT	1	EX GR EB BTW STR - RT
410	925+26.17	929+36.62	14' RT	1	EX GR EB BTW STR - LT
484	924+17.65	929+01.54	57' LT	2	EX GR WB BTW STR - LT
401	923+97.85	927+99.24	13' LT	PRE1B	EX GR WB BTW STR - RT
402	932+97.52	936+99.96	13' LT	2	EX GR WB APP - RT
402	933+02.54	937+04.99	52' LT	2	EX GR WB APP - LT
421	916+69.26	920+89.78	16' LT	2	TEMP GR WB - LT SIDE
96	928+41.10	929+36.62	13' LT	2	TEMP GR WB BTW STR - RT
96	924+54.54	925+50.06	16' RT	POST 2	TEMP GR WB XOVER APP - LT
402	933+24.60	937+27.04	14' RT	POST 2	TEMP GR WB XOVER APP - LT
4,454	TOTAL				

63500105	DELINEATORS		OFFSET	DISTANCE	SPACING	REMARKS
EACH	LOCATION	US 20				
3	911+40.00	920+15.00	WB OUTSIDE	875.0	400	
1	917+36.00	----	EB OUTSIDE	----	----	
1	917+07.00	----	EB INSIDE	----	----	
4	936+10.00	950+10.00	WB OUTSIDE	1,400.0	400	
3	909+00.00	917+37.00	EB OUTSIDE	837.0	400	
4	933+95.00	948+04.00	EB OUTSIDE	1,409.0	400	
1	936+74.00	----	WB INSIDE	----	----	
1	936+12.00	----	WB OUTSIDE	----	----	
4	AT EACH TBT, TY 1 (SP)	----	----	----	----	
1	927+18.00	----	EB OUTSIDE	----	----	AT CONC HEADWALL
1	927+18.00	----	EB INSIDE	----	----	AT CONC HEADWALL
1	927+18.00	----	WB INSIDE	----	----	AT CONC HEADWALL
1	927+18.00	----	WB OUTSIDE	----	----	AT CONC HEADWALL
1	933+70.00	----	EB OUTSIDE	----	----	AT CONC HEADWALL
1	933+70.00	----	EB INSIDE	----	----	AT CONC HEADWALL
1	933+70.00	----	WB INSIDE	----	----	AT CONC HEADWALL
1	933+70.00	----	WB OUTSIDE	----	----	AT CONC HEADWALL
30	TOTAL					

64200116	SHOULDER RUMBLE STRIPS, 16 INCH		OFFSET	REMARKS
FOOT	LOCATION	US 20		
890	911+41.00	920+31.00	WB LEFT	
175	925+96.00	927+71.00	WB LEFT	
1,542	934+68.00	950+10.00	WB LEFT	
476	915+40.00	920+16.00	WB RIGHT	
175	925+96.00	927+71.00	WB RIGHT	
252	934+68.00	937+20.00	WB RIGHT	
455	915+40.00	919+95.00	EB LEFT	
211	925+60.00	927+71.00	EB LEFT	
632	934+68.00	941+00.00	EB LEFT	
150	918+30.00	919+80.00	EB RIGHT	
211	925+60.00	927+71.00	EB RIGHT	
1,336	934+68.00	948+04.00	EB RIGHT	
6,505	TOTAL			

66700305	PERMANENT SURVEY MARKERS, TYPE II		ESTIMATED QUANTITY
EACH	LOCATION	NO	
2	ESTIMATED QUANTITY		

70300100	SHORT TERM PAVEMENT MARKING		OFFSET	REMARKS
FOOT	LOCATION	US 20		
168	918+53.24	935+37.72	WB	PRESTAGE 1B
168	918+53.24	935+37.72	WB	STAGE 1A
337	TOTAL			

70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS		NO	SO FT (EA)	STAGE	REMARKS
SO FT	LOCATION	IL 2				
78	240+58.60	243+58.60	NB TURN LANE 5	15.6	1	LEFT ARROW
78	TOTAL					

70300220	TEMPORARY PAVEMENT MARKING - LINE 4"		OFFSET	STAGE	REMARKS
FOOT	STA	US 20			
100	911+12.20	-45.9	912+11.40	-41.7	WB RIGHT EDGE 100% PRE1 SOLID WHITE
3,864	912+11.40	-41.7	950+75.00	-42.1	WB RIGHT EDGE 100% PRE1 SOLID WHITE
101	950+75.00	-42.1	951+75.00	-43.3	WB RIGHT EDGE 100% PRE1 SOLID WHITE
26	909+60.00	-32.0	910+60.00	-30.6	WB CENTER 25% PRE1 SKIP-DASH WHITE
1,004	910+60.00	-30.6	950+75.00	-31.1	WB CENTER 25% PRE1 SKIP-DASH WHITE
26	950+75.00	-31.1	951+75.00	-32.2	WB CENTER 25% PRE1 SKIP-DASH WHITE
101	939+00.00	44.1	940+00.00	42.0	EB RIGHT EDGE 100% PRE1 SOLID WHITE
901	940+00.00	42.0	949+00.00	41.9	EB RIGHT EDGE 100% PRE1 SOLID WHITE
101	949+00.00	41.9	950+00.00	43.8	EB RIGHT EDGE 100% PRE1 SOLID WHITE
26	939+00.00	32.1	940+00.00	31.0	EB CENTER 25% PRE1 SKIP-DASH WHITE
226	940+00.00	31.0	949+00.00	30.9	EB CENTER 25% PRE1 SKIP-DASH WHITE
26	949+00.00	30.9	950+00.00	32.0	EB CENTER 25% PRE1 SKIP-DASH WHITE
151	906+90.00	-19.9	908+40.00	-23.6	WB LEFT EDGE 100% PRE1A SOLID YELLOW
3,976	908+40.00	-23.6	948+15.00	-24.1	WB LEFT EDGE 100% PRE1A SOLID YELLOW
151	948+15.00	-24.1	949+65.00	-20.4	WB LEFT EDGE 100% PRE1A SOLID YELLOW
38	906+90.00	-32.0	908+40.00	-34.6	WB CENTER 25% PRE1A SKIP-DASH WHITE
994	908+40.00	-34.6	948+15.00	-35.1	WB CENTER 25% PRE1A SKIP-DASH WHITE
38	948+15.00	-35.1	949+65.00	-32.4	WB CENTER 25% PRE1A SKIP-DASH WHITE
3,721	910+94.90	-45.6	948+15.00	-46.1	WB RIGHT EDGE 100% PRE1A SOLID WHITE
151	948+15.00	-46.1	949+65.00	-43.5	WB RIGHT EDGE 100% PRE1A SOLID WHITE
151	906+40.00	20.4	907+90.00	24.4	EB LEFT EDGE 100% PRE1A SOLID YELLOW
811	907+90.00	24.4	916+00.00	24.9	EB LEFT EDGE 100% PRE1A SOLID YELLOW
151	916+00.00	24.9	917+50.00	21.2	EB LEFT EDGE 100% PRE1A SOLID YELLOW
38	906+40.00	32.0	907+90.00	35.4	EB CENTER 25% PRE1A SKIP-DASH WHITE
203	907+90.00	35.4	916+00.00	35.9	EB CENTER 25% PRE1A SKIP-DASH WHITE
38	916+00.00	35.9	917+50.00	32.0	EB CENTER 25% PRE1A SKIP-DASH WHITE
151	906+40.00	44.4	907+90.00	46.4	EB RIGHT EDGE 100% PRE1A SOLID WHITE
151	907+90.00	46.4	909+40.00	46.5	EB RIGHT EDGE 100% PRE1A SOLID WHITE
150	941+00.20	20.7	942+50.00	24.6	EB LEFT EDGE 100% PRE1A SOLID YELLOW
516	942+50.00	24.0	947+65.00	23.9	EB LEFT EDGE 100% PRE1A SOLID YELLOW
151	947+65.00	23.9	949+15.00	20.6	EB LEFT EDGE 100% PRE1A SOLID YELLOW
38	941+00.00	31.6	942+50.00	35.0	EB CENTER 25% PRE1A SKIP-DASH WHITE
129	942+50.00	35.0	947+65.00	34.9	EB CENTER 25% PRE1A SKIP-DASH WHITE
38	947+65.00	34.9	949+15.00	31.9	EB CENTER 25% PRE1A SKIP-DASH WHITE
151	941+00.00	44.1	942+50.00	46.0	EB RIGHT EDGE 100% PRE1A SOLID WHITE
516	942+50.00	46.0	947+65.00	45.9	EB RIGHT EDGE 100% PRE1A SOLID WHITE
151	947+65.00	45.9	949+15.00	43.9	EB RIGHT EDGE 100% PRE1A SOLID WHITE

FILE NAME = D264019-ah-t-Schedule.dgn
 MODEL = Default
 PLOT DRIVER = VBA:IDOT_PDF...11x17.plt